

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	65

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

CLASS A PATCHING, 11"

PATCH AREA

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200561	44200565	44200569	44200571	44213200	Z0075300	44213000
					TYPE I 11.0" (sq_yd)	TYPE II 11.0" (sq_yd)	TYPE III 11.0" (sq_yd)	TYPE IV 11.0" (sq_yd)	SAW CUTS (ft)	TIE BARS (each)	PATCHING REINFORCEMENT (sq_yd)
937+11.00	EB	DL	20	6	0	13.3	0.0	0.0	64.0	10	13.3
935+86.00	EB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
934+53.00	EB	DL	40	6	0	0.0	0.0	26.7	104.0	20	26.7
932+60.00	EB	DL	15	12	0	0.0	20.0	0.0	78.0	0	20.0
930+29.00	EB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
929+85.00	EB	DL	15	6	0	10.0	0.0	0.0	54.0	0	10.0
929+35.00	EB	DL	30	6	0	0.0	20.0	0.0	84.0	15	20.0
928+74.00	EB	DL	20	6	0	13.3	0.0	0.0	64.0	10	13.3
928+34.00	EB	DL	35	12	0	0.0	0.0	46.7	118.0	18	46.7
927+73.00	EB	DL	30	12	0	0.0	0.0	40.0	108.0	15	40.0
927+13.00	EB	DL	30	12	0	0.0	0.0	40.0	108.0	15	40.0
927+10.00	EB	DL	85	6	0	0.0	0.0	56.7	194.0	43	56.7
926+00.00	EB	DL	30	6	0	0.0	20.0	0.0	84.0	15	20.0
928+47.00	EB	DL	10	12	0	13.3	0.0	0.0	68.0	0	13.3
927+85.00	EB	DL	8	6	0	5.3	0.0	0.0	40.0	0	5.3
927+64.00	EB	DL	30	6	0	0.0	20.0	0.0	84.0	15	20.0
926+92.00	EB	DL	40	6	0	0.0	0.0	26.7	104.0	20	26.7
923+85.00	EB	DL	40	12	0	0.0	0.0	53.3	128.0	20	53.3
923+08.00	EB	DL	45	6	0	0.0	0.0	30.0	114.0	23	30.0
922+50.00	EB	DL	30	12	0	0.0	0.0	40.0	108.0	15	40.0
920+10.00	EB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
919+69.00	EB	DL	8	6	0	5.3	0.0	0.0	40.0	0	5.3
919+21.00	EB	DL	80	6	0	0.0	0.0	53.3	184.0	40	53.3
918+08.00	EB	DL	75	6	0	0.0	0.0	50.0	174.0	38	50.0
916+68.00	EB	DL	20	6	0	13.3	0.0	0.0	64.0	10	13.3
915+10.00	EB	DL	50	6	0	0.0	0.0	33.3	124.0	25	33.3
914+81.00	EB	DL	8	6	0	5.3	0.0	0.0	40.0	0	5.3
914+51.00	EB	DL	10	6	0	6.7	0.0	0.0	44.0	0	6.7
912+86.00	EB	DL	15	6	0	10.0	0.0	0.0	54.0	0	10.0
911+96.00	EB	DL	10	6	0	6.7	0.0	0.0	44.0	0	6.7
911+56.00	EB	DL	50	6	0	0.0	0.0	33.3	124.0	25	33.3
910+29.00	EB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
910+00.00	EB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
SUB-TOTAL =					20.0	102.7	80.0	530.0	2778.0	392.0	732.7

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\work\pwwork\cear\lock\jd\0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cear\lock\jd

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY
 Sheet 1 of 6 Sheets
 SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.