

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	67

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

CLASS A PATCHING, 11" (CONT'D)

PATCH AREA

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200561	44200565	44200569	44200571	44213200	Z0075300	44213000
					TYPE I 11.0" (sq_yd)	TYPE II 11.0" (sq_yd)	TYPE III 11.0" (sq_yd)	TYPE IV 11.0" (sq_yd)	SAW CUTS (ft)	TIE BARS (each)	PATCHING REINFORCEMENT (sq_yd)
1388+92.00	EB	DL	20	12	0.0	0.0	0.0	26.7	88.0	10	26.7
1384+88.00	EB	DL	15	6	0.0	10.0	0.0	0.0	54.0	0	10.0
1385+64.00	EB	DL	25	12	0.0	0.0	0.0	33.3	98.0	13	33.3
1381+18.00	EB	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3
1380+34.00	EB	DL	15	6	0.0	10.0	0.0	0.0	54.0	0	10.0
1379+75.00	EB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0
1379+55.00	EB	DL	15	12	0.0	0.0	20.0	0.0	78.0	0	20.0
1379+13.00	EB	DL	15	12	0.0	0.0	20.0	0.0	78.0	0	20.0
1364+38.00	EB	DL	20	6	0.0	13.3	0.0	0.0	64.0	10	13.3
1363+98.00	EB	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0
1362+41.00	EB	DL	20	6	0.0	13.3	0.0	0.0	64.0	10	13.3
1361+63.00	EB	DL	30	12	0.0	0.0	0.0	40.0	108.0	15	40.0
1357+35.00	EB	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0
1357+26.00	EB	DL	40	6	0.0	0.0	0.0	26.7	104.0	20	26.7
1356+11.00	EB	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3
1354+57.00	EB	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3
1350+00.00	EB	DL	50	12	0.0	0.0	0.0	66.7	148.0	25	66.7
1349+78.00	EB	DL	10	12	0.0	13.3	0.0	0.0	68.0	0	13.3
1349+40.00	EB	DL	12	12	0.0	0.0	16.0	0.0	72.0	0	16.0
1326+45.00	EB	DL	8	12	0.0	10.7	0.0	0.0	64.0	0	10.7
1309+70.00	EB	DL	25	6	0.0	0.0	16.7	0.0	74.0	13	16.7
1308+64.00	EB	DL	35	12	0.0	0.0	0.0	46.7	118.0	18	46.7
1308+53.00	EB	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3
1307+13.00	EB	DL	10	12	0.0	13.3	0.0	0.0	68.0	0	13.3
1288+31.00	EB	DL	10	12	0.0	13.3	0.0	0.0	68.0	0	13.3
1249+36.00	EB	DL	10	12	0.0	13.3	0.0	0.0	68.0	0	13.3
1246+10.00	EB	DL	12	6	0.0	8.0	0.0	0.0	48.0	0	8.0
1225+09.00	EB	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0
1218+73.00	EB	DL	15	12	0.0	0.0	20.0	0.0	78.0	0	20.0
1216+03.00	EB	DL	20	6	0.0	13.3	0.0	0.0	64.0	10	13.3
SUB-TOTAL =					8.0	169.3	92.7	240.0	2080.0	144.0	510.0
EAST BOUND TOTAL =					68.0	391.3	318.0	800.0	6630.0	676.0	1577.3

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\cear\lock\p1\dot\cear\lock\jd\0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cealrlockjd

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY
 Sheet 3 of 6 Sheets

SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.