

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	68

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

CLASS A PATCHING, 11" (CONT'D)

PATCH AREA

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200561	44200565	44200569	44200571	44213200	Z0075300	44213000
					TYPE I 11.0" (sq. yd)	TYPE II 11.0" (sq. yd)	TYPE III 11.0" (sq. yd)	TYPE IV 11.0" (sq. yd)	SAW CUTS (ft)	TIE BARS (each)	PATCHING REINFORCEMENT (sq. yd)
1326+50.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1326+05.00	WB	DL	12	12	0	0.0	16.0	0.0	72.0	0	16.0
1324+24.00	WB	DL	25	12	0	0.0	0.0	33.3	98.0	13	33.3
1303+22.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1303+22.00	WB	*PL*	8	12	0	10.7	0.0	0.0	64.0	0.0	10.7
1303+00.00	WB	DL	20	12	0	0.0	0.0	26.7	88.0	10.0	26.7
1301+93.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
1301+54.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
1300+66.00	WB	DL	20	12	0	0.0	0.0	26.7	88.0	10.0	26.7
1300+28.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
1300+00.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1299+67.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1299+67.00	WB	*PL*	6	12	0	8.0	0.0	0.0	60.0	0	8.0
964+69.00	WB	DL	12	6	0	8.0	0.0	0.0	48.0	0	8.0
964+15.00	WB	DL	15	6	0	10.0	0.0	0.0	54.0	0	10.0
963+87.00	WB	DL	10	6	0	6.7	0.0	0.0	44.0	0	6.7
963+34.00	WB	DL	10	6	0	6.7	0.0	0.0	44.0	0	6.7
954+76.00	WB	DL	10	12	0	13.3	0.0	0.0	68.0	0	13.3
952+20.00	WB	DL	30	6	0	0.0	20.0	0.0	84.0	15	20.0
951+89.00	WB	DL	20	6	0	13.3	0.0	0.0	64.0	10	13.3
950+75.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
950+46.00	WB	DL	10	6	0	6.7	0.0	0.0	44.0	0	6.7
948+66.00	WB	DL	10	6	0	6.7	0.0	0.0	44.0	0	6.7
947+45.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
946+15.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
944+65.00	WB	DL	30	6	0	0.0	20.0	0.0	84.0	15	20.0
939+50.00	WB	DL	25	6	0	0.0	16.7	0.0	74.0	13	16.7
937+20.00	WB	DL	40	6	0	0.0	0.0	26.7	104.0	20	26.7
936+13.00	WB	*PL*	6	12	0	8.0	0.0	0.0	60.0	0	8.0
935+00.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
932+00.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
929+68.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
927+90.00	WB	DL	15	6	0	10.0	0.0	0.0	54.0	0	10.0
926+71.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
926+01.00	WB	DL	40	6	0	0.0	0.0	26.7	104.0	20.0	26.7
925+17.00	WB	DL	20	12	0	0.0	0.0	26.7	88.0	10.0	26.7
924+43.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
923+78.00	WB	DL	12	12	0	0.0	16.0	0.0	72.0	0.0	16.0
923+53.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0.0	4.0
923+17.00	WB	DL	8	6	0	5.3	0.0	0.0	40.0	0.0	5.3
922+78.00	WB	DL	12	12	0	0.0	16.0	0.0	72.0	0	16.0
922+55.00	WB	DL	15	6	0	10.0	0.0	0.0	54.0	0	10.0
921+87.00	WB	DL	20	6	0	13.3	0.0	0.0	64.0	10	13.3
921+16.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
916+30.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
915+10.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
913+37.00	WB	DL	30	12	0	0.0	0.0	40.0	108.0	15	40.0
SUB-TOTAL =					36.0	216.7	104.7	206.7	2866.0	161.0	564.0

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\cear\lock\j\d0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = ceair\lockj

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY
 Sheet 4 of 6 Sheets

SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.