

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	69

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

CLASS A PATCHING, 11" (CONT'D)

PATCH AREA

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	44200561	44200565	44200569	44200571	44213200	Z0075300	44213000
					TYPE I 11.0" (sq. yd)	TYPE II 11.0" (sq. yd)	TYPE III 11.0" (sq. yd)	TYPE IV 11.0" (sq. yd)	SAW CUTS (ft)	TIE BARS (each)	PATCHING REINFORCEMENT (sq. yd)
1389+95.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1389+77.00	WB	DL	22	12	0	0.0	0.0	29.3	92.0	11	29.3
1386+65.00	WB	DL	8	12	0	10.7	0.0	0.0	64.0	0	10.7
1382+22.00	WB	DL	20	12	0	0.0	0.0	26.7	88.0	10	26.7
1381+79.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
1381+58.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
1381+02.00	WB	DL	15	6	0	10.0	0.0	0.0	54.0	0.0	10.0
1380+33.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
1380+04.00	WB	DL	10	6	0	6.7	0.0	0.0	44.0	0.0	6.7
1379+65.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
1379+24.00	WB	DL	8	6	0	5.3	0.0	0.0	40.0	0	5.3
1378+91.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1377+62.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1376+93.00	WB	DL	75	6	0	0.0	0.0	50.0	174.0	38	50.0
1376+36.00	WB	DL	100	12	0	0.0	0.0	133.3	248.0	50	133.3
1361+10.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
1346+88.00	WB	DL	10	6	0	6.7	0.0	0.0	44.0	0	6.7
1345+50.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
1339+38.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1338+34.00	WB	DL	20	12	0	0.0	0.0	26.7	88.0	10	26.7
1338+00.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
1337+54.00	WB	DL	20	12	0	0.0	0.0	26.7	88.0	10	26.7
1336+97.00	WB	DL	10	6	0	6.7	0.0	0.0	44.0	0	6.7
1336+43.00	WB	DL	10	6	0	6.7	0.0	0.0	44.0	0	6.7
1335+50.00	WB	DL	30	6	0	0.0	20.0	0.0	84.0	15	20.0
1335+00.00	WB	DL	40	12	0	0.0	0.0	53.3	128.0	20	53.3
1334+68.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1334+44.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
1329+50.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1328+92.00	WB	DL	35	12	0	0.0	0.0	46.7	118.0	18	46.7
SUB-TOTAL =					16.0	132.7	20.0	392.7	2186.0	182.0	561.3

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\cear\lock\p1\dot\cear\lock\jd\0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cealrlockjd

ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES	
F.A.I. ROUTE 72 SECTION (58,74-66)&(74-67&68)RS-1 PIATT COUNTY Sheet 5 of 6 Sheets	
SCALE: NONE	DRAWN BY: CADD
DATE: 12/15/09	CHECKED BY: R.T.B.