

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	70

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

CLASS A PATCHING, 11" (CONT'D)

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA						
					44200561 TYPE I 11.0" (sq. yd)	44200565 TYPE II 11.0" (sq. yd)	44200569 TYPE III 11.0" (sq. yd)	44200571 TYPE IV 11.0" (sq. yd)	44213200 SAW CUTS (ft)	Z0075300 TIE BARS (each)	44213000 PATCHING REINFORCEMENT (sq. yd)
1444+75.00	WB	DL	6	6	4	0.0	0.0	0.0	36.0	0	4.0
1443+00.00	WB	DL	10	6	0	6.7	0.0	0.0	44.0	0.0	6.7
1430+11.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
1430+11.00	WB	*PL*	6	12	0	8.0	0.0	0.0	60.0	0.0	8.0
1421+56.00	WB	DL	10	12	0	13.3	0.0	0.0	68.0	0.0	13.3
1421+00.00	WB	DL	8	12	0	10.7	0.0	0.0	64.0	0.0	10.7
1420+19.00	WB	DL	20	12	0	0.0	0.0	26.7	88.0	10.0	26.7
1419+77.00	WB	DL	12	12	0	0.0	16.0	0.0	72.0	0	16.0
1418+50.00	WB	DL	25	12	0	0.0	0.0	33.3	98.0	13	33.3
1418+04.00	WB	DL	12	12	0	0.0	16.0	0.0	72.0	0	16.0
1417+73.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1417+55.00	WB	DL	8	12	0	10.7	0.0	0.0	64.0	0	10.7
1416+77.00	WB	DL	25	12	0	0.0	0.0	33.3	98.0	13	33.3
1414+27.00	WB	DL	45	12	0	0.0	0.0	60.0	138.0	23	60.0
1413+51.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1409+11.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1408+21.00	WB	DL	25	12	0	0.0	0.0	33.3	98.0	13	33.3
1407+19.00	WB	DL	12	12	0	0.0	16.0	0.0	72.0	0	16.0
1405+34.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1405+13.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1399+20.00	WB	DL	8	12	0	10.7	0.0	0.0	64.0	0	10.7
1397+77.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1393+83.00	WB	DL	10	12	0	13.3	0.0	0.0	68.0	0	13.3
1393+38.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
1392+03.00	WB	DL	20	12	0	0.0	0.0	26.7	88.0	10	26.7
1391+55.00	WB	DL	50	12	0	0.0	0.0	66.7	148.0	25	66.7
1390+56.00	WB	DL	6	12	0	8.0	0.0	0.0	60.0	0	8.0
SUB-TOTAL =					4.0	145.3	48.0	280.0	1980.0	107.0	477.3
WEST BOUND TOTAL =					56.0	494.7	172.7	879.3	7032.0	450.0	1602.7
TOTAL =					124.0	886.0	490.7	1679.3	13662.0	1126.0	3180.0
USE =					124.0	886.0	491.0	1680.0	13662.0	1126.0	3180.0

CLASS A PATCHING, 13"

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA						
					44200573 TYPE I 13.0" (sq. yd)	44200610 TYPE II 13.0" (sq. yd)	TYPE III 13.0" (sq. yd)	TYPE IV 13.0" (sq. yd)	44213200 SAW CUTS (ft)	Z0075300 TIE BARS (each)	44213000 PATCHING REINFORCEMENT (sq. yd)
1209+76.00	EB	DL	6	6	4.0	0.0	0.0	0.0	36	0	4.0
965+37.00	EB	DL	10	12	0.0	13.3	0.0	0.0	68	0	13.3
TOTAL =					4.0	13.3	0.0	0.0	104.0	0	17.3
USE =					4.0	14.0	0.0	0.0	104.0	0	18.0

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
SECTION (58,74-66)&(74-67&68)RS-1
PIATT COUNTY
Sheet 6 of 6 Sheets

SCALE: NONE DRAWN BY: CADD
DATE: 12/15/09 CHECKED BY: R.T.B.

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\cear\lock\p1\dot\cear\lock\j\d0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cear\lockj