

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	PIATT	251	79

*(58,74-66)&(74-67&68)RS-1

SCHEDULES

CLASS B PATCHING, 10" (CONT'D)

PATCH AREA

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	TYPE I 10.0" (sq. yd)	PATCH AREA				Z0017100 DOWEL BARS (each)	44213200 SAW CUTS (ft)	Z0075300 TIE BARS (each)	44213100 PAVEMENT FABRIC (sq. yd)
						4400970 TYPE II 10.0" (sq. yd)	44200974 TYPE III 10.0" (sq. yd)	44200976 TYPE IV 10.0" (sq. yd)					
1325+05.00	EB	DL	15	12	0.0	0.0	20.0	0.0		20.0	66.0	0.0	20.0
1325+05.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1324+57.00	EB	DL	30	12	0.0	0.0	0.0	40.0		30.0	96.0	15.0	40.0
1324+24.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1324+05.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1324+05.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1323+81.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1323+81.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1323+51.00	EB	DL	25	12	0.0	0.0	0.0	33.3		30.0	86.0	13.0	33.3
1322+96.00	EB	DL	12	12	0.0	0.0	16.0	0.0		20.0	60.0	0.0	16.0
1321+56.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1321+31.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1319+97.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1319+78.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1318+58.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1318+44.00	EB	DL	15	12	0.0	0.0	20.0	0.0		20.0	66.0	0.0	20.0
1318+16.00	EB	DL	15	12	0.0	0.0	20.0	0.0		20.0	66.0	0.0	20.0
1317+59.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1316+77.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1316+77.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1316+55.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1312+91.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1312+38.00	EB	DL	30	12	0.0	0.0	0.0	40.0		30.0	96.0	15.0	40.0
1310+55.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1310+55.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1310+40.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1310+00.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1310+00.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1309+80.00	EB	DL	30	12	0.0	0.0	0.0	40.0		30.0	96.0	15.0	40.0
1309+55.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1309+41.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1309+05.00	EB	DL	12	12	0.0	0.0	16.0	0.0		20.0	60.0	0.0	16.0
1309+05.00	EB	*PL*	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1308+75.00	EB	DL	8	12	0.0	10.7	0.0	0.0		20.0	52.0	0.0	0.0
1308+57.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1308+30.00	EB	DL	6	12	0.0	8.0	0.0	0.0		20.0	48.0	0.0	0.0
1307+70.00	EB	DL	40	12	0.0	0.0	0.0	53.3		40.0	116.0	20.0	53.3
SUB-TOTAL =					0.0	218.7	92.0	206.7		800.0	2108.0	78.0	298.7

PLOT DATE = 2/8/2010
 FILE NAME = c:\pwwork\cear\lock\p1\dot\cear\lock\j\d0109678\TEXT2899.DGN
 PLOT SCALE = 105.8824 / IN.
 USER NAME = cear\lock\j

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

F.A.I. ROUTE 72
 SECTION (58,74-66)&(74-67&68)RS-1
 PIATT COUNTY
Sheet 9 of 24 Sheets

SCALE: NONE DRAWN BY: CADD
 DATE: 12/15/09 CHECKED BY: R.T.B.