

PAVING - CONTINUED

LOCATION	PAVEMENT WIDTH (FOOT)	LEFT SHOULDER WIDTH (FOOT)	RIGHT SHOULDER WIDTH (FOOT)	PAVT AREA	SHLD AREA	BIT MATL PR CT (TON)	AGG PR CT (TON)	HMA BIND CSE (TON)	HMA SURF CSE MIX E N105 (TON)	HMA SURF CSE MIX C N50 (TON)
FAU 8136 (STAUNTON ROAD)										
STA 105+66.00 TO STA 122+25.00 BK	24			4,424.00		1.68	8.85			371.62
STA 21+09.83 AH TO STA 24+59.23	24			931.73		0.35	1.86			78.27
STA 24+59.23 TO STA 25+12.42	24	4 TO 8	4 TO 10	141.84	76.83	0.08	0.44			18.37
STA 25+12.42 TO STA 25+52.01	24	8 TO 10	10	105.57	83.58	0.07	0.38			15.89
STA 25+52.01 TO STA 29+37.84	24 TO 29	10	10	1,136.06	857.40	0.76	3.99			167.45
STA 29+37.84 TO STA 34+50.00	29	10	10	1,650.29	1,138.13	1.06	5.58			234.23
STA 34+50.00 TO STA 34+78.15	29 TO 46	10		117.29	31.28	0.06	0.30			12.48
STA 34+78.15 TO STA 35+41.43	46	10		323.43		0.12	0.65			27.17
STA 35+41.43 TO STA 35+80.78	46 TO 29	10		163.96	43.72	0.08	0.42			17.45
STA 35+80.78 TO STA 40+83.10	29	10	10	1,618.59	1,116.27	1.04	5.47			229.73
STA 40+83.10 TO STA 41+27.12	29		10	141.84	48.91	0.07	0.38			16.02
STA 41+27.12 TO STA 41+59.80	29			105.30		0.04	0.21			8.85
STA 41+59.80 TO STA 42+08.23	29 TO 40			185.65		0.07	0.37			15.59
STA 42+08.23 TO STA 42+35.78	46			140.81		0.05	0.28			11.83
STA 42+35.78 TO STA 42+38.51	46	10		13.95	3.03	0.01	0.03			1.43
STA 42+38.51 TO STA 42+98.20	46	10	10	305.08	132.64	0.17	0.88			36.77
STA 42+98.20 TO STA 43+54.27	40 TO 41	10	10	252.32	124.60	0.14	0.75			31.66
STA 43+54.27 TO STA 45+65.00	41	10	10	959.99	468.29	0.54	2.86			119.98
STA 45+65.00 TO STA 48+67.00	41 TO 29	10	10	1,174.44	671.11	0.70	3.69			155.03
STA 48+67.00 TO STA 48+74.00	29	10	10	22.56	15.56	0.01	0.08			3.20
STA 51+26.00 TO STA 51+36.36	29	10	10	33.38	23.02	0.02	0.11			4.74
STA 51+36.36 TO STA 54+35.00	29 TO 41	10	10	1,161.38	663.64	0.69	3.65			153.30
STA 54+35.00 TO STA 56+54.40	41	10	10	999.49	487.56	0.57	2.97			124.91
STA 56+54.40 TO STA 57+06.11	41 TO 40	10	10	232.70	114.91	0.13	0.70			29.20
STA 57+06.11 TO STA 57+60.31	46	10	10	277.02	120.44	0.15	0.79			33.39
STA 57+60.31 TO STA 57+72.69	46		10	63.28	13.76	0.03	0.15			6.47
STA 57+72.69 TO STA 57+96.92	46			123.84		0.05	0.25			10.40
STA 57+96.92 TO STA 58+44.68	40 TO 29			183.08		0.07	0.37			15.38
STA 58+44.68 TO STA 58+81.00	29			117.03		0.04	0.23			9.83
STA 58+81.00 TO STA 59+47.15	29	10		213.15	73.50	0.11	0.57			24.08
STA 59+47.15 TO STA 64+56.75	29	10	10	1,642.04	1,132.44	1.05	5.55			233.06
STA 64+56.75 TO STA 65+31.75	29		10	241.67	83.33	0.12	0.65			27.30
STA 65+31.75 TO STA 65+39.24	29			24.13		0.01	0.05			2.03
STA 65+39.24 TO STA 65+66.86	29 TO 43			110.48		0.04	0.22			9.28
STA 65+66.86 TO STA 66+31.62	46			331.00		0.13	0.66			27.80
STA 66+31.62 TO STA 66+59.24	43 TO 29			110.48		0.04	0.22			9.28
STA 66+59.24 TO STA 66+71.02	29			37.96		0.01	0.08			3.19
STA 66+71.02 TO STA 67+14.71	29		10	140.78	48.54	0.07	0.38			15.90
STA 67+14.71 TO STA 69+55.51	29 TO 32	10	10	816.04	535.11	0.51	2.70			113.50
STA 69+55.51 TO STA 71+90.37	29	10	10	756.77	521.91	0.49	2.56			107.41
STA 71+90.37 TO STA 75+98.18	31 TO 24	10	10	1,246.09	906.24	0.82	4.30			180.80
STA 75+98.18 TO STA 76+00.00	24	10	10	4.85	4.04	0.00	0.02			0.75
STA 76+00.00 TO STA 76+85.00	24 TO 21	10	10	212.50	188.89	0.15	0.80			33.72
ENTRANCES, SIDE ROADS						0.70	3.50			
TOTAL						90.1	474	19,314*	10,529*	11,543

HOT-MIX ASPHALT SHOULDERS 8"

LOCATION	LEFT SHOULDER WIDTH (FT)	RIGHT SHOULDER WIDTH (FT)	HMA SHLDS 8" (SQ YD)	EXCAV & GR EX SHLDS (UNIT)
I-55 MAINLINE				
SOUTHBOUND				
STA 701+32.00 TO STA 705+61.00	4.00		190.67	4.30
STA 240+85.00 TO STA 245+14.00	4.00		190.67	4.30
NORTHBOUND				
STA 705+91.00 TO STA 710+20.00		4.00	190.67	4.30
STA 245+44.00 TO STA 249+73.00		4.00	190.67	4.30
FAU 8136 (STAUNTON ROAD)				
STA 105+66.00 TO STA 122+25.00 BK	4.00	4.00	1,474.67	33.20
STA 21+09.83 AH TO STA 24+59.03	4.00	4.00	310.40	7.00
RAMP INTERSECTION IMPROVEMENTS			294.27	
TOTAL			2,842	57

\* - TO BE PLACED WITH THE MATERIAL TRANSFER DEVICE

FILE NAME =	USER NAME = coxte	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\PIWID01\COXTE\dms25312\0672A00-schedule.dgn		DRAWN -	REVISED -		55	59RS-2, BR	MACOUPIN	100	18				
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 72A60								
PLOT DATE = Mar-23-2010 03:21:24PM		DATE -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			