

SUMMARY OF QUANTITIES			1001 STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	SFTY-2A
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	18105	18105	
40600300	AGGREGATE (PRIME COAT)	TON	362	362	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	7384	7384	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1275	1275	
40600990	TEMPORARY RAMP	SQ YD	640	640	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	78		78
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	14849	14849	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	538	538	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	76517	76517	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	15042	15042	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	85215	85215	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	914		914
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	1634	1634	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	185	185	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	168	168	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2549	2549	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	914		914
64200105	SHOULDER RUMBLE STRIP	FOOT	76607	76607	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	

SUMMARY OF QUANTITIES (Cont'd)			1001 STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	SFTY-2A
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	21912	21912	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	119677	119677	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	13040	13040	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2037	2037	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2434	2434	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	119677	119677	
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	13040	13040	
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2037	2037	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1597	1597	
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	68		68
78200300	PRISMATIC CURB REFLECTOR	EACH	333	333	
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	196		196
X4421000	PARTIAL DEPTH PATCHING	TON	50	50	
X4422000	PARTIAL DEPTH REMOVAL (VARIABLE DEPTH)	SQ YD	400	400	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1		1
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	30		30
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	46		46
Z0024478	FLEXIBLE DELINEATORS	EACH	50	50	
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOUR</del>	<del>500</del>	<del>500</del>	

04080  
\*Specialty Items  
• (51-24)RS-3 & (51-24-2)RS-1

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -					327		LAWRENCE	49	3	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -					SCALE: NA			SHEET NO. 1 OF 1 SHEETS STA. TO STA.		
	PLOT DATE = #DATE#	DATE -	REVISED -								ILLINOIS FED. AID PROJECT		
											CONTRACT NO. 74390		