

RAMPS PAVEMENT MARKING SCHEDULE (Cont' d)		LENGTH	THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 6" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 8" WHITE	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 8"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	PRISMATIC CURB REFLECTOR
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH
LAKE LAWRENCE INTERCHANGE													
RAMP E													
5+95.04 TO 6+86.89	91.9	0.0	91.9	0.0	0.0	91.9	0.0	0.0	0.0	0.0	0.0	2.0	0.0
6+86.89 TO 7+80.00	93.1	0.0	93.1	0.0	93.1	93.1	0.0	93.1	0.0	0.0	0.0	2.0	0.0
7+80.00 TO 10+00.00	220.0	0.0	220.0	0.0	0.0	220.0	0.0	0.0	0.0	0.0	0.0	12.0	0.0
10+00.00 TO 10+82.38	82.4	0.0	82.4	0.0	0.0	82.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0
RAMP F													
66+22.74 TO 71+51.36	528.6	528.6	0.0	0.0	0.0	528.6	0.0	0.0	0.0	0.0	0.0	0.0	26.0
71+51.36 TO 72+83.57	132.2	132.2	0.0	0.0	0.0	132.2	0.0	0.0	0.0	0.0	0.0	0.0	7.0
73+14.35 TO 74+41.82	127.5	127.5	0.0	0.0	0.0	127.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0
RAMP G													
72+24.65 TO 74+41.82	217.2	217.2	0.0	0.0	0.0	217.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0
IL 33/C. H. 3													
74+41.82 TO 74+69.37	27.6	55.1	34.4	0.0	0.0	89.5	0.0	0.0	12.0	1.3	0.0	0.0	0.0
74+69.37 TO 75+16.47	47.1	47.1	58.9	0.0	0.0	106.0	0.0	0.0	12.0	1.3	0.0	0.0	0.0
75+16.47 TO 75+96.00	79.5	0.0	99.4	0.0	0.0	99.4	0.0	0.0	24.0	2.7	0.0	0.0	0.0
75+96.00 TO 76+42.77	46.8	46.8	58.5	0.0	0.0	105.2	0.0	0.0	12.0	1.3	0.0	0.0	0.0
76+42.77 TO 77+34.50	91.7	91.7	114.7	0.0	0.0	206.4	0.0	0.0	24.0	2.7	0.0	0.0	0.0
SHEET TOTALS		1246.2	853.2	0.0	93.1	2099.4	0.0	93.1	84.0	9.3	16.0	33.0	
GRAND TOTALS		15223.0	5042.0	130.0	765.0	20265.0	130.0	765.0	252.0	28.0	307.0	333.0	