

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	25	25
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20	20
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16	16
40600300	AGGREGATE (PRIME COAT)	TON	80	80
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600535	LEVELING BINDER (HAND METHOD), N70	TON	30	30
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	380	380
40600990	TEMPORARY RAMP	SQ YD	475	475
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,050	2,050
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	300	300
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	19,900	19,900
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	70	70
44000600	SIDEWALK REMOVAL	SQ FT	300	300
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	700	700
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	600	600
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	420	420
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	130	130
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,200	1,200
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5	5
60262700	INLETS TO BE RECONSTRUCTED	EACH	5	5
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	8
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6

• DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,500	1,500
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	450	450
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24,900	24,900
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,000	3,000
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	150	150
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	120	120
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	870	870
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,100	4,100
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8,300	8,300
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,000	1,000
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	50	50
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	40	40
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	290	290
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	380	380
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	365	365
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	800	800
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,080	1,080
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	30	30

FILE NAME = N:\PROJECTS\3368-08\Design\ProposedPlan\3368-08-03-Quantities.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60659  
Tel: 773.775.4009 Fax: 773.775.4014

USER NAME = mready	DESIGNED MWR	REVISED -
	DRAWN MWR	REVISED -
PLOT SCALE = 1:8000 / 1 IN.	CHECKED WBL	REVISED -
PLOT DATE = 3/30/2009	DATE 3/31/2009	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>IL 31 / IL 56</b>	
<b>INTERSTATE 88 TO IL 56 (STATE STREET)</b>	
<b>SUMMARY OF QUANTITIES</b>	
SCALE:	SHEET NO. 3 OF 21 SHEETS STA. TO STA.

F.A.P. RTE. 365	SECTION A-R-RS-4	COUNTY KANE	TOTAL SHEETS 21	SHEET NO. 3
CONTRACT NO. 60F33				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				