

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18
40600300	AGGREGATE (PRIME COAT)	TON	118	118
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	112	112
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	498	498
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	98	98
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,902	2,902
42001300	PROTECTIVE COAT	SQ YD	369	369
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	150	150
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	5,748	5,748
44000600	SIDEWALK REMOVAL	SQ FT	150	150
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,320	2,320
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SQ YD	700	700
44003100	MEDIAN REMOVAL	SQ FT	1,511	1,511
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	13,595	13,595
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	475	475
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	130	130
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	100	100
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,196	1,196
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7	7
60404950	FRAMES AND GRATES, TYPE 24	EACH	2	2
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	128	128
60624600	CORRUGATED MEDIAN	SQ FT	1,600	1,600

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,190	5,190
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13,794	13,794
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	381	381
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	97	97
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	182	182
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	102	102
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	577	577
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13,794	13,794
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	381	381
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	97	97
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	182	182
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	102	102
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	678	678
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	678	678
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	364	364
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	150	150
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,019	1,019
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	5,360	5,360
X4421000	PARTIAL DEPTH PATCHING	TON	215	215
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	1,282	1,282
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	43	43

* SPECIALTY ITEM

FILE NAME = D160F41-shr-S00.dgn
PLOT DATE = 3/20/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	S.J.P.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	S.J.P.	REVISED -	
DATE -	MARCH 20, 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. 83 (OAKTON STREET) IL. 72 TO ELMHURST ROAD

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
344	0405 RS-8	COOK	24	3
CONTRACT NO. 60F41			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	