

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23	23
40600300	AGGREGATE (PRIME COAT)	TON	115	115
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	480	480
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	169	169
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,421	2,421
42001300	PROTECTIVE COAT	SQ YD	505	505
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	28,820	28,820
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,047	2,047
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	860	860
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	320	320
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	300	300
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	240	240
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,976	2,976
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	15	15
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	44	44
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
67100100	MOBILIZATION	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11,000	11,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	817	817
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15,152	15,152
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,200	2,200
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	848	848
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	176	176
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,500	1,500
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	817	817
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15,152	15,152
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,200	2,200
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	848	848
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	176	176
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	537	537
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	845	845
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	80	80
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,210	1,210
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	96	96

* SPECIALTY ITEM

FILE NAME = 0168093-eh-t-500.dgn
PLOT DATE = 4/15/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	M.P.	REVISED -	
DATE -	APRIL 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
HARLEM AVENUE

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2766	3839 RS-4	COOK	17	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60693	