

## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

Γ	ILE NAME =	USER NAME = hemdenah		REVISED - R. MIRS 09-15-97		ARTERIAL	ROAD	F.A.P. SECTION	COUNTY TOTAL SHEET SHEETS NO.
·	:\pw_work\PWIDOT\HAMDANAH\dØ137Ø88\Dis	tStd.dgn		REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS	INFORMATI		400 124 RS-7	LAKE 17 17
		PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -T. RAMMACHER 02-02-99				TC-22	CONTRACT NO. 60H07
L		PLOT DATE = 4/20/2009	DATE -	REVISED - C. JUCIUS 01-31-07		SCALE: NONE SHEET NO. 1 OF 1 SHEET	S STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FE	ED. AID PROJECT