

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
20200100	EARTH EXCAVATION	CU YD	300	300
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	40	40
35800200	AGGREGATE BASE REPAIR	TON	390	390
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	30	30
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	8	8
40600300	AGGREGATE (PRIME COAT)	TON	40	40
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2
40600535	LEVELING BINDER (HAND METHOD), N70	TON	5	5
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	180	180
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	390	390
40600990	TEMPORARY RAMP	SQ YD	280	280
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	4	4
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2,600	2,600
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	10	10
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	50	50
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	9,800	9,800
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50	50
44000600	SIDEWALK REMOVAL	SQ FT	50	50
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,110	2,110
44003100	MEDIAN REMOVAL	SQ FT	310	310
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	3,020	3,020
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,890	1,890
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	500	500
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	630	630
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	700	700
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	200	200
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	550	550
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,400	1,400
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	75	75

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	70	70
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	19	19
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	310	310
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,170	4,170
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11,500	11,500
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,500	1,500
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	300	300
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	300	300
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,900	1,900
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	50	50
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,100	7,100
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	500	500
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100	100
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	190	190
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,500	1,500
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,400	1,400
X4400100	PORTLAND CEMENT CONCRETE REMOVAL (VARIABLE DEPTH)	SQ YD	3,540	3,540
X4421000	PARTIAL DEPTH PATCHING	TON	350	350
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	1,980	1,980
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	95	95
Z0055400	RUMBLE STRIP	FOOT	600	600

FILE NAME = m:\pro\3368\3368_14\design\proposals\3368_14_03-Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60658
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = alou	DESIGNED MBT	REVISED -
PLOT SCALE = 1:2000' / IN.	DRAWN DKD	REVISED -
PLOT DATE = 4/28/2009	CHECKED WBL	REVISED -
	DATE 4/20/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SHERIDAN ROAD /SOUTH BOULEVARD
JUNEWAY TERRACE TO SOUTH BLVD & SHERIDAN RD TO CHICAGO AVE
SUMMARY OF QUANTITIES

SCALE: SHEET NO. 3 OF 19 SHEETS STA. TO STA.

F.A.J. RTE. 1332/2865	SECTION 2009-049 RS	COUNTY COOK	TOTAL SHEETS 19	SHEET NO. 3
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT			CONTRACT NO. 60H09	