

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	36	36
40600300	AGGREGATE (PRIME COAT)	TON	202	202
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	850	850
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	187	187
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	472	472
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5,332	5,332
42001300	PROTECTIVE COAT	SQ YD	2,278	2,278
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	100	100
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	5,611	5,611
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	2,022	2,022
44000600	SIDEWALK REMOVAL	SQ FT	100	100
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	6,650	6,650
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	720	720
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	600	600
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	300	300
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,624	2,624
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	45	45
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7	7
60404300	FRAMES AND GRATES, TYPE 3	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13,000	13,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	655	655
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18,977	18,977
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,143	2,143
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,224	1,224
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	344	344
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,300	2,300
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	655	655
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18,977	18,977
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,143	2,143
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,224	1,224
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	344	344
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	916	916
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	916	916
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,690	1,690
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	50	50
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,894	1,894
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	10,917	10,917
X4421000	PARTIAL DEPTH PATCHING	TON	96	96
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	570	570
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	86	86
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

* SPECIALTY ITEM

FILE NAME = D:\60H13-aht-S00.dgn
PLOT DATE = 4/15/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L.	REVISED -	
DRAWN -	B.K.	REVISED -	
CHECKED -	M.P.	REVISED -	
DATE -	APRIL 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
WILLOW ROAD (LANDWEHR ROAD TO UNION PACIFIC R.R.)

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	1518 RS-3	COOK	18	3
CONTRACT NO. 60H13				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				