

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	35	35	
40600300	AGGREGATE (PRIME COAT)	TON	195	195	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	50	50	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	169	169	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	967	967	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5,076	5,076	
42001300	PROTECTIVE COAT	SQ YD	693	693	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,020	1,020	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,240	1,240	
44000600	SIDEWALK REMOVAL	SQ FT	1,020	1,020	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,740	1,740	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	500	500	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	340	340	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	280	280	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	11	11	
55039700	STORM SEWERS TO BE CLEANED	FOOT	3,660	3,660	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	

SUMMARY OF QUANTITIES				100% STATE		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16,000	16,000			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,444	1,444			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11,604	11,604			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5,298	5,298			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	668	668			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	769	769			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	657	657			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,200	3,200			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,444	1,444			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,604	11,604			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,298	5,298			
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	668	668			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	769	769			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	657	657			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	795	795			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	795	795			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4,670	4,670			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52			
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,914	1,914			
X4421000	PARTIAL DEPTH PATCHING	TON	56	56			
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	333	333			
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	7,478	7,478			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	105	105			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			

* SPECIALTY ITEM