

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	115	115
40600300	AGGREGATE (PRIME COAT)	TON	574	574
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	23	23
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,404	2,404
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2,508	2,508
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	18,748	18,748
42001300	PROTECTIVE COAT	SQ YD	89	89
44000159	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/2"	SQ YD	191,303	191,303
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	400	400
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	11,193	11,193
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	600	600
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	800	800
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	500	500
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	8,800	8,800
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,000	1,000
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	20	20
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,924	1,924
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,278	2,278
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	85,327	85,327
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8,223	8,223
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	903	903
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	558	558
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	642	642
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,278	2,278
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	85,327	85,327
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8,223	8,223

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	903	903
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	558	558
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	676	676
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	609	609
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,580	1,580
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	8,035	8,035
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	65	65

* SPECIALTY ITEM

PLOT DATE = 4/20/2009
 FILE NAME = K:\1122514\Frand Road South\Cad\Sheets\FrandSouth_S01.dgn
 USER NAME = jsw
 MODEL = Default



200 West Front Street
 Wheaton, IL 60187

DESIGNED - BLB
 DRAWN - JMT
 CHECKED - MAK
 DATE - 4/13/2009

REVISED - ---
 REVISED - ---
 REVISED - ---
 REVISED - ---

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

US RTE 12 (RAND RD)

SUMMARY OF QUANTITIES

F.A.P. RTE. 334	SECTION SY-1-RS-4	COUNTY LAKE	TOTAL SHEETS 28	SHEET NO. 3
CONTRACT NO. 60H24				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SCALE: SHEET NO. 3 OF 28 SHEETS STA. _____ TO STA. _____