

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)
UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = gaglianobt	DESIGNED -	REVISED -	R. MIRS 09-15-97			ARTERIAL ROAD	F.A.	μ. SECTION	COUNTY	TOTAL SHEET
W:\diststd\22x34\tc22.dgn		DRAWN -	REVISED -	R. MIRS 12-11-97	STATE OF ILLINOIS			390	02 16-Z-1-RS-1	KANE	18 17
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED -T.	RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION	INFORMATION SIGN			TC-22	CONTRACT	NO. 60H30
	PLOT DATE = 1/4/2008	DATE -	REVISED ~	C. JUCIUS 01-31-07		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED		ID PROJECT	