## INDEX OF SHEETS

SHEET NO.	<u>DESCRIPTION</u>
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDANDS, GENERAL NOTES AND MIX SCHEDULE
3	SUMMARY OF QUANTITIES
4	EXISTING AND PROPOSED TYPICAL CROSS SECTIONS
5-10	ROADWAY AND PAVEMENT MARKING PLANS
11-12	DETECTOR LOOP PLANS
13	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING
14	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT
15	CURB OR CURB AND GUTTER REMOVAL AND REPACEMENT
16	BUTT JOINT AND HMA TAPER DETAILS
17	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
18	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
19	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
20	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
21	ARTERIAL ROAD INFORMATION SIGN
22	DISTRICT ONE DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING
	STATE STANDARDS

## STATE STANDARDS

STANDARD I	NO. DESCRIPTION
000001- <b>05</b>	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
442201 <b>-03</b>	CLASS C AND CLASS D PATCHES
701301 <b>- 03</b>	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311 <b>- 03</b>	LANE CLOSURE, 2L, 2W, MOVING DAY OPERATIONS
701501 <b>-05</b>	URBAN LANE CLOSURE, 2'L, 2W, UNDIVIDED
701701 <b>- 06</b>	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701901 <b>-01</b>	TRAFFIC CONTROL DEVICES
886001 <b>-01</b>	DETECTOR LOOP INSTALLATIONS
886006 <b>-01</b>	TYPICAL LAYOUT FOR DETECTION LOOPS

## PLAN NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC. TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES WITHIN THE VILLAGE OF WINFIELD AND THE CITY OF WHEATON.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OF FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT). IN ACCORDANCE WITH THE "BUTT JOINT AND HOT-MIX ASPHALT TAPER DETAILS" SHEETS INCLUDED ON THE PLANS. UNLESS OTHERWISE SPECIFIED.

THE RESIDENT ENGINEER SHALL CONTACT MS. PATRICE HARRIS AREA TRAFFIC FIELD ENGINEER AT (708) 597-9800 A MINIMUM OF 2 WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKING.

10 FEET (3 METERS) TRANSITION SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER TO EXISTING CURB AND GUTTERS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITION SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OR WORK SPECIFIED.

WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED I'2 INCHES (40MM) WHERE THE SPEED LIMIT IS 45 MPH (80 KM/H) OR LESS AND 1 INCH (25MM) WHERE THE SPEED LIMIT IS GREATER THAN 45 MPH (80 KM/H). WITH WRITTEN APPROVAL FROM THE ENGINEER, A MAXIMUM GRADE DIFFERNTIAL OF 3 INCHES (75MM) MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM 1:3 (V:H).

	USER NAME = \$USER\$	DESIGNED - MJY	REVISED -
		DRAWN - ZDA	REVISED -
CONSULTING ENGINEERS 1979 N. MILL ST. SUITE 210	PLOT SCALE = \$SCALE\$	CHECKED - MJY	REVISED -
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100	PLOT DATE = \$DATE\$	DATE - 04/22/2009	REVISED -

STATE	OF	ILLINOIS
DEPARTMENT	OF	TRANSPORTATION

	INDEX O	F SHEETS, STATE STANDA	RDS, AND GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
	ILL 38 ROOSEVELT RD.		347	(G & 2) Y-RS-7	DUPAGE	22	2	
				C-91-601-09		CONTRACT NO. 60H31		
į	SCALE: NONE	SHEET NO. 2 OF 22 SHEETS	STA. 13+00 TO STA. 150+00	FED. RO	OAD DIST, NO. ILLINOIS FED. A	ID PROJECT		