

ROCK FILL WITH GEOTECHNICIAL FABRIC

FOR GROUND STABILIZATION.
PAID FOR BY RESPECTIVE PAY ITEMS

## NOTES:

- 1. STRUCTURE EXCAVATION AND BACKFILL SHALL BE IN ACCORDANCE WITH SECTION 502 AND PAYMENT FOR STRUCTURE EXCAVATION SHALL BE IN ACCORDANCE TO ARTICLE 502.13 OF THE STANDARD SPECIFICATIONS.
- 2. POROUS GRANULAR EMBANKMENT SHALL BE PLACED IN ACCORDANCE WITH ARTICLE 540.06 OF THE STANDARD SPECIFICATIONS AND SHALL BE INCLUDED IN THE COST OF THE PRECAST BOX CULVERT PAY ITEM AND THE PRECAST BOX CULVERT END SECTION PAY ITEM.
- 3. WRAP POROUS GRANULAR MATERIAL AND ROCK FILL IN FABRIC. THE FABRIC SHALL BE ACCORDING TO THE REQUIREMENTS OF THE APPLICABLE PORTIONS OF SECTION 1080 AND SECTION 282 WITH 6 OR 8 OZ/SQ YD MATERIAL ALLOWED.

LOCATION	w	н	t	L	ROCK FILL	GEOTECH. FABRIC
	FOOT	FOOT	INCHES	FOOT	TON	SQ. YD.
LT. STA. 490+33.16*	4	5	5	24.6	16.5	43.3
RT. STA. 490+33.16*	4	5	5	17.5	15.8	41.3
LT. STA. 497+77*	3	3	4	19.4	11.3	31.6
RT. STA. 497+77*	3	3	4	21.3	15.9	44.5
LT. STA. 28+73*	3	3	4	17.6	10.3	28.7
RT. STA. 28+73	3	3	4	17.4	13.6	38.1

\*SEE DROP STRUCTURE DETAILS

DRAWING NOT TO SCALE FILE NAME = USER NAME ≈ ghidinaam DESIGNED -REVISED SECTION COUNTY DETAIL OF EXCAVATION AND BACKFILL FOR ropplanshts.dgn DRAWN STATE OF ILLINOIS REVISED -FULTON 315 PRECAST BOX CULVERT EXTENSIONS PLOT SCALE = 100.0000 ' / IN. CHECKED -REVISED **DEPARTMENT OF TRANSPORTATION** CONTRACT NO. 68330 PLOT DATE = 3/25/2009 DATE REVISED SCALE: SHEET NO. OF SHEETS STA,