

SUMMARY OF QUANTITIES

FAP 669

FAP 693

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				IL 29 100% State	IL 29 100% State	IL 9 100% State	IL 9 100% State
				ROADWAY 1000 URBAN	TRAFFIC SIGNALS Y031-1F URBAN	ROADWAY 1000 URBAN	TRAFFIC SIGNALS Y031-1F URBAN
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	55.2	33		22.2	
40600300	AGGREGATE (PRIME COAT)	TON	276.6	165		111.6	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4			4	
40600895	CONSTRUCTING TEST STRIP	EACH	1	0.5		0.5	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2127	1874		253	
40600990	TEMPORARY RAMP	SQ YD	1295	644		651	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1585	1585			
40603365	HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	13458	8771		4687	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	384	384			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	55802			55802	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	80846	80846			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	10	10			
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	251			251	
44201389	CLASS C PATCHES, TYPE II, 13 INCH	SQ YD	2090	2090			
44201394	CLASS C PATCHES, TYPE III, 13 INCH	SQ YD	387	387			
44201396	CLASS C PATCHES, TYPE IV, 13 INCH	SQ YD	1544	1544			
44201415	CLASS C PATCHES, TYPE II, 15 INCH	SQ YD	899			899	
44201421	CLASS C PATCHES, TYPE IV, 15 INCH	SQ YD	80			80	
44213200	SAW CUTS	FOOT	1680			1680	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	63	63			
60260100	INLETS TO BE ADJUSTED	EACH	1	1			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	75	75			

* SPECIALTY ITEMS