

F.A.E. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	.	TAZEWELL	54	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*10,15RS-5, 9RS, 13RS-2, 15RS-4				
CONTRACT NO. 68892				

Temporary and Permanent Pavement Markings											
Sta. to Sta. Margaret St.	CL Skip-Dash Pref 6" W	Epoxy						Ltrs&Syms sq ft	RPM each	RPM Rem each	
		8"W	12"W	24"W	4" Y	4"Y skip	12"Y				
113+40	118+19	240							12	12	
118+19	122+98	240	246		40				12	12	
122+98	127+77	240	423		50		31.2		12	12	
127+77	132+56	240	158		40				12	12	
132+56	132+96	20									
132+96	135+91	74	230	50							
135+91	139+62	93	278		45		31.2				
12+83	14+34	38	134	20							
14+34	14+97	16	92		42						
15+50	16+20	35	285			140			5	5	
2+10	5+03	147				586	147	156	22	22	
5+03	9+82	240				958	240	78	36	36	
9+82	14+61	240	440		82	958	240	78	36	36	
14+61	19+40	240				958	240	62.4	36	36	
19+40	24+19	240				958	240	78	36	36	
24+19	28+98	240				958	240	78	36	36	
28+98	31+15	109				434		31.2	16	16	
31+15	32+96	91				362			14	14	
32+96	33+77	41	426		66	324	50	31.2	6	6	
33+77	36+92	158				1260	90		24	24	
36+92	38+56	82	88			328		31.2	12	12	
38+56	43+35	240				958	240	62.4	36	36	
43+35	48+14	240				958	240	78	36	36	
48+14	52+11	199				794	199	93.6	30	30	
52+11	52+50	20				78			3	3	
52+50	55+52	151	320			604		62.4	23	23	
55+52	60+25	237	240			946	291	46.8	35	35	
60+25	61+10	43				170	43	78	6	6	
61+10	68+00	345				1380	345	62.4	52	52	
68+00	68+91	46				182	46		7	7	
Ann Eliza											
113+30	127+00	685			78			183.6			
127+00	130+50	88									
130+50	135+40	123									
135+40	140+22	121									
140+22	144+26	101	470		60			62.4			
		5703	3830	70	503	14294	2460	431	1416	555	555
				501			16754				

Short Term Pavement Marking		
white	lane lines	5073
yellow	bidirectional	1354
white	stop bars	3018
total lin ft		9445

Work Zone Pavement Marking Removal		
white	lane lines	837
yellow	bidirectional	223
white	stop bars	498
total sq ft		1558

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

DRAWN BY \_\_\_\_\_

CHECKED BY \_\_\_\_\_

DATE \_\_\_\_\_