

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	*	TAZEWELL	54	42
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		
*10, 15RS-5, 9RS, 13RS-2, 15RS-4 CONTRACT NO. 68892				

DETECTOR LOOP AND DETECTOR ASSIGNMENT SCHEDULE			
IL 9 (COURT) & TENTH			
DETECTOR LOOP	TYPE	DETECTOR LOOP QTY.	DETECTOR LEAD-IN QTY.
D-4A	6' X 20'	52	30
D-4B	6' X 20'	52	18
D-4C	6' X 20'	52	6
D-8A	6' X 20'	52	30
D-8B	6' X 20'	52	18
D-8C	6' X 20'	52	6
TOTAL:		312	108

DETECTOR LOOP AND DETECTOR ASSIGNMENT SCHEDULE			
IL 9 (COURT) & FOURTEENTH			
DETECTOR LOOP	TYPE	DETECTOR LOOP QTY.	DETECTOR LEAD-IN QTY.
D-1	6' X 50' QUAD	162	30
D-2A	6' X 6'	24	18
D-2B	6' X 6'	24	6
D-5	6' X 50' QUAD	162	30
D-6A	6' X 6'	24	18
D-6B	6' X 6'	24	6
TOTAL:		420	108

INTERSECTION	PEDESTRIAN PUSHBUTTON	TRAFFIC STRUCTURES TO BE SAFETY BONDED					ELCBL C GROUND 6 1C	GROUND CABLE INSTALLATION NOTES
		SERVICE RISER	DOUBLE HANDHOLE	HANDHOLE	MAST ARM	SIGNAL POST		
IL 9 (COURT) & FOURTEENTH	8	1	1	4	4	1	410.0	ENTIRE INTERSECTION
NOTE: ONLY HANDHOLES WITH HIGH VOLTAGE CONDUCTORS SHALL BE GROUNDED. DETECTOR LOOP AND TRAFFIC SIGNAL INTERCONNECT HANDHOLES WILL TYPICALLY NOT REQUIRE GROUNDING.								

TOTALS	8	1	1	4	4	1	410
				11			

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		TRAFFIC SIGNAL DETAIL
DATE		DRAWN BY CHECKED BY

\$\$\$DATE\$\$\$
DCN-ONLY