

| | | | | |
|---------------------|-----------|------------------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 709 | (104)RS-1 | MCLEAN | 21 | 13 |
| TO STA. | | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

PARTIAL DEPTH PATCH

| STATION | DIRECTION | LANE | LENGTH (ft) | WIDTH (ft) | EXISTING OVERLAY THICKNESS (4 3/4" or less) (Inch) | PARTIAL DEPTH REMOVAL X4401705 (sq. yd) | PARTIAL DEPTH PATCHING X4421000 (tons) |
|---------------------|-----------|---------|----------------|---------------|--|--|---|
| 1336+99 | WB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1340+25 | WB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1340+25 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1340+56 | WB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1341+06 | WB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1341+06 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1341+28 | WB | DRIVING | 10 | 12 | 2.5 | 13.3 | 4.1 |
| 1342+35 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1358+45 | EB | DRIVING | 6 | 12 | 2.5 | 8.0 | 2.5 |
| 1372+51 | WB | DRIVING | 6 | 12 | 2.5 | 8.0 | 2.5 |
| 1376+52 | WB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1376+88 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1378+21 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1379+33 | WB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1387+34 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1394+74 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1394+74 | WB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1401+35 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1401+78 | EB | DRIVING | 6 | 12 | 2.5 | 8.0 | 2.5 |
| 1401+90 | WB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1422+95 | EB | DRIVING | 6 | 12 | 2.5 | 8.0 | 2.5 |
| 1435+65 | EB | DRIVING | 8 | 12 | 2.5 | 10.7 | 3.3 |
| 1437+12 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1450+13 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1450+64 | WB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| 1450+64 | EB | DRIVING | 4 | 12 | 2.5 | 5.3 | 1.6 |
| | | DRIVING | | 12 | 2.5 | 0.0 | 0.0 |
| | | DRIVING | | 12 | 2.5 | 0.0 | 0.0 |
| | | DRIVING | | 12 | 2.5 | 0.0 | 0.0 |
| | | DRIVING | | 12 | 2.5 | 0.0 | 0.0 |
| SHEET TOTALS | | | | | | 162.7 (sq. yd) | 50.1 (tons) |
| | | | | | | PARTIAL DEPTH REMOVAL X4401705 (sq. yd) | PARTIAL DEPTH PATCHING X4421000 (tons) |
| FINAL TOTALS | | | | | | 780.0 (sq. yd) | 240.2 (tons) |

PLOT DATE = 3/25/2008
 FILE NAME = \\sawtooth\work\p\m\DOT\AUSTIN\RL\0028975\70508plan.dgn
 PLOT SCALE = 42.3559 / IN.
 USER NAME = dqb11r1