TABULATION OF PARTIAL DEPTH PAVEMENT PATCHING-RURAL (EB)

STATION	DIRECTION	LENGTH	WIDTH	EXISTING OVERLAY THICKNESS	PARTIAL DEPTH REMOVAL X4401705	PARTIAL DEPTH PATCHING X4421000
700.50		(FT)	(FT)	(INCH)	(SQ YD)	(TON)
766+53	EB	6	12	6.5	8.0	4.3
791+22	EB	6	12	6.5	8.0	4.3
793+40	EB	6	12	6.5	8.0	4.3
796+78	EB	6 6	12 12	6.5	8.0	4.3
797+81 798+13	EB EB	6	12	6.5 6.5	8.0 8.0	4.3
800+31	EB	6	12	6.5	8.0	4.3
812+04	EB	6	12	7	8.0	4.5
837+48	EB	6	12	7	8.0	4.5
838+65	EB	6	12	7	8.0	4.5
858+64	EB	6	12	7	8.0	4.5
862+63	EB	6	12	7	8.0	4.5
873+43	EB	6	12	7	8.0	4.5
885+21	EB	6	12	6.5	8.0	4.3
888+95	EB	6	12	6.5	8.0	4.3
894+61	EB	6	12	6.5	8.0	4.3
902+65	EB	6	12	6.5	8.0	4.3
903+41	EB	6	12	6.5	8.0	4.3
906+45	EB	6	12	6.5	8.0	4.3
907+93	EB	6	12	6.5	8.0	4.3
911+80	EB	6	12	6.5	8.0	4.3
916+14	EB	6	12	6.5	8.0	4.3
919+37	EB	8	12	6.5	10.7	5.7
922+02	EB	8	12	6.5	10.7	5.7
925+40	EB	6	12	6.5	8.0	4.3
932+15	EB	10	12	6.5	13.3	7.1
936+00	EB	10	12	6.5	13.3	7.1
950+78	EB	12	12	6.5	16.0	8.5
953+46	EB	6	12	6.5	8.0	4.3
954+49	EB	6	12	6.5	8.0	4.3
958+22	EB	6	12	6.5	8.0	4.3
958+36	EB	6	12	6.5	8.0	4.3
962+54	EB	6	12	6.5	8.0	4.3
973+13	EB	6	12	6.5	8.0	4.3
974+19	EB	10	12	6.5	13.3	7.1
977+22	EB	6	12	6.5	8.0	4.3
980+56	EB	6	12	6.5	8.0	4.3
985+10	EB	10	12	6.5	13.3	7.1
987+58	EB	6	12	6.5	8.0	4.3
988+83	EB	6	12	6.5	8.0	4.3
989+67	EB	6	12	6.5	8.0	4.3
				SUB-TOTAL 3:	362.7	194.3

SUB-TOTAL 3: 362.7 194.3

TABULATION OF PARTIAL DEPTH PAVEMENT PATCHING- RURAL (EB)

STATION	DIRECTION	LENGTH	WIDTH	EXISTING OVERLAY THICKNESS	PARTIAL DEPTH REMOVAL X4401705	PARTIAL DEPTH PATCHING X4421000
		(FT)	(FT)	(INCH)	(SQ YD)	(TON)
992+90	EB	6	12	6.5	8.0	4.3
995+93	EB	6	12	6.5	8.0	4.3
998+64	EB	6	12	6	8.0	2.7
1011+05	EB	6	12	6	8.0	2.7
1012+37	EB	6	12	6	8.0	2.7
1021+99	EB	6	12	6.5	8.0	4.3
1036+06	EB	6	12	6.5	8.0	4.3
1036+56	EB	6	12	6.5	8.0	4.3
1039+09	EB	8	12	6.5	10.7	5.7
1044+14	EB	12	12	6.5	16.0	8.5
1046+45	EB	10	12	6.5	13.3	7.1
1050+30	EB	6	12	6	8.0	2.7
1056+83	EB	6	12	6	8.0	2.7
1059+14	EB	6	12	6	8.0	2.7
1068+90	EB	6	12	6.5	8.0	4.3
1072+28	EB	6	12	6.5	8.0	4.3
1074+65	EB	6	12	6.5	8.0	4.3
1092+12	EB	8	12	6	10.7	3.6
1093+06	EB	6	12	6.5	8.0	4.3

SUB-TOTAL 4: 170.7 79.3

FILE NAME = USER NAME = cearlockjd		DESIGNED -	REVISED -					
c:\pw_work\PWIDOT\CEARLOCKJD\dØ115224\D	570764-sht-Schedule.dgn	DRAWN -	REVISED -					
	PLOT SCALE = 40.0000 '/ IN.	CHECKED -	REVISED -					
	PLOT DATE = 4/10/2009	DATE -	REVISED -					

STATI	E OF	F ILLINOIS
DEPARTMENT	OF	TRANSPORTATION

						F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SCHEDULES					697	2RS-3&46RS-8	Vermilion	43	28	
							CONTRACT	NO.	70764	
SCALE:	SHEET NO	0. 01	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				