

TABULATION OF PARTIAL DEPTH PAVEMENT PATCHING- RURAL (WB)

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	EXISTING OVERLAY THICKNESS (INCH)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)
844+49	WB	6	12	7	8.0	4.5
862+63	WB	6	12	7	8.0	4.5
873+43	WB	6	12	7	8.0	4.5
885+21	WB	6	12	6.5	8.0	4.3
888+95	WB	6	12	6.5	8.0	4.3
894+61	WB	6	12	6.5	8.0	4.3
902+65	WB	6	12	6.5	8.0	4.3
903+41	WB	6	12	6.5	8.0	4.3
906+45	WB	6	12	6.5	8.0	4.3
907+93	WB	10	12	6.5	13.3	7.1
911+80	WB	6	12	6.5	8.0	4.3
916+14	WB	6	12	6.5	8.0	4.3
919+37	WB	8	12	6.5	10.7	5.7
922+02	WB	8	12	6.5	10.7	5.7
925+40	WB	6	12	6.5	8.0	4.3
932+15	WB	10	12	6.5	13.3	7.1
936+00	WB	10	12	6.5	13.3	7.1
942+98	WB	8	12	6.5	10.7	5.7
950+78	WB	12	12	6.5	16.0	8.5
953+46	WB	6	12	6.5	8.0	4.3
954+49	WB	6	12	6.5	8.0	4.3
955+30	WB	8	12	6.5	10.7	5.7
958+22	WB	6	12	6.5	8.0	4.3
958+36	WB	6	12	6.5	8.0	4.3
962+54	WB	6	12	6.5	8.0	4.3
973+13	WB	6	12	6.5	8.0	4.3
974+19	WB	10	12	6.5	13.3	7.1
976+37	WB	12	12	6.5	16.0	8.5
977+22	WB	6	12	6.5	8.0	4.3
980+56	WB	6	12	6.5	8.0	4.3
982+11	WB	6	12	6.5	8.0	4.3
985+10	WB	10	12	6.5	13.3	7.1
987+58	WB	6	12	6.5	8.0	4.3
988+83	WB	6	12	6.5	8.0	4.3
989+67	WB	6	12	6.5	8.0	4.3
992+90	WB	6	12	6.5	8.0	4.3
995+93	WB	6	12	6.5	8.0	4.3
998+64	WB	6	12	6	8.0	2.7
1011+05	WB	6	12	6	8.0	2.7
1021+99	WB	6	12	6.5	8.0	4.3
1036+06	WB	6	12	6.5	8.0	4.3
<b>SUB-TOTAL 7:</b>					<b>381.3</b>	<b>200.4</b>

TABULATION OF PARTIAL DEPTH PAVEMENT PATCHING- RURAL (WB)

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	EXISTING OVERLAY THICKNESS (INCH)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)
1036+56	WB	6	12	6.5	8.0	4.3
1039+09	WB	8	12	6.5	10.7	5.7
1044+14	WB	12	12	6.5	16.0	8.5
1046+45	WB	10	12	6.5	13.3	7.1
1050+01	WB	6	12	6	8.0	2.7
1059+14	WB	6	12	6	8.0	2.7
1068+90	WB	6	12	6.5	8.0	4.3
1072+28	WB	6	12	6.5	8.0	4.3
1074+65	WB	10	12	6.5	13.3	7.1
1082+22	WB	8	12	6	10.7	3.6
1092+12	WB	8	12	6	10.7	3.6
1093+06	WB	6	12	6.5	8.0	4.3
1093+14	WB	6	12	6.5	8.0	4.3
<b>SUB-TOTAL 8:</b>					<b>130.7</b>	<b>62.2</b>
<b>RURAL TOTAL (SUB-TOTALS 1-8):</b>					<b>2632.0</b>	<b>1288.3</b>

TABULATION OF PARTIAL DEPTH PAVEMENT PATCHING- URBAN

STATION	DIRECTION	LENGTH (FT)	WIDTH (FT)	EXISTING OVERLAY THICKNESS (INCH)	PARTIAL DEPTH REMOVAL X4401705 (SQ YD)	PARTIAL DEPTH PATCHING X4421000 (TON)
1112+74	LTL	6	4	7.5	2.7	1.6
1112+74	EB	6	12	7.5	8.0	4.7
1125+55	EB	6	12	6	8.0	4.0
1132+04	EB	12	12	6	16.0	8.1
1112+74	WB	6	12	7.5	8.0	4.7
1125+55	WB	6	12	6	8.0	4.0
1132+04	WB	12	12	6	16.0	8.1
1135+16	WB	12	12	6	16.0	8.1
1140+28	WB	10	12	6	13.3	6.7
<b>URBAN TOTAL:</b>					<b>96.0</b>	<b>50.0</b>
<b>JOB TOTALS:</b>					<b>2728.0</b>	<b>1340.0</b>