ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

				100% STATE		
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000		
20201100	GRADING EXISTING SHOULDER	UNIT	7.2	7.2		
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	120	120		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20		
40600300	AGGREGATE (PRIME COAT)	TON	98	98		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,940	1,940		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	972	972		
40600990	TEMPORARY RAMP	SQ YD	59	59		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3,903	3,903		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	379	379		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	1,113	1,113		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	45,651	45,651		
44000400	GUTTER REMOVAL	FOOT	680	680		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	176	176		
44002500	GUTTER OUTLET REMOVAL	EACH	1	1		
44200188	PAVEMENT PATCHING, TYPE I, 16 INCH	SQ YD	20	20		
44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SQ YD	211	211		
44200196	PAVEMENT PATCHING, TYPE III, 16 INCH	SQ YD	289	289		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,197	1,197		
48203006	HOT-MIX ASPHALT SHOULDERS, 2 1/4"	SQ YD	660	660		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4	4		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	7	7		
60602500	CONCRETE GUTTER, TYPE A	FOOT	674	674		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	176	176		
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	975	975		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12	12		
63200310	GUARDRAIL REMOVAL	FOOT	1,250	1,250		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,471	4,471		
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	48,833	48,833		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	497	497		
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	48,833	48,833		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	208	208		
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	27	27		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	250	250		

				100% STATE		
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000-2A		

*Specialty Items

FILE NAME = c:\pw_work\PWIDOT\CABRERARS\dms28567\s-tsoq.dgn	USER NAME = cabrerars	DESIGNED - RSC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JWC	REVISED -			317	(3,4)RS-6, (5,6)RS-4	ADAMS	30	3
	PLOT SCALE = 107.0000 ' / IN.	CHECKED - RSC	REVISED -					CONTRACT NO. 72845		
	PLOT DATE = Apr-09-2009 02:52:21PM	DATE - 7/23/08	REVISED -		SCALE: 50 / SHEET NO. 1 OF 1 SHEETS / STA. / TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		