

URETHANE PAVEMENT MARKING SCHEDULE									
LOCATION	URETHANE PAVEMENT MARKING LINE 5 INCH				URETHANE PAVEMENT MARKING LINE 6 INCH		URETHANE PAVEMENT MARKING LINE 8 INCH	URETHANE PAVEMENT MARKING LINE 12 INCH	
STATION TO STATION	SOLID WHITE EDGE LINES	SOLID YELLOW EDGE LINES	SKIP-DASH YELLOW	DOUBLE SOLID YELLOW	TURN LANE CHANNELIZATION SOLID WHITE	DOTTED EXTENSION OF TURN LANE LINE WHITE (2' SKIP-DASH AT 6' SPC)	SOLID WHITE ISLAND EDGE	SOLID WHITE DIAGONALS	SOLID YELLOW DIAGONALS
	QUANTITY (FT)	QUANTITY (FT)	QUANTITY (FT)	QUANTITY (FT)	QUANTITY (FT)	QUANTITY (FT)	QUANTITY (FT)	QUANTITY (FT)	QUANTITY (FT)
IL 10 EAST BOUND LANES 33+80 - 133+71.35	7,482								
IL 10 WEST BOUND LANES 33+80 - 133+71.35	8,113								
IL 10 CENTER MEDIANS 33+93 - 133+14		17,711							13
OMISSION 133+71.35 - 143+90.83									
IL 10 BI-DIRECTIONAL TURN LANE PAINTED MEDIAN & CENTERLINE EXTENSION 144+48 - 177+87			1,180	6,946					41
I-55 SB ON & OFF RAMPS	298	221			78		354	101	
I-55 NB ON & OFF RAMPS	305	177			156		369	112	
SIDESTREETS Heitmann Dr Madigan Dr Connolley Rd Malerich Dr.	282			130	74	6	261 368 455 102	90 226	
TOTALS	16,480	18,109	1,180	7,076	308	6	1,909	529	54