

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	113	113		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11740	11740		
40600300	AGGREGATE (PRIME COAT)	TON	235	235		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4615	4615		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174	174		
40600990	TEMPORARY RAMP	SQ YD	81	81		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	9861	9861		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	141	141		
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	109500	109500		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	7520	7520		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	202	202		
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	98	98		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	148	148		
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	17	17		
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	86	86		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2150	2150		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	238	238		
60500305	FILLING INLETS	EACH	2	2		
* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	1250	1250		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8		
63200310	GUARDRAIL REMOVAL	FOOT	1025	1025		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	9	9		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	15360	15360		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1301	1301		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5834	5834		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	220	220		

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	39	39		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	98485	98485		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	490	490		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	21	21		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8		
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	3	3		
Z0055600	RUMBLE STRIP	SQ YD	217	217		

* Specialty Items

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -
ct:\pwork\PWIDOT\TEASLEYCK\0123498.D	74380-shr-SDD.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/10/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
758	3RS-4,(4,5)RS-2	Moutrie	10	3
CONTRACT NO. 74380			ILLINOIS FED. AID PROJECT	