

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	118	118		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	20401	20401		
40600300	AGGREGATE (PRIME COAT)	TON	408	408		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	5599	5599		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	2829	2829		
40600990	TEMPORARY RAMP	SO YD	212	212		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	11198	11198		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	37	37		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	3463	3463		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	129558	129558		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	3318	3318		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	580	580		
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	1010	1010		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1193	1193		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	4477	4477		
48203105	HOT-MIX ASPHALT SHOULDERS, SPECIAL	TON	2482	2482		
66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	12	12		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18186	18186		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	101821	101821		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1703	1703		
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	230.4	230.4		
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8931	8931		
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	163	163		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	93501	93501		
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	538	538		
X0301232	SURVEY MARKER VAULT	EACH	1	1		
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	3	3		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		

*Specialty Items

FILE NAME =	USER NAME = teeslayck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct\pwwork\pwwid\TEASLEYCK\0121195\07	4381-sh1-500.dgn	DRAWN -	REVISED -			749	119 RS-2	Moultrie	26	3	
	PLLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 74381					
	PLLOT DATE = 4/10/2009	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					