ROUTE: IL RTE 132 (GRAND AVENUE) - FROM U.S. ROUTE 45 TO IL ROUTE 59

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	HMA SURF REM 2-1/4" & RESURF	HMA SURF REM (SP) & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
IL RTE 83		WB	1	12	6	72	8				8				
		WB	1	12	6	72	8				8				
		WB	1	12	6	72	8				8				
		WB	1	12	6	72	8				8				
		WB	1	6	10	60	7				7				
		WB	1	6	10	60	7				7				
		WB	1	6	12	72	8				8				
		WB	1	6	12	72	8				8				
		WB	1	6	12	72	8				8				
		WB	1	6	12	72	8				8				
		WB	1	6	20	120	13				13				
		WB	1	6	20	120	13				13				
		WB	1	6	20	120	13				13				
		WB	1	6	20	120	13				13				
		WB	1	6	20	120	13				13				
		EB	2	10	12	120	13				13				
		EB	1	6	12	72	8				8				
		EB	1	6	12	72	8				8				
		EB	1	6	12	72	8				8				
		EB	1	6	12	72	8				8				
		EB	1	6	30	180	20					20			
		EB	1	4	20	80	9				9				
		EB	1	4	20	80	9				9				
		EB	1	12	15	180	20					20			
		EB	1	6	12	72	8				8				
		EB	1	6	12	72	8				8				
		EB	1	6	12	72	8				8				
	FAIRFIELD ROAD	EB	1	6	12	72	8				8				
FAIRFIELD ROAD		WB	1	12	10	120	13				13				
		WB	1	12	6	72	8				8				
		WB	1	12	6	72	8				8				
		WB	1	12	6	72	8				8				
		WB	1	4	10	40	4			4					
		EB	1	12	12	144	16				16				
		EB	1	6	12	72	8				8				
		EB	1	6	12	72	8				8				
		EB	1	6	12	72	8				8				
	IL. RTE 59	EB	1	6	12	72	8				8				
		TOTALS:						319 SY	211 SY	35 SY	692 SY	87 SY		1000 FT	20 EACH

FILE NAME = c:\projects\d136088\design_aa.dgn

USER NAME = wilgroendp

PLOT SCALE = 100.0000 ' / IN.

PLOT DATE = 4/10/2008

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 132

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-020 PP	LAKE	59	42

CONTRACT NO. 60E49

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT