AU064 TOTAL SHEETS: 23

# CITY OF AURORA AURORA, ILLINOIS


CONSTRUCTION PLANS
FOR


# AURORA MUNICIPAL AIRPORT


REHABILITATE AND STRENGTHEN TAXIWAY
ALPHA ENDS AND CONNECTING TAXIWAYS - PHASE 2

ILLINOIS PROJECT: ARR-3770 A.I.P. PROJECT: 3-17-0003-B36

FEBRUARY 1, 2008







CALL J.U.L.I.E BEFORE EXCAVATING 1-800-892-0123

AURORA MUNICIPAL AIRPORT

SECTION: 17 AND 18 RANGE: 7 EAST TOWNSHIP: 38 NORTH COUNTY: KANE U.S. ROUTE 30 SUGAR GROVE TOWNSHI

#### DESIGN INFORMATION

DESIGN AIRCRAFT APPROACH CATEGORY D
DESIGN AIRCRAFT GROUP III

LOCATION MAP

SITE PLAN

#### SUMMARY OF QUANTITIES

ITEM NUMBER	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
AR108158	1/C #8 5 KV UG CABLE IN UD	LF	4,395	
AR109210	VAULT MODIFICATIONS	LS	1	
AR110212	2" STEEL DUCT, DIRECT BURY	LF	30	
AR110504	4-WAYCONCRETE ENCASED DUCT	LF	60	
AR110550	SPLIT DUCT	LF	100	
AR125410	MITL - STAKE MOUNTED	EACH	53	
AR125415	MITL - BASE MOUNTED	EACH	6	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	3	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	2	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	2	
AR125470	MODIFY EXISTING SIGN PANEL	EACH	10	
AR125565	SPLICE CAN	EACH	1	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	38	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	7	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	2	
AR150510	ENGINEER'S FIELD OFFICE	LS	1	
AR152410	UNCLASSIFIED EXCAVATION	CY	1,715	
AR152455	EMBANKMENT IN PLACE	CY	690	
AR156520	INLET PROTECTION	EACH	6	
AR163520	CONSTRUCTION FENCE	LF	985	
AR201610	BITUMINOUS BASE COURSE	TON	275	
AR208515	POROUS GRANULAR EMBANKMENT	CY	200	
AR209604	CRUSHED AGG. BASE COURSE - 4"	SY	718	
AR401610	BITUMINOUS SURFACE COURSE	TON	135	
AR401655	BUTT JOINT CONSTRUCTION	SY	290	
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	5,408	·
AR501509	9" PCC PAVEMENT	SY	9,105	
AR501530	PCC TEST BATCH	EACH	1	
AR501900	REMOVE PCC PAVEMENT	SY	100	
AR602510	BITUMINOUS PRIME COAT	GAL	200	
AR603510	BITUMINOUS TACK COAT	GAL	267	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	3,620	
AR620525	PAVEMENT MARKING - BLACK BORDER	SF	3,540	
AR620900	PAVEMENT MARKING REMOVAL	SF	520	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	LF	1,155	
AR705900	REMOVE UNDERDRAIN	LF	910	
AR705904	REMOVE UNDERDRAIN CLEANOUT	EACH	1	
AR751943	ADJUST MANHOLE	EACH	2	
AR800023	2/C #4 600V, 1/C #8 GND. UG CABLE	LF	710	
AR800081	REMOVE BIT. PVMT. (VAR. DEPTH)	SY	4,000	
AR800160	TEMPORARY GAS LINE CROSSING	EACH	1	
AR901510	SEEDING	ACRE	0.9	
AR904510	SODDING	SY	1,790	************************
AR905520	TOPSOILING (FROM OFF SITE)	CY	644	·
AR908510	MULCHING	ACRE	0.9	

#### INDEX TO SHEETS

COVER SHEET INDEX TO SHEETS / SUMMARY OF QUANTITIES
SITE PLAN / PROJECT CONTROL PLAN
SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS SEQUENCE OF CONSTRUCTION PER AC 150/5370-2E (LATEST EDITION) TYPICAL SECTIONS EXISTING CONDITIONS / PROPOSED REMOVALS - SHEET 1 8. EXISTING CONDITIONS / PROPOSED REMOVALS — SHEET 2
9. PLAN AND PROFILE — SHEET 1
10. PLAN AND PROFILE — SHEET 1
11. PAVEMENT JOINTING PLAN — SHEET 1
12. PAVEMENT JOINTING PLAN — SHEET 2
13. PAVEMENT JOINTING DETAILS 13. PAVEMENT JOINTING DETAILS

14. GRADING AND LANDSCAPING PLAN — SHEET 1

15. GRADING AND LANDSCAPING PLAN — SHEET 2

16. STORM WATER POLLUTION PREVENTION PLAN NOTES

17. STORM WATER POLLUTION PREVENTION PLAN DETAILS

18. LIGHTING AND PAVEMENT MARKING PLAN — SHEET 1


19. LIGHTING AND PAVEMENT MARKING PLAN — SHEET 2

20. AIRFIELD SIGNAGE PLAN

21. ELECTRICAL DETAILS — SHEET 1

22. ELECTRICAL DETAILS — SHEET 2

23. VAULT MODIFICATION DETAIL



# NOTES

- 1, LAY TIES IN TWO LAYERS SET LOWER TIES AND BACKFILL TO TOP OF TIES; SET SECOND LAYER AND BACKFILL TO GRADE.
- 2. PROVIDE TEMPORARY FENCE TO DEFINE CROSSING.
- 3. MAINTAIN TEMPORARY FENCING DURING CONSTRUCTION.
- 4. MAX LOADING: WHEEL LOAD: 15,000 LBS, TRACK LOAD: 80,000 LBS.
- 5. ALTERNATIVE METHODS OF TEMPORARY GAS PIPELINE CROSSING MUST BE SUBMITTED FOR APPROVAL BY NICOR GAS.

# DETAIL OF TIE SLAB FOR HEAVY EQUIPMENT CROSSING PIPELINES

(DETAIL PROVIDED BY NICOR GAS)

AU064 K:\AuroraAp\0428505 Txy A Ends Rehob\!PH2\Draw FILE: Ph2-qty-index.dwg LAYOUT: Exhibit1 DAYOUT EXHIBIT
UPDATE BY: Marc Katz
SURVEY BOOK #
DATE: Mondoy, April 14, 2008 1:35:14 PM
XREF DWG: tbcInt.dwg
tb.dwg

	REVISIONS	
NUMBER	BY	DATE.
***************************************		

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

AURORA MUNICIPAL AIRPORT
AURORA, ILLINOIS
REHABILITATE AND STRENGTHEN TAXIWAY ALPHA
ENDS AND CONNECTING TAXIWAYS - PHASE 2 SHEETS/ QUANTITIES INDEX 1 3 DESIGN BY: AAO DRAWN BY: AAO CHECKED BY:

APPROVED BY:


10/31/07

07285-04

ILLINOIS PROJECT: ARR-3770 A.I.P. PROJECT: 3-17-0003-B36 FINAL SUBMITTAL SHEET 2 OF 23 SHEETS

DATE:

JOB No:




#### **GENERAL NOTES**

- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACT OF THE AIRPORT DIRECTOR AND RESIDENT ENGINEER AND BE APPROVED BY THE DIVISION OF AERONAUTICS AND FEDERAL AVIATION ADMINISTRATION.
- 2. ALL OPERATIONS SHALL BE IN CONFORMANCE WITH AC 150/5370-2E (LATEST EDITION) SAFETY DURING
- CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE AREA WHEN CONSTRUCTION IS NOT IN PROGRESS.
- 4. THE AIRPORT DIRECTOR IN CONSULTATION WITH THE RESIDENT ENGINEER SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING SEQUENCE AS IT RELATES TO PEDESTRIAN, VEHICULAR AND
- 5. ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A HAUL ROAD OR STORAGE AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT DIRECTOR. THE COST OF MAINTAINING, REPAIRING OR CONSTRUCTING THESE PAVEMENTS AND AREAS SHALL BE INCIDENTAL TO THE CONTRACT. EXISTING AREAS OUTSIDE THE PROJECT LIMITS WHICH ARE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE
- THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE EXISTING TAXIWAYS, APRONS AND RUMAY'S OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE ENGINEER.
- 7. WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE. LIGHTING SHALL BE AS APPROVED BY THE ENGINEER AND SHALL NOT BE IF THEY AFFECT FLIGHT SAFETY. CONTRACTOR'S WORK HOURS SHALL BE IN ACCORDANCE WITH LOCAL
- 8. THE CONTRACTOR SHALL PROVIDE PORTABLE FLOOD LIGHTING FOR NIGHTIME CONSTRUCTION. SUFFICIENT UNITS SHALL BE PROVIDED SO THAT WORK AREAS ARE ILLUMINATED TO A LEVEL OF FIVE HORIZONTAL FOOT CANDLES. THE LIGHTING LEVELS SHALL BE CALCULATED AND MEASURED IN ACCORDANCE WITH THE CURRENT STANDARDS OF THE ILLUMINATION ENGINEERING SOCIETY, LIGHTS SHALL BE POSITIONED SO AS NOT TO INTERFERE WITH AIRPORT OPERATIONS.
- 9. THE CONTRACTOR WILL BE REQUIRED TO HAVE A SWEEPER AVAILABLE FOR USE AT ALL TIMES. WHEN ACTIVE AIRFIELD PAYEMENTS ARE UTILIZED AS HAUL ROADS BY THE CONTRACTOR, MATERIAL TRACKED ON TO THE PAYEMENT SHALL BE CONTINUALLY REMOVED WITH SAID SWEEPER. THIS SWEEPING SHALL NOT BE PAID FOR SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 10. MATERIALS REMOVED FROM THE PROJECT WILL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED
- 11. PAYMENT FOR TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO BARRICADES, SIGNING, RUNWAY CLOSED MARKERS, AIR OPERATIONS AREA (A.O.A.) LATHE AND RIBBON, ETC. SHALL NOT BE PAID SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. BARRICADES AT 10-FOOT CENTERS WITH ONE STALL BE CONTROLL BETWEEN EACH SET OF BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER, BARRICADES SHALL BE WEIGHTED TO PREVENT BLOWING OVER, BARRICADES SHALL HAVE A FLASHING RED LIGHT AND CONFORM TO IDOT STANDARD 702001, TYPE II. BARRICADE INSTALLATION WILL BE REQUIRED PRIOR TO ACCESS TO THE A.O.A. BY CONTRACTOR'S WORKERS, EQUIPMENT OR MATERIAL. SIGNS SHALL BE PLACED AT EACH TAXIWAY/RUNWAY CLOSURE LOCATION AND SHALL BE ATTACHED TO THE BARRICADES. EACH BARRICADE LOCATION SHALL CONSIDERED INCIDENTAL TO THE CONTRACT.
- 12. THE CONTRACTOR SHALL CONTACT THE AIRPORT DIRECTOR (5) WORKING DAYS IN ADVANCE OF THE START OF CONSTRUCTION SO THAT THE APPROPRIATE NOTAMS MAY BE ISSUED.
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ALL CONSTRUCTION ACCESS GATES CLOSED DURING NON WORKING HOURS. THE CONTRACTOR SHALL PROVIDE A SIGN AT THE ACCESS GATE SAYING "AUTHORIZED PERSONNEL ONLY". THE CONTRACTOR SHALL CLOSE AND LOCK THE ACCESS GATE UPON LEAVING THE SITE. THROUGHOUT THE DURATION OF THE CONTRACT, ANY DAMAGES TO THE ACCESS ROAD ACCESS GATE OR FENCING ADJACENT TO THE PROJECT SHALL BE REPAIRED BY THE CONTRACTOR TO TH SATISFACTION OF THE RESIDENT ENGINEER. ALL COST RELATING TO CONTRACTOR'S ACCESS AND SECURITY
- 14. CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS OR HAVE BEACON LIGHTS DURING DAYLIGHT HOURS, ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION. ANY EQUIPMENT OPERATING DURING HOURS OF DARKNESS OR REDUCED VISIBILITY MUST BE EQUIPPED WITH BEACON LIGHTS. SEE FLAG DETAIL,
- 15. IN THE CASE OF AN EMERGENCY, CONTRACTOR SHALL NOTIFY AIRPORT DIRECTOR AND THE ENGINEER IMMEDIATELY.
- 16. DURING ADVERSE WEATHER, THE CONTRACTOR SHALL MAKE PROVISIONS FOR ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT, NO EXTENSION OF CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK.
- 17. THE TALLEST PIECE OF CONSTRUCTION EQUIPMENT IS ANTICIPATED TO BE AN ASPHALT/STONE TRUCK WHICH HAS A MAXIMUM HEIGHT OF 20 FEET IN A DUMP POSITION.
- 18. IF RUNWAY NUMERALS ARE PRESENT DURING CONSTRUCTION, CONTRACTOR SHALL PLACE CLOSED RUNWAY MARKER OVER NUMERALS AS DETAILED, OTHERWISE PLACE IN TURF OFF END OF RUNWAY AS DETAILED.
- AURORA MUNICIPAL AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF WORK WITH THE AIRPORT IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT
- 20. APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT AND THE SEQUENCE OF CONSTRUCTION PLAN. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS, COUNTY ROADS OR CITY STREETS) WITH THE APPROPRIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE ROADS USED AS HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE
  CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL
  ROUTE. THE BEFORE AND AFTER CONDITION OF ON—SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED
  AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER, FENCING, DRAINAGE, GRADING AND OTHER
  MISCELLANGOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OR ACCESS POINTS
  ON THE AIRPORT WILL BE THE CONTRACTOR'S TOTAL RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE WORK, ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN
- 21. MOBILIZATION/EQUIPMENT STORAGE AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS, THIS AREA SHALL BE RESTORED TO THE ORIGINAL CONDITION UPON COMPLETION OF THE PROJECT AT THE CONTRACTOR'S EXPENSE.
- 22. LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGEO, REPAIRS SHALL BE DONE FROM POINT TO POINT IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING

- 23. COORDINATION MEETINGS THE CONTRACTOR SHALL CONDUCT WEEKLY COORDINATION MEETINGS TO DISCUSS WORK AREAS AND SCHEDULING, ETC. WITH THE ENGINEER, AIRPORT OPERATIONS, AND OTHER APPROPRIATE OFFICIALS. MINUTES FROM THE WEEKLY MEETINGS SHALL BE PREPARED BY THE CONTRACTOR, FURNISHED TO ALL ATTENDEES PRIOR TO THE SUBSEQUENT MEETING, AND KEPT ON FILE AT THE FIELD OFFICE. THE COORDINATION MEETING COSTS SHALL BE CONSIDERED INCIDENTAL TO THE OPPLIES.
- 24. THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL, INCLUDING THE PROJECT SUPERINTENDENT, WHO MAY BE CONTACTED IN AN EMERGENCY, PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES.
- 25. DRAINAGE MODIFICATIONS SHALL BE SEQUENCED TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES AT NO ADDITIONAL COST TO THE CONTRACT
- 26. VEHICLES AND EQUIPMENT SHALL NOT BE ALLOWED WITHIN 65' FROM ACTIVE TAXIWAYS AND 200' FROM ACTIVE RUNWAYS UNLESS OTHERWISE APPROVED BY THE AIRPORT DIRECTOR.
- 27. CONTRACTOR SHALL STORE FOLIPMENT AND MATERIALS/STOCKPILES IN SUCH A MANNER AS NOT TO IOLATE FEDERAL AVIATION ADMINISTRATION PART 77 SURFACES OR RUNWAY AND TAXIWAY SAFETY AREAS
- 28. ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER ELECTRICAL CABLES SHALL REMAIN IN SERVICE AT ALL TIMES. ALL EXISTING LIGHTING AND VAULT EQUIPMENT SHALL REMAIN IN SERVICE UNTIL PROPOSED IMPROVEMENTS ARE INSTALLED AND OPERATIONAL, UNLESS OTHERWISE APPROVED BY THE ENGINEER. ANY CABLES DAMAGED BY THE CONTRACTOR SHALL BE IMMEDIATELY REPAIRED AT HIS EXPENSE
- 29. COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED, CONTRACTOR IS REFERRED TO SECTION 50--17 OF THE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER OR THE DESIGN ENGINEER ASSUME ANY RESPONSIBILITY WHATEVER IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND THE AMEDIAL OF EXPRESSED ON THE PROPERTY OF THE SECONDARY OF THE PROPERTY OF THE SECONDARY OF THE SECONDARY OF THE PROPERTY OF THE SECONDARY INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND TYPE MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE RESIDENT ENGINEER AND THE AIRPORT DIRECTOR, ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT DIRECTOR.
- 30. ALL AIRFIELD LIGHTING AND LIGHTING GUIDANCE SYSTEMS (NAVAIDS) LOCATED WITHIN AND IMMEDIATELY ADJACENT TO THE CONTRACTOR'S WORK ZONE SHALL BE CHECKED FOR OPERATIONAL CONDITION PRIOR TO THE DEPARTURE FROM THE AIRPORT WITH THE AIRPORT MAINTENANCE DIRECTOR. ANY DEFECIENCIES IN THESE SYSTEMS DUE TO THE ACTS OF CONTRACTOR OR HIS SUBCONTRACTORS, SUPPLIERS OR

#### CONTRACTOR CROSSING RUNWAY AND TAXIWAY AIR OPERATIONS AREA (A.O.A.)

- 31. ANYTIME THE CONTRACTOR IS REQUIRED TO UTILIZE OR CROSS ACTIVE AIRFIELD PAVEMENTS FOR ACCESS TO ANYTIME THE CONTRACTOR IS REQUIRED TO UTILIZE OR CROSS ACTIVE AIRFIELD PAVEMENTS FOR ACCESS TO AND FROM THE WORK ZONE, A FULL TIME CROSSING GUARD IN RADIO CONTACT WITH THE CONTROL TOWER SHALL BE FURNISHED BY THE CONTRACTOR FOR MOVEMENTS OF VEHICLES OR EQUIPMENT TO AND FROM THE WORK ZONE. THE RADIO OPERATOR SHALL BE FAMILIAR WITH AIRPORT GROUND CONTROL PROCEDURES AND DEMONSTRATE KNOWLEDGE OF SAME TO THE AIRPORT, THE AIRPORT RESERVES THE RIGHT TO APPROVE THE CROSSING GUARDS. THE CONTRACTOR SHALL PROVIDE THEIR OWN RADIOS. THIS COST SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYMENT OF MUNICIPAL FINES (\$500 PER OCCURENCE) DUE TO AIRFIELD INCURSIONS BY HIS EMPLOYEES, SUBCONTRACTORS, SUPPLIERS, CONSULTANTS, AND OR ACENTS.
- 32. ANY PAVEMENT DAMAGED BY CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY BY HIM TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT DIRECTOR AT NO ADDITIONAL COST TO THE OWNER. PAVEMENT SHALL BE CONTINUALLY SWEPT TO PROVIDE DEBRIS FREE SURFACE DURING ALL HAUL ROAD OPERATIONS, THIS COST SHALL NOT BE PAID SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE
- 33, WORK WITHIN THE A.O.A. SHALL BE EXPEDITED. ANY DROP OFF SHALL BE ADEQUATELY LIGHTED. SIGNED AND BARRICADED, NO MATERIAL SHALL BE STOCKPILED WITHIN THE A.O.A. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE EQUIPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT DIRECTOR TWO (2) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS.



#### TYPICAL SECTION **OBSTACLE FREE ZONE (OFZ)**

NO SCALE

RUNWAY	TYPE OF RUNWAY	H (FEET)
9-27	PRECISION (CAT I)	43
*15-13	PRECISION (CAT I)	43
*15~33 18~36	VISUAL	150

NOTE: ONCE RUNWAY 15/33 IMPROVEMENTS (BY OTHERS) ARE COMPLETE, THE RUNWAY WILL BE CHANGED FROM A VISUAL TYPE TO A PRECISION (CAT 1).


#### LIMITATIONS ON CONSTRUCTION WITHIN AIRPORT OPERATIONS AREA (A.O.A.)

#### RUNWAYS:

ANY WORK WITHIN 200' OF THE CENTERLINE OF AN ACTIVE RUNWAY SHALL BE DONE AS SHOWN ON THE SEQUENCE OF CONSTRUCTION PLAN SHEETS. ON ANY DAY WHEN CONSTRUCTION IS WITHIN 200' OF THE CENTERLINE OF THE RUNWAY, THE RUNWAY SHALL BE CLOSED. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT DIRECTOR TWO (2) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. WORK SHALL BE EXPEDITED IN THESE AREAS AND AT THE COMPLETION OF THE PHASE THE AREAS SHALL BE SMOOTHLY GRADED TO ALLOW THE RUNWAY TO BE REOPENED. AT LEAST ONE OF THE RUNWAYS SHALL BE MIND IN OPERATION AT ALL TIMES. IF NECCESSARY STEEL PLATES SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR TO COVER ANY OPEN TRENCHES OR EXCAVATION WITHIN THE A.D.A. IF DURING RUNWAY CLOSURE AN EMERGENCY IS DECLARED, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE RUNWAY OF ALL VEHICLES, MEN AND EQUIPMENT.


CONSTRUCTION WILL BE ALLOWED UP TO THE EDGE OF THE TAXIWAY PAVEMENTS WITHOUT CLOSURE ON A LIMITED BASIS. WORK WITHIN THE A.O.A. SHALL BE EXPEDITED. ANY DROP OFF SHALL BE ADEQUATELY LIGHTED, SIGNED AND BARRICADED. NO MATERIAL SHALL BE STOCKPILED WITHIN THE A.O.A. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE EQUIPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT DIRECTOR TWO (2) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS.

NOTE - ALL PHASES ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER AIRPORT ELECTRICAL CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT ENGINEER, ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED INCIDENTAL TO CONTRACT.



#### TYPICAL SECTION F.A.R. PART 77 IMAGINARY SURFACES

NOTE: IMAGINARY SURFACE REQUIREMENTS FOR EXISTING ACTIVE RUNWAYS (R/W) ARE SIMILAR EXCEPT PRIMARY SURFACE (PS) DIMENSIONS VARY R/W 18~36 500' PS (250' LT & RT OF  $\mathbb C$ ) R/W 9~27,15/33 1000' PS (500' LT & RT OF  $\mathbb C$ )



#### CONSTRUCTION EQUIPMENT AND TRUCK SIGNAL FLAG

NOT TO SCALE 200' RUNWAY PAVEMENT 200' **ELEVATION** APPROACH SLOPF APPROACH SLOPE TYPICAL PROFILE

# F.A.R. PART 77 IMAGINARY SURFACES

RUNWAY END	ELEVATION	APPROACH SLOPE
9	707	50:1
27	706	34:1
18	700	20:1
36	700	20:1
15	712	20:1
33	699	20:1
*15	712	50:1
*33	699	50:1

\* NOTE: ONCE RUNWAY 15/33 IMPROVEMENTS (BY OTHERS) ARE COMPLETE, THE

#### AU064 K:\AuroroAp\0428505 Txy A Ends Rehob\!PH2\Drox FILE: Seq-notes.dwg LAYOUT: Loyout1 UPDATE BY: Marc Katz SURVEY BOOK # DATE: Thursday, April 03, 2008 2:44:50 PM XREF DWG: tbclnt.dwg tb.dwg

F	3	
NUMBER	BY	DATE
0	1	2

THIS BAR IS FOUAL TO 2"


GTHEN TAXIWAY ALPH TAXIWAYS - PHASE 2 PE A AIRPORT 즈 디 22 AND MUNICIP/ ÖØ URORA, STRENC 00 TE AND CONNEC шZ A RC ENDS AND ΘZ ШШ **S** 

3 AAO DRAWN RY JRO CHECKED BY MLK

APPROVED BY DATE 10/31/07

JOB No 07285-04 ILLINOIS PROJECT: ARR-3770 A.I.P. PROJECT: 3-17-0003-B36 FINAL SUBMITTAL

SHEET 4 OF 23 SHEETS



#### CLOSED RUNWAY MARKER DETAIL NOTES

- 1. CLOSED RUNWAY MARKERS SHALL BE YELLOW
- 2. MARKERS SHALL BE MATERIAL APPROVED BY THE ENGINEER.
- 3. CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE
- 6. DURING VARIOUS PHASES OF WORK, IT WILL BE NECESSARY TO CLOSE RUNWAYS TO AIR TRAFFIC ON A TEMPORARY BASIS AS COORDINATED WITH THE AIRPORT AND TOWER PERSONNEL. THE CONTRACTOR SHALL MARK THE RUNWAYS TO BE CLOSED BY PLACING A YELLOW CROSS AT THE LOCATION AND DIMENSIONS DETAILED ON THIS SHEET. THE CROSSES ARE SHOWN ON THE RESPECTIVE RUNWAYS ACCORDING TO THE VARIOUS PHASES OF WORK AS DELINEATED IN THE SUGGESTED SEQUENCE OF CONSTRUCTION.

4. MARKERS ON PAVEMENT SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS AS SHOWN. 5. COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE SPECIAL PROVISIONS SECTION 30-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS AND SUBCONTRACTORS.

#### OPERATIONAL STATUS/ WORK AREA ALLOWABLE WORK RESTRICTIONS PERIODS PHASE 1A RUNWAY 9/27, TAXIWAY A BETWEEN TAXIWAY A1 AND A2, TAXIWAY A1, A5 AND A7 AND NO RESTRICTIONS TAXIWAY A BETWEEN AS AND A7 CLOSED BEGIN WORK AFTER ALL P.C.C. PAVING IS COMPLETE AS WELL AS ALL PHASE 1B DAY CLOSURES OF RUNWAY 9/27, WHEN WORKING WITHIN RUNWAY 9/27 AOA. CLOSURE OF TAXIWAY A1. A5 AND A7 AS GRADING WITHIN RUNWAY 9/27 A.O.A. WELL AS TAXIWAY ALPHA BETWEEN TAXIWAY AT AND AZ AND ALSO BETWEEN TAXIWAY A7 AND TAXIWAY BRAVO FOR DURATION OF WORK

#### SUGGESTED SEQUENCE OF CONSTRUCTION

ON PAVEMENT

CLOSED RUNWAY MARKER DETAIL

DESIGN AIRPORT GROUP: III GROUND CONTROL FREQUENCY: 121.70 AIR CONTROL FREQUENCY: 120.60

MAXIMUM ANTICIPATED HEIGHT OF CONSTRUCTION EQUIPMENT: 20'

CLOSEST CONSTRUCTION POINT TO RUNWAY 9/27 - POINT A LATITUDE: 41°46'12.09" N (NAD 83)
LONGITUDE: 88°29'04.63" W
EXISTING ELEVATION: XXX.XX

CLOSEST CONSTRUCTION POINT TO

RUNWAY 15/33 - POINT B LATITUDE: 41'46'12.49" (NAD 83)

LONGITUDE: 88'28'51.40" EXISTING ELEVATION: XXX.XX

NO SCALE

#### PHASE 1A

- CLOSE RUNWAY 9/27.
- PLACE X'S AND BARRICADES AS SHOWN OR AS DIRECTED BY THE ENGINEER. (SEE PHASING NOTE 4)
- PLACE CONSTRUCTION FENCE AND TIE SLAB (PER DETAIL) FOR GAS MAIN PROTECTION,
- REMOVE BITUMINOUS PAVEMENT AND UNDERDRAIN.
- WIDEN FILLETS.
- · CONSTRUCT ALL P.C.C. PAVEMENT
- CONSTRUCT SHOULDER GRADING (SEE PHASING NOTE 1).
- · CLEAN PAVEMENTS, REMOVE BARRICADES AND OPEN RUNWAY 9/27.

#### PHASE 1B

- COORDINATE DAY CLOSURES OF RUNWAY 9/27 AS NEEDED WITH RESIDENT ENGINEER.
- PLACE X'S AND BARRICADES AS SHOWN OR AS DIRECTED BY THE ENGINEER. (SEE PHASING NOTE 4)
- CONSTRUCT UNDERDRAIN, LIGHTING AND LANDSCAPING IMPROVEMENTS.
- CLEAN PAVEMENTS, REMOVE BARRICADES AND OPEN TAXIWAYS.

(PH 18 WORK WITHIN RUNWAY AGA SHALL BE EXPEDITED)

#### **LEGEND**

AQA

NEW P.C.C. PAVEMENT

AIR OPERATIONS AREA (A.O.A.)
ACTIVE RUNWAYS 200' CENTERLINE TO A.O.A.
ACTIVE TAXIWAYS 76' CENTERLINE TO A.O.A.



AIRCRAFT MOVEMENT AREAS



BARRICADES WITH FLASHING RED LIGHTS AND SIGNS "DO NOT ENTER" AND "AIRCRAFT MOVEMENT AREA" (SEE GENERAL NOTE 11 ON PREVIOUS SHEET)



TEMPORARY CONSTRUCTION FENCING FOR GAS MAIN PROTECTION



CONTRACTOR'S ACCESS/HAUL ROAD

LIMITS OF WORK

#### PHASING NOTES

- PHASE 1A WORK SHALL BE EXPEDITED TO MINIMIZE RUNWAY 9/27 CLOSURE TIME. THE CONTRACTOR SHALL COMPLETE ALL PCC PAVING AS WELL AS SHOULDER GRADING WITHIN RUNWAY 9/27 A.O.A. FIRST SO RUNWAY 9/27 CAN BE OPENED.
- CONTRACTOR SHALL INSTALL TEMPORARY CONSTRUCTION FENCE PER PLAN AND PROFILE SHEET 10 AND PER NICOR REQUIREMENTS.
- CONTRACTOR SHALL MAINTAIN OPERATIONAL LIGHTING TO SKY HAVEN AREA AT ALL TIMES THROUGHOUT DURATION OF THE WORK, ALL TEMPORARY CABLING AND SPLICING SHALL BE CONSIDERED INCIDENTAL TO CONTRACT
- IN ADDITION TO BARRICADES SHOWN, BARRICADES SHALL BE PLACED ACROSS RUNWAY 9/27 AT THE AOA LINE EAST AND WEST OF TAXIWAY CHARLIE ANYTIME RUNWAY 9/27 IS CLOSED.

AU064 K:\AuraraAp\0428505 Txy A Ends Rehab\!PH2\Drox FILE: Ph2-sequence.dwa LAYOUT: Layout1 JPDATE BY: Marc Katz SURVEY BOOK # DATE: Thursday, April 03, 2008 2:38:14 PM XREF DWG: tbcint.dwg tb.dwg txyend-bose.dwg

	REVISIONS	ì
NUMBER	8Y	DATE
o o	1	2
THIS B	AD IS EQUAL	70.2"

AT FULL SCALE (34X22).

UCTION ST EDITION GTHEN TAXIWAY ALPHA TAXIWAYS - PHASE 2 AIRPORT ONSTRI (LATE MUNICIPAL UENCE OF C STREN EHABILITATE AND ENDS AND CONNE ō ЩO ある EB **5** DESIGN BY CAL DRAWN BY JRO CHECKED BY: CAL DATE: 10/31/07 JOB No: 07285-04 ILLINOIS PROJECT: ARR-3770 A.I.P. PROJECT: 3-17-0003-B36 FINAL SUBMITTAL

SHEET

5 OF 23 SHEETS

#### TAXIWAY A EAST, A1, A5 AND A7 TYPICAL SECTION A-A

NOT TO SCALE


# VARIES VARIES VARIES VARIES VARIES VARIES VARIES VARIES (SEE GRADING PLAN) F 1.0%-1.5% (TYPICAL) A B C W W W W N

# TAXIWAY A/A1 AND A/A5 FILLET WIDENING TYPICAL SECTION B-B

NOT TO SCALE

## LEGEND


- A) NEW 9" P.C.C. PAVEMENT (501)
- B EXISTING BITUMINOUS PAVEMENT TO BE REMOVED (VARIABLE DEPTH 4"-12")(SEE NOTE 5)
- EXISTING CRUSHED AGGREGATE BASE COURSE (VARIABLE DEPTH; 13" © TAXIWAY A1 AND 18" © TAXIWAY A5 AND A7)
- D EXISTING CRUSHED AGGREGATE
  BASE COURSE TO BE REMOVED AND
  PAID FOR AS UNCLASSIFIED EXCAVATION (152)
  (VARIABLE DEPTH)(SEE NOTE 1)
- E EXISTING GROUNDLINE
- F NEW 6' WIDE SOD (904)(SEE NOTE 2)
- G NEW TOPSOIL PLACEMENT (MINIMUM 4")(905)
- H NEW DOWEL BAR (501)
- (I) NEW TIE BAR (501)
- (J) EXISTING UNDERDRAIN TO REMAIN
- (K) EXISTING UNDERDRAIN TO BE REMOVED (TRENCH SHALL BE BACKFILLED WITH CRUSHED AGGREGATE BACKFILL (208). INCIDENTAL TO UNDERDRAIN REMOVAL)
- (L) NEW 4" CRUSHED AGGREGATE BASE COURSE (209)
- M NEW 18" CRUSHED AGGREGATE BASE COURSE PLACEMENT (SEE NOTE 3)
- (N) NEW 6" UNDERDRAIN W/ SOCK (705)
- (INCIDENTAL TO UNDERDRAIN)(705)
- P NEW UNDERDRAIN TRENCH FABRIC ENVELOPE (INCIDENTAL TO UNDERDRAIN)(705)
- NEW UNCLASSIFIED EXCAVATION (152)
- R LEVELING COURSE IN AREAS OF VARIABLE DEPTH BITUMINOUS PAVEMENT REMOVAL (ARBO0081) (INCIDENTAL TO ARBO0081)



#### UNDERDRAIN DETAIL EDGE OF FILLET WIDENING PAVEMENT AREAS NOT TO SCALE

## NOTES

- I. GRADING AND RE-COMPACTING OF EXISTING CRUSHED AGGREGATE BASE COURSE SHALL BE INCIDENTAL TO CRUSHED AGGREGATE BASE COURSE REMOVAL.
- SHOULDER SHALL BE DISCED OR SCARIFIED PRIOR TO PLACEMENT OF TOPSOIL. MAXIMUM PAY WIDTH FOR SOD SHALL BE 6'-0".
- CONTRACTOR SHALL REUSE EXISTING CRUSHED AGGREGATE BASE BEING REMOVED. PAYMENT SHALL BE PER 152 EMBANKMENT IN PLACE.
- ALL PROPOSED UNDERDRAIN AT EDGE OF PAVEMENT SHALL BE INSTALLED AFTER THE 9" P.C.C. PAVEMENT IS CONSTRUCTED.
- 5. SEE EXISTING CONDITION SHEETS FOR AREAS TO BE PAID FOR AS AR800081 REMOVE BITUMINOUS PAVEMENT (VAR. DEPTH) OR AR401900 REMOVE BITUMINOUS PAVEMENT.



KEY MAP

AUO64 K:\unordap\0428505 Txy A Ends Rehab\\PHZ\\Draw\
FILE: ph2—typsec.dwg
LAYOUT: Layout1
UPDATE BY: mkatz
SURVEY BOOK #
DATE: Mon 4/14/08 1:38pm
XREF DWG: tbcint.dwg
tb.dwg
txyend—base.dwg

REVISIONS

NUMBER BY DATE

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

AURORA MUNICIPAL AIRPORT
AURORA, ILLINOIS
REHABILITATE AND STRENGTHEN TAXIWAY ALPHA
ENDS AND CONNECTING TAXIWAYS - PHASE 2
TYPICAL SECTIONS

 DESIGN BY:
 CAL

 DRAWN BY:
 JRO


 CHECKED BY:
 CAL


 APPROVED BY:
 DATE:


 10/31/07


ILLINOIS PROJECT: ARR-3770 A.I.P. PROJECT: 3-17-0003-B36 FINAL SUBMITTAL


SHEET 6 OF 23 SHEETS























## STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SECURING, WHICH WILL BE THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLANT, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

#### SITE DESCRIPTION

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF REHABILITATING THE WEST END OF TAXIWAY ALPHA AT THE AURORA AIRPORT. THE PROJECT INCLUDES EXCAVATION, DRAINAGE, VARIOUS PAVEMENT ITEMS, ELECTRICAL IMPROVEMENTS AND OTHER

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS EXCAVATION AND GRADING:

- 1. PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL, SUCH AS INLET
- 2. EXCAVATION WILL BE COMPLETED WITHIN THE PROJECT LIMITS TO GRADE OUT FOR A TAXIWAY FILLET WIDENING.
- 3. UNDERDRAIN INSTALLATION.
- 4. PAVEMENT CONSTRUCTION.
- 5. ELECTRICAL IMPROVEMENTS
- 6. FINAL GRADING AND OTHER MISCELLANEOUS ITEMS.
- 7. PLACEMENT OF PERMANENT EROSION CONTROL, SUCH AS SODDING.

#### AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 3.00 ACRES OF WHICH 1.20 ACRES WILL BE DISTURBED BY EXCAVATION, GRADING AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- 2. PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

THE CONSTRUCTION SITE DRAINS INTO THE WELCH CREEK THROUGH A STORM SEWER SYSTEM.

#### CONTROLS-EROSION CONTROLS AND SEDIMENT CONTROL

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION

THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE SEEDING AND MULCHING AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES JANUEL BE INTUITED AS SOON AS POSSIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. WHERE WORK IS COMPLETE, PERMANENT STABILIZATION SHALL OCCUR WITHIN 14 DAYS OF COMPLETION, AND IN AREAS WHERE WORK HAS TEMPORARILY CEASED FOR 21 DAYS OR MORE, TEMPORARY STABILIZATION SHALL OCCUR BY THE 14TH DAY AFTER WORK HAS CEASED.

AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, INLET PROTECTION AND PERIMETER SILT FENCE SHALL BE INSTALLED AS CALLED OUT IN THE PLANS OR

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10. ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

#### DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES.

- 1. WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT
- 2. EARTH STOCKPILES AND OTHER BUILDING MATERIALS TO REMAIN IN PLACE MORE THAN (3) DAYS SHALL BE FURNISHED WITH EROSION AND SEDIMENT CONTROL MEASURES AND SHALL BE INCIDENTAL TO THE CONTRACT. IF THEY ARE TO REMAIN UNUSED FOR MORE THAN 30 DAYS. STOCKPILES SHALL NOT BE LOCATED IN SPECIAL MANAGEMENT AREAS.
- 3. AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEERS
- A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.
- B. CONSTRUCT DITCHES AND PROVIDE TEMPORARY EROSION CONTROL SYSTEMS.
- C. BUILD NECESSARY EMBANKMENT AT CULVERT/STORM SEWER LOCATIONS AND THEN EXCAVATE AND PLACE
- D. EXCAVATED AREAS AND EMBANKMENT AREAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S COST, IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS.
- E. ANY WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION SHALL BE
- 4. CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REQUILATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- 5. THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT DAILY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2 INCH OR GREATER OR EQUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD.
- 5. SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR UNCLASSIFIED EXCAVATION AND EROSION CONTROL ITEMS.
- 7. THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

#### DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

#### MAINTENANCE AFTER CONSTRUCTION

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.

#### CONTRACTORS

- 1. THE STORM WATER POLLUTION PREVENTION PLAN MUST CLEARLY IDENTIFY FOR EACH MEASURE IDENTIFIED IN THE PLAN, THE CONTRACTOR(S) OR SUBCONTRACTOR(S) THAT WILL IMPLEMENT THE MEASURE. ALL CONTRACTORS AND SUBCONTRACTORS IDENTIFIED IN THE PLAN MUST SIGN A COPY OF THE CERTIFICATION STATEMENT IN PARAGRAPH 2 BELOW IN ACCORDANCE WITH PART VI.G (SIGNATORY REQUIREMENTS) OF THIS PERMIT. ALL CERTIFICATIONS MUST BE INCLUDED IN THE STORM WATER POLLUTION PREVENTION PLAN EXCEPT FOR OWNERS THAT ARE ACTING AS CONTRACTOR.
- 2. CERTIFICATION STATEMENT. ALL CONTRACTORS AND SUBCONTRACTORS IDENTIFIED IN A STORM WATER POLLUTION PREVENTION PLAN IN ACCORDANCE WITH PARAGRAPH 1 ABOVE SHALL SIGN A COPY OF THE FOLLOWING CERTIFICATION STATEMENT BEFORE CONDUCTING ANY PROFESSIONAL SERVICE AT THE SITE IDENTIFIED IN THE STORM WATER POLLUTION PREVENTION PLAN:
  - "I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (1LR10) THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION."

THE CERTIFICATION MUST INCLUDE THE NAME AND TITLE OF THE PERSON PROVIDING THE SIGNATURE IN ACCORDANCE WITH PART VIG OF THIS PERMIT: THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE CONTRACTING FIRM; THE ADDRESS (OR OTHER IDENTIFYING DESCRIPTION) OF THE SITE: AND THE DATE THE CERTIFICATION IS MADE.

				TOR	GENERAL CONTRA
SIGNATURE TITLE D.	ATE	DATE	TITLE	······································	GIGNATURE

#### AU064 K:\AuroraAp\0428505 Txy A Ends Rehab\!PH2\Dron FILE: ph2-stormnotes.dwg LAYOUT: Model UPDATE BY: mkgtz SURVEY BOOK #

DATE: Mon 2/4/08 3:08pm XREF DWG: tbcint.dwg tb.dwg

R	EVISIONS	1	_
NUMBER	BY	DATE	
			_
			_
			•
	***************************************		_
			•

THIS BAR IS EQUAL TO 2 AT FULL SCALE (34X22)

# AURORA MUNICIPAL AIRPORT AURORA, ILLINOIS EHABILITATE AND STRENGTHEN TAXIWAY ALPH ENDS AND CONNECTING TAXIWAYS - PHASE 2 38 ōΖ ◄ ◘ 2 ATE ₹ ΣШ **~> 9**m ö DESIGN BY DKP JRO CHECKED BY: APPROVED BY: DATE: 10/31/07


07285-04

ILLINOIS PROJECT: ARR-3770 A.I.P. PROJECT: 3-17-0003-836 FINAL SUBMITTAL SHEET 16 OF 23 SHEETS

#### SOIL PROTECTION CHART

	<del></del>	·	·		·····		,	r			·	
STABILIZATION TYPE	JAN	FEB	MAR	APR	MAY	JUNE	JULY	AUG	SEPT	ОСТ	NOV	DEC
PERMANENT SEEDING			<b>≱</b> ≙		+ A1				-	+ <u>A1</u>		
DORMANT SEEDING	8		•								+8-	-
TEMPORARY SEEDING			+ <u>c</u>			-	D		-			
SODDING			**E						-			
MULCHING	F											-

- A KENTUCKY BLUEGRASS 100 LBS/ACRE PERENNIAL RYEGRASS 60 LBS/ACRE CREEPING RED FESCUE 40 LBS/ACRE
- B KENTUCKY BLUGRASS 100 LBS/ACRE PERENNIAL RYEGRASS 60 LBS/ACRE CREEPING RED FESCUE 40 LBS/ACRES
- D WHEAT OR CEREAL RYE 150 LBS/ACRE
- E SOD
- F HYDROMULCH 2 TON/ACRE
- C SPRING OATS 100 LBS/ACRE \* IRRIGATION NEEDED DURING JUNE AND JULY
  - \*\* IRRIGATION NEEDED FOR A MINIMUM 3 TO 4 WEEKS AFTER APPLYING SOD



#### NOTES:


- FILTER WRAP TO BE PLACED IN ALL SLOPE BOXES, INLETS, MANHOLES, TRENCH DRAINS AND CATCH BASINS LOCATED IN PAVED AREAS AND NONPAVED AREAS.
- FABRIC SHALL BE IN CONFORMANCE WITH MATERIALS SPECIFIED FOR FABRIC FENCE.
- FABRIC SHALL OVERLAY FRAME BY 2-INCH (MINIMUM).
- CONTRACTOR SHALL CLEAR DEBRIS AND SILT AS REQUIRED FROM FABRIC TO MAINTAIN DRAINAGE THROUGH THE STRUCTURE.
- FABRIC SHALL REMAIN IN PLACE UNTIL TURFED AREAS HAVE DEVELOPED A MINIMUM OF 80% OF COVERAGE.
- COST OF FILTER WRAP SHALL BE CONSIDERED INCIDENTAL TO INLET PROTECTION.

#### DRAINAGE STRUCTURE FILTER WRAP

NOT TO SCALE

# 5' MAX C. TO C. - 48" MIN. FENCE POSTS, DRIVEN 24" MINIMUM INTO GROUND - SILT FENCE (FABRIC FENCE)

#### PERSPECTIVE VIEW




#### EROSION CONTROL FABRIC FENCE DETAIL NOT TO SCALE

#### CONSTRUCTION NOTES FOR SILT (FABRIC) FENCE

- WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER— LAPPED BY 6—INCH MIN. AND FOLDED.
- 2. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.
  MAINTENANCE, WHICH INCLUDES THE REPLACEMENT OF DAMAGED
  FENCE, SHALL BE CONSIDERED INCIDENTAL TO THE COST OF
- 3. SILT FENCE SHALL BE INSTALLED PER GRADING AND LANDSCAPING PLAN OR AS DIRECTED BY THE ENGINEER


## **NOTES FOR ALL** INLET PROTECTION

- SILT FENCE AND SPACERS SHALL NOT BE MEASURED SEPERATELY FOR PAYMENT, BUT WILL BE INCLUDED IN THE UNIT PRICE FOR
- 2. INSPECTION SHALL BE FREQUENT AND REPAIR REPLACEMENT SHALL BE MADE PROMPTLY
- 3. AFTER FINAL APPROVAL OF THE ENGINEER, SILT FENCE MAY BE REMOVED. CONTRACTOR SHALL PLACE SEED AND MULCH OVER THE
- 4. SILT FILTER FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFIED FOR ITEM AR156000 EROSION CONTROL IN THE ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF AERONAUTICS SUPPLEMENTAL SPECIFICATIONS AND RECURING SPECIAL




# INLET PROTECTION (END SECTION)

NOT TO SCALE IDOT\_STANDARD\_280001~03



#### INLET PROTECTION (INLET/MANHOLES)

NOT TO SCALE IDOT STANDARD 280001-03



#### STABILIZED CONSTRUCTION ENTRANCE

FROM NRCS STANDARD DRAWING NO. IL-630

- FILTER FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFIED FOR AR152540 IN THE ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF AERONAUTICS SUPPLEMENTAL SPECIFICATIONS AND RECURING SPECIAL PROVISIONS.
- 2. ROCK OR RECLAIMED CONCRETE SHALL MEET ONE OF THE FOLLOWING IDOT COARSE AGGREGATE GRADATION, CA-1, CA-2, CA-3 OR CA-4.
- 3. ANY DRAINAGE FACILITIES REQUIRED BECAUSE OF WASHING SHALL BE CONSTRUCTED ACCORDING TO MANUFACTURERS SPECIFICATIONS AND SHALL BE INCIDENTAL TO THE CONTRACT.
- 4. MINIMUM WIDTH IS 14' FOR ONE-WAY TRAFFIC AND 20' FOR TWO WAY TRAFFIC. TWO-WAY TRAFFIC WIDTHS SHALL BE INCREASED A MINIMUM OF 4' FOR TRAILER TRAFFIC DEPENDING ON THE TYPE OF VEHICLE OR EQUIPMENT, SPEED, LOADS, CLIMATIC AND OTHER CONDITIONS UNDER WHICH VEHICLES AND EQUIPMENT OPERATE AN INCREASE IN THE MINIMUM WIDTHS MAY BE
- 5. ROADWAY SHALL FOLLOW THE CONTOUR OF THE NATURAL TERRAIN TO THE EXTENT POSSIBLE.
- 6. STABILIZED CONSTRUCTION ENTRANCE SHALL BE INCIDENTAL TO THE CONTRACT.

AU064 K:\AuraroAp\0428505 Txy A Ends Rehob\!PH2\Dran FILE: stormerosdtl.dwg LAYOUT: Layout1 UPDATE BY: mkgtz SURVEY BOOK # DATE: Mon 2/4/08 3:12pm XREF DWG: tbclnt,dwg tb.dwg

> **REVISIONS** NUMBER BY DATE

THIS BAR IS EQUAL TO 2' AT FULL SCALE (34X22).

UCIPAL AIRPORT A, ILLINOIS INGTHEN TAXIWAY ALPHA 3 TAXIWAYS - PHASE 2 TAIL T S A MUNICIPAL RORA, ILLIN 띺 STREN WAT

TORM EVEN

STO

AURORA


SEHABILITATE


DESIGN BY JRO


DRAWN BY: CHECKED BY: APPROVED BY: DATE: 10/31/07 JOB No: 07285-04


ILLINOIS PROJECT: ARR-3770 A.I.P. PROJECT: 3-17-0003-B36 FINAL SUBMITTAL

SHEET 17 OF 23 SHEETS









4A

# CONCRETE ENCASED DUCT END DETAIL

NO SCALE

4-WAY

#### CONCRETE ENCASED DUCT BANKS/SPLIT DUCT


4" INSIDE DIAMETER

-#4 CONTINUOUS REBARS IN EACH CORNER

NOT TO SCALE


#### NOTES:

- 1. DIMENSIONS ARE MINIMUM.
- 2. CONCRETE SHALL CONFORM TO ITEM 610.
- 3. ALL CONDUIT SHALL BE SCHEDULE 40 PVC
- TOP OF CONCRETE ENCASEMENT IN TURP AREAS SHALL NOT BE LESS THAN 24" BELOW FINISHED GRADE.
- 5. 4" SPLIT DUCT SHALL BE CONCRETE ENCASED WITH 3" MINIMUM CONCRETE SURROUNDING 4" CONDUIT. COST INCIDENTAL TO SPLIT DUCT.
- PROVIDE PULL STRINGS AND CAPS FOR UNUSED DUCTS.




# EXTENSION OF EXISTING DUCT

NOTE: COST OF CONNECTION SHALL BE CONSIDERED INCIDENTAL TO NEW DUCT.



.15"




DUCT MARKERS SHALL BE

DRILLED AND GROUTED FLUSH


WITH THE SURFACE OF THE

# DUCT/CONDUIT MARKER DETAIL NOT TO SCALE




ELECTRICAL

DUCT/CONDUIT




#### TYPE A - CABLE SPLICE

FOR SPLICES IN HOMERUNS AND FOR EXTENSIONS TO EXISTING CABLES ONLY N.T.S.



#### TYPE B - CABLE SPLICE

FOR SPLICES FOR USE AT JUNCTION OF HOMERUN WITH LOOP CIRCUIT N.T.S.




#### TYPE C AND D - CABLE SPLICE

FOR SPLICES AT RUNWAY/TAXIWAY LIGHTS AND SIGNS N.T.S.


#### NOTES

- 1. INSIDE DIAMETER OF CONNECTOR SHALL PROPERLY MATCH THE OUTSIDE DIAMETER OF CABLE.
- WRAP WITH AT LEAST ONE LAYER OF RUBBER OR SYNTHETIC RUBBER TAPE AND ONE LAYER OF PLASTIC TAPE, ONE—HALF LAPPED, EXTENDING AT LEAST 1-1/2 INCHES ON EACH SIDE OF JOINT.
- THE COST OF FURNISHING AND INSTALLING ALL SPLICE MATERIALS SHALL BE INCIDENTAL TO THE ASSOCIATED CABLE ITEMS.
- 4. THE CONTRACTOR SHALL HAVE A MINIMUM OF TWO (2) TYPE A SPLICE KITS ON THE JOB SITE AT ALL TIMES FOR EMERGENCY REPAIRS.




# GRS CONDUIT UNDER P.C.C. PAVEMENT DETAIL NOT TO SCALE

NEW DUCT BANK/CONDUIT SHALL BE INSTALLED AT AN ELEVATION THAT WILL NOT CONFLICT WITH EXISTING OR NEW UTILITIES INCLUDING STORM SEWER, UNDERDRAIN, CONDUIT, DUCT, GAS, WATERMAIN, PHONE, ELECTRICAL AT NO ADDITIONAL COST TO THE CONTRACT.



#### RUNWAY/TAXIWAY LIGHTING CIRCUIT CONNECTION DETAIL


NOT TO SCALE



# CABLE IN UNIT DUCT - PLOWED

NOT TO SCALE

CONTRACTOR SHALL HAVE THE OPTION TO TRENCH OR PLOW UNIT DUCT. NO ADDITIONAL PAYMENT SHALL BE MADE FOR TRENCHING.




#### TRENCH DETAIL

NOT TO SCALE

NOTE: AT CONTRACTOR'S OPTION, CABLE PLOWING MAY BE USED IN LIEU OF TRENCHING.

#### NOTES


- TRENCHES WITH MORE THAN 2 CABLES SHALL BE INCREASED 3" IN WIDTH FOR EACH ADDITIONAL CABLE. IF SPECIFIED ON PLANS, TWO PARALLEL TRENCHES MAY BE CONSTRUCTED.
- 2. DEPTH OF TRENCHES SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED ON THE PLANS.
- 3. SAND BACKFILL SHALL BE USED IF THE EXISTING SOIL DOES NOT MEET THE BACKFILL REQUIREMENTS.
- 4. ALL DISTURBED SURFACES SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST IS INCIDENTAL.



## CONCRETE ENCASED DUCT BACKFILL

NOT TO SCALE

AU064 PATH: K:\AuroraAp\0628503\Draw\Sh FILE: ph2-elecdtl-1 UPDATE BY: johse SURVEY BOOK # XREF DWG: XRFF DWG: DATE: Wed 12/15/04 5:43pm REVISIONS NUMBER RY DATE THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22). RA MUNICIPAL AIRPORT AURORA, ILLINOIS S STRENGTHEN TAXIWAY A ECTING TAXIWAYS - PHAS AND ONNE CTRIC, H S RAWFOR DESIGN BY: AB DRAWN BY JRO CHECKED BY APPROVED BY DATE: 10/31/07 07285~04 A.I.P. PROJECT: 3-17-0003-B36 FINAL SUBMITTAL SHEET 21 OF 23 SHEETS



# HOLD LINE / TAXIWAY GUIDANCE SIGN L-858, SIZE 2, STYLE 2, CLASS 2

10' (TYPICAL)

. HIGHT FIXTURE

(BLUE LENS)

BREAKABLE COUPLING

LIGHT IDENTIFICATION

#### SIGNAGE NOTES

- 1. ALL SIGNS ARE 2-SIDED SIGNS.
- 2. TRANSFORMER WATTAGE AS RECOMMENDED BY MANUFACTURER.
- 3. LIGHTED SIGNS SHALL BE BASE MOUNTED ONLY.
- 4. UNIT DUCT SHALL BE TERMINATED IN THE CAN AND SEALED TO THE CABLE WITH HEAT SHRINK AS SPECIFIED.
- 5. THE NUMBER OF MODULES PER SIGN SHALL BE AS RECOMMENDED BY THE MANUFACTURER.

30-45 WATT LAMP

SECONDARY LEAD


30/45 WATT 6.6/6.6 AMP

PROPOSED CONDUIT BUSHING (TYP.)

UNIT DUCT SHALL BE TERMINATED — INSIDE THE LIGHT BASE AND SEALED WITH HEAT SHRINK AS SPECIFIED

PROPOSED HEAT SHRINK (TYP.)

CONTRACTOR SHALL SUBMIT DETAILED SHOP DRAWING INCLUDING SIGN, COLOR, SIZE AND PROPOSED LEGEND, IN ENOUGH DETAIL AND DETERMINE PROPOSED SPACING AND OTHER INFORMATION REQUIRED BY SPECIAL PROVISIONS. CONTRACTOR TO VERIFY PROPOSED SIGN LOCATIONS AND ORIENTATIONS WITH RESIDENT ENGINEER PRIOR TO



# LIGHT IDENTIFICATION DETAIL

#### NOTES:

SEE CROSS SECTIONS

- PROPOSED L-823 PRIMARY CABLE CONNECTORS

- PROPOSED 1/C #8, SKV., L-824

TYPE C CABLE IN UNIT DUCT

- 3/4" DIA. X 10' LONG COPPER CLAD GROUND ROD.

(SEE GENERAL NOTE 10)

GRS CONDUIT (TYP.)
PROPOSED 6" SAND CUSHION—COMPACTED

3' OF SLACK MIN. IN EACH PRIMARY CABLE

BEND RADIUS 10" MIN. FOR UNIT DUCT.

L-867 CLASS | BASE 12" DIA.

24" MIN. DEPTH

ITEM 610 CONCRETE

- . INSTALL A NONCORROSIVE DISC OF 2" MINIMUM DIAMETER WITH THE NUMBER PERMANENTLY STAMPED, CUT OUT, OR ENGRAVED UNDER THE HEAD OF THE BASE PLATE BOLT OR ATTACHED TO LIGHT FLANGE WITH A SET SCREW.
- NUMERALS SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY, ALL EXISTING AND PROPOSED TAXIMAY AND RUNWAY LIGHTS SHALL BE TAGGED AS DIRECTED BY THE RESIDENT ENGINEER. ALL LIGHTS ON EXISTING CIRCUITS THAT HAVE LIGHTING IMPROVEMENTS (NEW OR RELOCATED LIGHTS) SHALL BE
- COST OF TAGGING LIGHTS SHALL NOT BE PAID FOR SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

AIRFIELD SIGNAGE SCHEDULE								
SIGN NUMBER	PROPOSED SIGN FACE	PROPOSED SIGN LEGEND	PROPOSED SIGN TYPE	SIGN PANEL SIZE	EXISTING SIGN LEGEND	COMMENTS		
S1	8	# V # LV BLANK	3.2 0	SEE NOTE 2	N/A	NEW SIGN PANEL 5 CHARACTER		
\$2	N S	VI BENK 12-27	0,2 2,1	SEE NOTE 2	●∀ l∀ A1 27	NEW SIGN PANEL 6 CHARACTER		
\$3	N S	N/C NANALE D	N/C 2,0	9'x2'	6-72 ⊃ 2 81 €	MODIFY EXISTING SIGN PANEL		
54	E W	J/N AI + C +	N/C 2,3	9'x2'	V 81-9€ A ♠ C	MODIFY EXISTING SIGN PANEL		
S5	E W	V BIVNK D\N	0,2 N/C	9'x2'	V 6 ♥ A 18-36	MODIFY EXISTING SIGN PANEL		
56	E W	N/C S\NK	0,2 N/C	11'x2'	V 6 ♥ A 15-33	MODIFY EXISTING SIGN PANEL		
\$7	N S	N/C	3,2,3 N/C	9'x2'	8 V <b>→</b> 9-27 B	MODIFY EXISTING SIGN PANEL		
S8	N 5	BI BIVAK D\N	0,2 N/C	9'x2'	● ∀ 8 8 9-27	MODIFY EXISTING SIGN PANEL		
59	N S	3/N B BLANK	N/C 2,0	12'x2'	6-∠Z 8 •15 8	MODIFY EXISTING SIGN PANEL		
S10	N S	# V ⇒ GV	3.2 0	SEE NOTE 2	N/A	NEW SIGN PANEL 5 CHARACTER		
511	N S	N/G STANK	0,2 N/C	9'x2'	SV ♦ V ♣ A5 9-27	MODIFY EXISTING SIGN PANEL		
S12	N S	BLANK BLANK	2,3 0	SEE NOTE 2	N/A	NEW SIGN PANEL 4 CHARACTER		
S13	N S	A7 B-27	0,2 2,1	SEE NOTE 2	XNV18   ZV   87   27   27   27   27   27   27   27	NEW SIGN PANEL 6 CHARACTER		
S14	E W	* 3 *   V	3,2 2	SEE NOTE 2	N/A	NEW SIGN PANEL 4 CHARACTER		
S15	ε <b>w</b>	<b>*3 *</b> d	3,2 2	SEE NOTE 2	N/A	NEW SIGN PANEL 4 CHARACTER		
S16	E W	E BIANK	0,2 N/C	11'x2'	d ££ ¢ P 18-36	MODIFY EXISTING SIGN PANEL		
S17	E W	3/N P BLANK	N/C 2,0	9'x2'	22 d 0 RMP P	MODIFY EXISTING SIGN PANEL		

#### PROPOSED SIGN TYPE LEGEND


- 0 BLANK PANEL BLACK
- 1 RUNWAY/TAXIWAY HOLDLINE WHITE LEGEND ON RED BACKGROUND
  2 LOCATION SIGN YELLOW LEGEND ON BLACK BACKGROUND
  3 DIRECTION SIGN BLACK LEGEND ON YELLOW BACKGROUND 4- REMAINING DISTANCE - WHITE LEGEND ON BLACK BACKGROUND

#### NOTES

- EXCHANGING OF EXISTING PANELS BETWEEN SIGNS WILL BE INCIDENTAL
  TO THE COST OF RELOCATING OR ADJUSTING THE SIGN. ANY EXISTING
- 2. PROPOSED GUIDANCE SIGNS PANEL SIZE WILL BE BASED ON THE MANUFACTURER'S RECOMMENDATION. CONTRACTOR TO VERIFY SIZE OF PANEL BEFORE SUBMITTING SHOP DRAWINGS OR ORDERING MATERIALS.
- 3. EXISTING SIGN TO BE REMOVED AND REPLACED WITH NEW SIGN

### GERERAL NOTES:

- THE CONCRETE BASE FOR BASE MTD. LIGHTS SHALL BE TROWEL FINISHED WITH A 45° BEVELED EDGE. SLOPE TO DRAIN (610).
- 2. TRANSFORMER HOLDER SHALL BE ANY COMMERCIALLY AVAILABLE BRICK.
- 3. BREAKING GROOVE COUPLINGS SHALL NOT BE OVER 1" ABOVE GROUND LINE.
- 4. ISOLATION TRANSFORMERS COME WITH A FACTORY INSTALLED PLUG (TYPE 1, CLASS A, STYLE 2) AND RECEPTACLE (TYPE 1, CLASS A, STYLE 9). A TYPE 1, CLASS B, STYLE 10 RECEPTACLE SHALL BE INSTALLED ON THE 1/C, No. B, 5000 V., L-824 TYPE C CABLES FOR CONNECTION TO EACH TRANSFORMER.
- 5. TO FURTHER REDUCE THE POSSIBILITY OF WATER/MOISTURE ENTRANCE INTO THE CONNECTOR BETWEEN THE CABLE AND THE FIELD ATTACHED CONNECTOR, IT IS REQUIRED THAT A HEAT SHRINKABLE TUBING WITH INTERNAL ADHESIVE BE
- ALL SIGNS, LIGHTS, CABLES AND TRANSFORMERS TO BE REMOVED SHALL REMAIN THE PROPERTY OF THE AIRPORT. AT THE DISCRETION OF THE AIRPORT DIRECTOR, THE CONTRACTOR MAY BE REQUIRED TO DISPOSE OF THESE MATERIALS OFFSITE.
- 7. TAXIWAY LIGHTS SHALL HAVE A BLUE LENS, RUNWAY LIGHTS SHALL HAVE A CLEAR OR 180° AMBER/CLEAR LENS AS DESIGNATED ON PLANS.
- 8. DUCT MARKERS SHALL BE INSTALLED AT EVERY NEW DUCT AND AT EVERY EXISTING DUCT USED FOR THIS PROJECT.
- 9. CONTRACTOR SHALL HAVE THE OPTION TO TRENCH OR PLOW UNIT DUCT. NO ADDITIONAL PAYMENT SHALL BE MADE FOR TRENCHING.
- 10. INSTALL 1/C #6 AWG BARE COPPER GROUND JUMPER CONNECTED TO GROUND LUG INSIDE BASE CAN OR STAKE AND EXOTHERMICALLY WELDED TO GROUND ROD.



# NEW/ADJUSTED/RELOCATED STAKE MOUNTED MEDIUM INTENSITY TAXIWAY LIGHT

NOT TO SCALE

# XREF DWG: DATE: Wed 12/15/04 5:41pm REVISIONS NUMBER BY DATE THIS BAR IS EQUAL TO 2 AT FULL SCALE (34X22). A MUNICIPAL AIRPORT AURORA, ILLINOIS S STRENGTHEN TAXIWAY A ECTING TAXIWAYS - PHAS S S AURORA E AND 3 DESIGN BY AB DRAWN BY JRO CHECKED BY: AB ' APPROVED BY DATE: 10/31/07 07285-04 ILLINOIS PROJECT: ARR-3770 A.I.P. PROJECT: 3-17-0003-B36 FINAL SUBMITTAL SHEET 22 OF 23 SHEETS

AU064 PATH: K:\AuroraAp\06285D3\Draw\S

FILE: edtl1.dwg UPDATE BY: johse

SURVEY BOOK #

# NEW/ADJUSTED/RELOCATED BASE MOUNTED MEDIUM INTENSITY TAXIWAY LIGHT

24" ROUND

OR SQUARE

0

0

∠ BRICK

NOT TO SCALE

