DE069

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR110014	4" DIRECTIONAL BORE	L.F.	172	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR208910	REMOVE & REPLACE AGGREGATE BASE	S.Y.	88	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	418	
AR501910	REMOVE & REPLACE PCC PAVEMENT	S.Y.	49	
AR620520	PAVEMENT MARKING – WATERBORNE	S.F.	100	
AR701830	TRENCH BACKFILL	C.Y.	1,085	
AR760508	8" DUCTILE IRON WATER MAIN	L.F.	2,049	
AR760718	18" STEEL CASING	L.F.	90	
AR760800	FIRE HYDRANT	EA.	2	
AR760830	WATER VALVE	EA.	4	
AR760840	IRON FITTINGS	LBS.	250	
AR760905	REMOVE FIRE HYDRANT	EA.	2	
AR760907	REMOVE WATER VALVE	EA.	3	
AR800460	12" X 8" TAPPING VALVE & SLEEVE	EA.	2	
AR800461	1" RPZ BACKFLOW PREVENTER	EA.	2	
AR800462	WATER SERVICE–LONG	EA.	5	
AR800463	WATER SERVICE–SHORT	EA.	5	
AR800464	RECONNECT WATER SERVICE	EA.	10	
AR800465	FILL EXISTING WATER MAIN	C.Y.	13	
AR901510	SEEDING	AC.	1	
AR908510	MULCHING	AC.	1	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN – GA RAMP AREA
5	PROPOSED CONSTRUCTION PLAN – GA RAMP AREA
6	PROPOSED CONSTRUCTION PLAN – NORTHWEST QUADRANT AREA
7	PROPOSED PLAN AND PROFILE SOUTH LEG, STA. 0+00 TO STA. 5+00
8	PROPOSED PLAN AND PROFILE NORTH SOUTH LEG, STA. 5+00 TO STA. 9+60
9	PROPOSED PLAN AND PROFILE NORTH SOUTH LEG, STA. 9+60 TO STA. 14+60
10	PROPOSED PLAN AND PROFILE NORTH SOUTH LEG, STA. 14+60 TO STA. 16+60
11	PROPOSED PLAN AND PROFILE NORTH LEG, STA. 0+00 TO STA. 5+00
12	PROPOSED WATER MAIN DETAIL SHEET 1
13	PROPOSED WATER MAIN DETAIL SHEET 2
14	PROPOSED WATER MAIN DETAIL SHEET 3
15	PROPOSED WATER MAIN DETAIL SHEET 4

DATE	REVISION	BY

DECATUR AIRPORT

DECATUR, ILLINOIS

IL PROJ.: DEC-3801 A.I.P. PROJ.: 3-17-0033-XX

HGI Project No. 07A0060D 0800
Filename R-002FLP.DWG
Scale NOT TO SCALE
Date 03/12/08

LAYOUT	RAW	03/12/08
DRAWN	BAK	03/12/08
REVIEWED	JR	04/18/08

HANSON

Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

CONSTRUCT WATER MAIN

SUMMARY OF QUANTITIES AND INDEX TO SHEETS

2

APR 18, 2008 1:27 PM WALLE00723
I:\AIRPORTS\DECATUR\07A0060\CAD\SHEETS\R-002FLP.DWG – Layout1