
CONSTRUCTION PLANS FOR

KEWANEE MUNICIPAL AIRPORT

KEWANEE, HENRY COUNTY, ILLINOIS **CONSTRUCT VAULT**

SCOPE OF WORK

THIS PROJECT CONSISTS OF THE CONSTRUCTION OF A NEW AIRPORT ELECTRICAL VAULT WITH NEW ELECTRICAL & MECHANICAL EQUIPMENT. PROJECT INCLUDES NEW ELECTRIC SERVICE, THE REMOVAL OF THE EXISTING ELECTRICAL VAULT AND ELECTRICAL EQUIPMENT, & INTERFACING/REPLACING CABLE TO AIRFIELD LIGHTING SYSTEMS. PROJECT ALSO INCLUDES REPLACING THE EXISTING L-807 WIND CONE WITH A NEW WIND CONE, AND UPGRADES TO THE EXISTING AIRPORT ROTATING BEACON AND PLASI UNITS.




LOCATION

ILL. PROJ. A.I.P. PRO

LATITUDE: LONGITUDE: 89° 57' 50" ELEVATION: 858.0' M.S.L. DATE: APRIL 1, 2008

KE008 TOTAL SHEETS: 27

HANSON



IGHTFOOT 062-047643

HANSON

KEWANEE AIRPORT AUTHORITY

PLANS PREPARED BY:

EZI-3586 J. 3-17-0058-B12	Approved Syll 177
41' 12' 19"	Approved

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR107812	L-807 WIND CONE-12' INTERNALLY LIT	EA	1	
AR107900	REMOVE WIND CONE	EA	1111	
AR108158	1/C #8 5KV UG CABLE IN UD	LF	7100	
AR108554	2/C #4 600V UG CABLE IN UD	LF	920	
AR108656	3/C #6 600V UG CABLE IN UD	LF	870	
AR108800	CONTROL CABLE	LF	560	
AR109110	ERECT PRE-FABRICATED VAULT	LS	11	
AR109200	INSTALL ELECTRICAL EQUIPMENT	LS	1	
AR109901	REMOVE ELECTRICAL VAULT	LS	1	
AR110014	4" DIRECTIONAL BORE	LF	340	
AR110503	3-WAY CONCRETE ENCASED DUCT	LF	216	
AR110504	4-WAY CONCRETE ENCASED DUCT	LF	66	
AR110610	ELECTRICAL HANDHOLE	EA	3	
AR125989	REFURBISH PLASI	EA	2	
AR150540	HAUL ROUTE	LS	1	
AR800590	4/C #6 600V UG CABLE IN UD	LF	310	
AR800591	UPGRADE AIRPORT ROTATING BEACON	LS	1	
				·
				·····

	(
···········				
····				
	,			***************************************
			······································	***************************************

	KE008	è		
	INDEX TO SHEETS	REVISION		
HEET NO.	DESCRIPTION	1	++++	+
1 2 3 4 5 6	COVER SHEET SUMMARY OF QUANTITIES, INDEX TO SHEETS PROPOSED SAFETY PLAN ELECTRICAL LEGEND AND ABBREVIATIONS EXISTING VAULT SITE PLAN PROPOSED VAULT SITE PLAN	DAT	40IS	717 0000
8 9 10 11 12 13	PROPOSED ELECTRICAL PLAN TAXIWAY "A" PROPOSED ELECTRICAL PLAN STA. 12+00 TO STA. 20+00 PROPOSED AIRPORT ELECTRICAL VAULT EQUIPMENT PLAN VAULT LIGHTING AND RECEPTACLE PLAN PROPOSED AIRPORT ELECTRICAL VAULT WALL ELEVATIONS PROPOSED VAULT ELECTRICAL ONE-LINE DIAGRAM SHEET 1	PAI AIRPOR	SOUNTY, ILLINOIS A.P. PROJ.: 3-17-0058-812	
14 15 16 17 18 19 20 21 22	PROPOSED VAULT ELECTRICAL ONE-LINE DIAGRAM SHEET 2 PANEL SCHEDULES & DETAILS HIGH VOLTAGE WIRING SCHEMATIC AIRFIELD LIGHTING CONTROL SCHEMATIC CONTINUED LIGHTING CONTACTOR PANEL DETAIL LEGEND PLATE SCHEDULE AND TRANSFORMER WIRING DIAGRAMS ELECTRICAL AND GROUNDING DETAILS WIND CONE ELEVATION DETAILS PROPOSED PLASI WIRING DETAILS & NOTES	KEWANEE MINIORE INCOME	KEWANEE, HENRY COUNTY, ILLINOIS PROJ.: EZI-3586 AJP, PROJ.: 3-17-0058-	
23 24 25	LIGHTNING PROTECTION DETAILS FOR BEACON ELECTRICAL DETAILS		آ ک و	
26 27	ELECTRICAL NOTES SHEET 1 ELECTRICAL NOTES SHEET 2	roject No.	DRAWN MV 04/13/06 DRAWN MV 04/18/06 REVIEWED C.A.H. 04/27/06	
		HANSON	Hanson Professional Services Inc. 3125 Dandy Trait, Suite 100 Indianapolis, Indiana 45214 Offices Naborwide	
		CONSTRUCT VAULT	SUMMARY OF QUANTITIES, INDEX TO SHEETS	
			2	

SCOPE OF WORK

THE PROPOSED IMPROVEMENTS INCLUDE THE CONSTRUCTION OF A NEW ELECTRICAL VAULT, REMOVAL OF THE EXISTING ELECTRICAL VAULT, GROUNDING UPGRADES TO AND REFURBISHMENT OF AIRFIELD EQUIPMENT, REMOVAL AND REPLACEMENT OF PRIMARY WIND CONE, AND MODIFICATIONS TO THE ROTATING BEACON.

CONTRACTOR'S RESPONSIBILITIES

THE CONTRACTOR MUST FOLLOW PROCEDURES ON THIS SHEET THAT ASSURES SAFE OPERATING CONDITIONS FOR AIRCRAFT AS WELL AS HIS PERSONNEL AND EQUIPMENT. THE AIRPORT MANAGER WILL AT ALL TIMES HAVE JURISDICTION OVER THE SAFETY OF AIR TRAFFIC DURING CONSTRUCTION.

IDENTIFICATION - THE CONTRACTOR IS REQUIRED TO MARK ALL VEHICLES AND EQUIPMENT USED FOR CONSTRUCTION WITH 3 FT, SQUARE, INTERNATIONAL ORANGE AND WHITE CHECKERED FLAGS ANYTIME THEY ARE ON AIRPORT PROPERTY.

ALL CONTRACTOR PERSONNEL SHALL HAVE IDENTIFICATION MAKING IT OBVIOUS THAT THEY ARE A PART OF THE CONSTRUCTION CREW.

THE CONTRACTOR, HIS EMPLOYEES, AND EQUIPMENT SHALL BE RESTRICTED TO THE PROJECT WORK AREA.

RADIO CONTROL - THE CONTRACTOR IS REQUIRED TO BE IN TWO-WAY RADIO CONTACT WITH THE KEWANEE MUNICIPAL AIRPORT UNICOM (122.80 MHZ) WHENEVER HIS PERSONNEL ARE ON THE AIRPORT PROPERTY.

EQUIPMENT PARKING AND STORAGE - THE CONTRACTOR'S EQUIPMENT PARKING, MATERIAL STORAGE, AND EMPLOYEE PARKING WILL BE AT THE LOCATION SHOWN ON THIS DRAWING. ONLY VEHICLES AND EQUIPMENT NECESSARY FOR CONSTRUCTION WILL BE PERMITTED TO LEAVE THESE AREAS.

THE CONTRACTOR IS REQUIRED TO LIMIT THE USE OF CONSTRUCTION EQUIPMENT ON THE EXISTING PAVEMENTS. ONLY EQUIPMENT NEEDED TO COMPLETE THE SPECIFIC WORK ON THE EXISTING PAVEMENT WILL BE PERMITTED. THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING ANY DAMAGE TO EXISTING PAVEMENTS CAUSED BY HIS PERSONNEL OR

NO OPEN HOLES OR TRENCHES WILL BE ALLOWED WITHIN 200' OF AN ACTIVE RUNWAY, WITHIN 40' OF AN ACTIVE TAXIWAY OR TAXILANE, NOR WILL EITHER HOLES OR OPEN TRENCHES BE ALLOWED TO REMAIN EXPOSED OR OPEN OVER

TRAFFIC CONES

TRAFFIC CONES WILL BE USED ON A CLOSED RUNWAY FOR TRAFFIC CONTROL IN LIEU OF BARRICADES.


AIRCRAFT OPERATION LINE

(HORIZONTAL AND VERTICAL I	DATA		`
NO.	DESCRIPTION	NORTHING	EASTING	ELEV.
1	KEWPORT AZ (NGS) MARKER, ALUM. ROD	1,652,491.649	2,349,792.846	850.62
2	CHISELED "O" ON INSPECTION HOLE		-	848.87
3	KEWPORT (NGS) MARKER, ALUM. ROD	1,652,431.715	2,352,728.103	854.13
4	CHISELED "O" ON EAST END OF CONC. SIGN BASE		-	854.76
5	CHISELED "□" ON WEST END OF CONC. SIGN BASE	-	-	851.21

PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTITY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

150-ENGINEER'S FIELD OFFICE NOTES

AN ENGINEER'S FIELD OFFICE WILL NOT BE REQUIRED FOR THIS PROJECT.




THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE

CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 1-800-892-0123.

TEMPORARY RUNWAY CLOSURE NOTE

COST OF CONSTRUCTING, PLACING, MAINTAINING AND REMOVING CROSSES WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED. THE CROSSES WILL BE YELLOW IN COLOR AND SHALL BE MADE OF A SUITABLE MATERIAL AS APPROVED BY THE RESIDENT ENGINEER. THE CROSSES WILL BE PLACED AS SHOWN ON THIS SHEET AND SECURED IN A MANNER APPROVED BY THE RESIDENT ENGINEER. THE PROPOSED CROSSES WILL BE PLACED EACH DAY THE RUNWAY IS CLOSED AND REMOVED WHEN THE RUNWAY IS RE-OPENED. THE CONTRACTOR WILL BE RESPONSIBILE FOR THE PLACEMENT AND REMOVAL OF THE CROSSES. NO ADDITIONAL COMPENSATION TO THE CONTRACT WILL BE ALLOWED.



CROSSES MAY BE PLACED OVER THE NUMERALS OR OFF THE RUNWAY END AS DETAILED.

KE008

COUNTY, ILLINOIS

AIRPORT

MUNICIPAL

KEWANEE MUNI KEWANEE, HENRY

310-06VL) ?-101SAE. 1"= 400' 1/01/08

HANSON

STRUCT

DETAIL OF CROSS FOR CLOSED RUNWAY

RUNWAY CLOSURE PROCEDURES:

- * CONTACT THE AIRPORT MANAGER OR HIS ASSIGNED REPRESENTATIVE.
- * ISSUANCE OF NOTAM BY THE AIRPORT MANAGER OR HIS ASSIGNED REPRESENTATIVE.
- * PLACEMENT OF CROSSES (SEE DETAIL THIS SHEET).

* PLACEMENT OF LIGHTED BARRICADES. ONLY AT THE TIME THAT ALL OF THE ABOVE ARE COMPLETED MAY ANY CONSTRUCTION OPERATIONS WITHIN 200 FT. OF THE AFFECTED RUNWAY CENTERLINE BEGIN.

RUNWAY RE-OPENING PROCEDURES:

- REMOVE CROSSES.
- * REMOVE LIGHTED BARRICADES.

* NOTIFY THE AIRPORT MANAGER OR HIS REPRESENTATIVE TO CANCEL THE NOTAM.

* CANCELLATION OF THE NOTAM. A CLOSED RUNWAY WILL NOT BE RE-OPENED UNTIL ALL EQUIPMENT AND WORK ARE FURTHER THAN 200 FT. FROM THE AFFECTED RUNWAY CENTERLINE.

RUNWAY AND TAXIWAY CLOSURE NOTE:

RUNWAY 9-27 AND 1-19 WILL BE CLOSED ANY TIME CONSTRUCTION ACTIVITIES ARE REQUIRED WITHIN 200' OF THE RESPECTIVE RUNWAY CENTERLINE, IN ACCORDANCE WITH THE PROCEDURES SHOWN ON THIS PROPOSED SAFETY PLAN. HOWEVER, ONE RUNWAY WILL REMAIN OPEN AT ALL TIMES. TAXIWAY "B" AND "C", AS WELL AS THE PORTION OF THE RAMP AFFECTED BY THE PROJECT, WILL BE CLOSED ANY TIME CONSTRUCTION ACTIVITIES ARE WITHIN 40' OF THE TAXILANE OR TAXIWAY CENTERLINE.

THE MAXIMUM ANTICIPATED HEIGHT OF THE CONSTRUCTION EQUIPMENT WILL BE 25 FT. THE TALLEST EQUIPMENT IS EXPECTED TO BE A CRANE OR BUCKET TRUCK USED TO WORK ON THE AIRPORT PRIMARY WIND CONE.

THE CONTRACTOR IS REQUIRED TO CONSTRUCT A TEMPORARY HAUL ROUTE AND EQUIPMENT PARKING AREA IN ACCORDANCE WITH THE SPECIAL PROVISIONS AND AT THE LOCATION SHOWN ON THIS SHEET. THE HAUL ROUTE AND EQUIPMENT PARKING AREA SHALL BE ESTABLISHED AS FAR SOUTH AND EAST OF RUNWAY 1-19 AS IS PRACTICAL.

THE DESIGNATED HAUL ROUTE SHALL BE THE ONLY ACCESS USED BY THE CONTRACTOR OR HIS EMPLOYEES.

THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS TO USE STATE, CITY, COUNTY, OR TOWNSHIP ROADS.

THE CONTRACTOR AND HIS PERSONNEL SHALL ACCESS THE AIRPORT THROUGH AN EXISTING GATE LOCATED OFF MIDLAND ROAD. THE CONTRACTOR WILL ENSURE THE GATE IS CLOSED AND LOCKED AT THE END OF EACH DAY.

THE INSTALLATION OF THE PROPOSED LIGHTING HOMERUN CABLES THROUGH OR ACROSS THE HAUL ROUTE WILL REQUIRE COORDINATION BETWEEN CONTRACTORS AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR LABOR OR MATERIAL ASSOCIATED WITH THE COORDINATION OR INSTALLATION FOR WORK BEYOND THAT IS SPECIFIED.

ALL WORK ASSOCIATED WITH THE PROPOSED HAUL ROUTE SHALL BE CONSIDERED INCIDENTAL TO AR150540 - HAUL ROUTE.

THE PROPOSED CONSTRUCTION WILL DISTURB LESS THAN 1 ACRES OF LAND, THEREFORE AN EROSION CONTROL PLAN AND AN NPDES

OPERATIONAL LIGHTING

ALL EXISTING AIRFIELD CIRCUITS SHALL BE OPERABLE DURING NIGHTFALL. CONTRACTOR SHALL PROVIDE ALL TEMPORARY WORK, AS NECESSARY, TO MAINTAIN OPERATION OF THE AIRFIELD LIGHTING SYSTEMS AT NIGHTFALL. ALL WORK SHALL BE COORDINATED WITH THE AIRPORT MANAGER AND SHALL BE COORDINATED TO MINIMIZE DOWN TIME TO THE RESPECTIVE LIGHTING SYSTEMS.

CRITICAL POINT DATA CRITICAL POINT 1

LATITUDE - 41' 12' 12.08227" LONGITUDE - 89' 57' 37.36973" ELEVATION - 854.90

CRITICAL POINT 2


LATITUDE - 41' 12' 10.29760" LONGITUDE - 89° 57' 42.21939" ELEVATION ~ 855.10

EXISTING IMPROVEMENTS PROPOSED IMPROVEMENTS EXISTING BUILDINGS

> PROPOSED EQUIPMENT/VEHICLE PARKING AREA & HAUL ROUTE

 EXISTING AIRPORT PROPERTY LINE LIGHTED BARRICADES

HORIZONTAL/VERTICAL CONTROL



HEIGHT OF CONSTRUCTION EQUIPMENT HAUL ROUTE AND EQUIPMENT PARKING

ELECTRICAL LEGEND — SCHEMATIC				
	NORMALLY CLOSED (N.C.) CONTACT			
(5)	STARTER COIL. * = STARTER NUMBER			
à	OVERLOAD RELAY CONTACT			
(R)	CONTROL RELAY, * = CONTROL RELAY NUMBER			
(R)	RELAY, * = RELAY NUMBER			
	TOGGLE SWITCH / 2 POSITION SWITCH			
OFF AUTO	2-Position selector switch			
HAND OFF AUTO XOO I OOX	3-Position selector switch (H-O-A Shown)			
1	2 POLE DISCONNECT SWITCH			
111	3 POLE DISCONNECT SWITCH			
`` —	PHOTOCELL			
-0-	TERMINAL BLOCK, * = TERMINAL NUMBER			
	DEVICE TERMINAL, * == DEVICE TERMINAL NUMBER			
	INTERNAL PANEL WIRING			
	FIELD WIRING			
	FUSE			
GND	GROUND BUS OR TERMINAL			
S/N	NEUTRAL BUS			
- -	GROUND, GROUND ROD			
000	INDUSTRIAL CONTROL RELAY OR LIGHTING CONTACTOR			
CCR	S1 CUTOUT HANDLE REMOVED			
CCR	S1 CUTOUT HANDLE INSERTED			
of to	n.o. Thermal Switch			
ुरु	N.C. THERMAL SWITCH			
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				

	ELECTRICAL ABBREVIATIONS		
AF.F.	ABOVE FINSHED FLOOR		
A, AMP	AMPERES		
ATS	AUTOMATIC TRANSFER SWITCH		
AWG	AMERICAN WIRE GAUGE		
BKR	BREAKER		
C	CONDUIT		
C8	CIRCUIT BREAKER		
скт	CIRCUIT		
ÇR	CONTROL RELAY		
CU	COPPER		
DPDT	DOUBLE POLE DOUBLE THROW		
DPST	DOUBLE POLE SINGLE THROW		
EM	EMERGENCY		
EMT	ELECTRICAL METALLIC TUBING		
ENCL	ENCLOSURE		
EP	EXPLOSION PROOF		
ES	EMERGENCY STOP		
ETL	INTERTEX — ELECTRICAL TESTING LABS		
ETM	ELAPSE TIME METER		
GFCI	GROUND FAULT CIRCUIT INTERRUPTER		
GFI	GROUND FAULT INTERRUPTER		
GND	GROUND		
GRSC	GALVANIZED RIGID STEEL CONDUIT		
HID	HIGH INTENSITY DISCHARGE		
HOA	HAND OFF AUTOMATIC		
HP	HORSEPOWER		
HPS	HIGH PRESSURE SODIUM		
	JUNCTION BOX		
KVA	KILOVOLT AMPERE(S)		
KW	KILOWATTS		
fc	UGHTING CONTACTOR		
LTFMC	LIQUID TIGHT FLEXIBLE METAL CONDUIT (UL LISTED)		
LTG	LIGHTING		
ሆ	LIGHTING PANEL		
MAX	MAXIMUM		
MCB	MAIN CIRCUIT BREAKER		
MCM	THOUSAND CIRCLUAR MIL.		
MDP	MAIN DISTRIBUTION PANEL		
NFR	MANUFACTURER		
WH	METAL HALIDE		
MIN	MINIMUM		
WLO	MAIN LUGS ONLY		
NEC	NATIONAL ELECTRICAL CODE (NFPA 70)		
NC	NORMALLY CLOSED		
NO	NORMALLY OPEN		
NTS	NOT TO SCALE		
OHE	OVERHEAD ELECTRIC		
	OKTOLOGO		

OL OVERLOAD

EU	ECTRICAL ABBREVIATIONS (CONTINUED)		
PB	PULL BOX		
PC	PHOTO CELL		
P08	POWER DISTRIBUTION BLOCK		
PNL	PANEL		
RCPT	RECEPTACLE		
R	RELAY		
s	STARTER		
SPD	SURGE PROTECTION DEVICE		
SPST	SINGLE POLE SINGLE THROW		
TVSS	Transient voltage surge suppressor		
TYP	TYPICAL		
UG	UNDERGROUND		
UGE	UNDERGROUND ELECTRIC		
UL	Underwriter's laboratories		
٧	VOLTS		
₩/	WITH		
W /0	without		
WP	WEATHER PROOF		
XFER	TRANSFER		
XFMR	TRANSFORMER		

	AIRPORT EQUIPMENT ABBREVIATIONS
CCR	CONSTANT CURRENT REGULATOR
MIRL	MEDIUM INTENSITY RUNWAY LIGHT
MITL.	MEDIUM INTENSITY TAXIWAY LIGHT
NDB	NON-DIRECTIONAL BEACON
PAPI	PRECISION APPROACH PATH INDICATOR
PLASI	PULSE LIGHT APPROACH SLOPE INDICATOR
REIL	RUNWAY END IDENTIFIER LIGHT
VADI	VISUAL APPROACH DESCENT INDICATOR
VASI	VISUAL APPROACH SLOPE INDICATOR
WC	WIND CONE

	electrical legend — Plans	
	CONDUIT (EXPOSED)	
	CONDUIT OR UNIT DUCT (CONCEALED OR BURIED)	
	DUCT	
E	BURIED/UNDERGROUND ELECTRIC	
UGE	UNDERGROUND ELECTRIC	
3H0	OVERHEAD ELECTRIC	
¥	POLE MOUNTED HID FIXTURE	
0	DUPLEX CONVENIENCE RECEPTACLE, 120V, SINGLE PHASE, GROUNDING TYPE, 48° A.F.F. EXCEPT AS NOTED	
ф0·	WALL OR CEILING MIT'D, JUNCTION BOX, CONFIGURATION VARIES WITH USE	
Ō	SINGLE THROW DISCONNECT SWITCH	
rZ)	SINGLE THROW, FUSIBLE DISCONNECT SWITCH	
r(28)	ENCLOSED CIRCUIT BREAKER	
CED .	CONTROL PANEL	
Ó	MOTOR. ESTIMATED H.P. AS INDICATED.	
0	MOTOR	
T	TRANSFORMER	
	ELECTRIC UTILITY METER	
	ENCLOSURE	
	CIRCUIT BREAKER PANEL-SEE SCHEDULES	
•	GROUND ROD	
-#4	LONG SLASHES INDICATE NEUTRAL SHORT SLASHES INDICATE HOT OR SWITCHED LEG. G = SEPARATE GROUND WIRE,	
	Honerun to Panel Pril a indicates panel 1,3,5 indicates circuit numbers	
\$	SINGLE POLE SWITCH	
\$ OR \$1	Fractional HP Starter	
©	CONTACTOR	
	SURFACE MOUNTED OR CHAIN HUNG FLUORESCENT FIXTURE	
юо	WALL OR CEILING INT'D. INCANDESCENT OR HID FIXTURE.	

- 1. ALL ELECTRICAL EQUIPMENT SHALL BE INSTALLED IN CONFORMANCE WITH NFPA 70 - NATIONAL ELECTRICAL CODE (NEC) MOST CURRENT ISSUE IN FORCE, THE RESPECTIVE EQUIPMENT MANUFACTURER'S DIRECTIONS AND ALL OTHER APPLICABLE LOCAL CODES, LAWS, ORDINANCES, AND REQUIREMENTS IN FORCE. ANY INSTALLATIONS WHICH VOID THE U.L. LISTING, ETL LISTING (OR OTHER THIRD PARTY LISTING) AND/OR THE MANUFACTURER'S WARRANTY OF A DEVICE WILL NOT
- 2. CONTRACTOR SHALL COORDINATE WORK AND ANY POWER OUTAGES WITH THE RESPECTIVE FACILITY OWNER PERSONNEL AND THE AIRPORT MANAGER.
- 3. COLOR CODE PHASE AND NEUTRAL CONDUCTOR INSULATION FOR NO. 6 AWG OR SMALLER. PROVIDE COLORED INSULATION OR COLORED MARKING TAPE FOR PHASE AND NEUTRAL CONDUCTORS FOR NO. 4 AWG AND LARGER. INSULATED GROUND CONDUCTORS SHALL HAVE GREEN COLORED INSULATION FOR ALL CONDUCTOR AWG AND/OR KCMIL TO COMPLY WITH NEC 250.119. NEUTRAL CONDUCTORS SHALL HAVE WHITE COLORED INSULATION FOR NO. 6 AWG AND SMALLER TO MEET THE REQUIREMENTS OF NEC 200.6. STANDARD COLORS FOR POWER WIRING AND BRANCH CIRCUITS SHALL BE AS FOLLOWS:

120/240 VAC, 1 PHASE, 3 WIRE PHASE A PHASE B RED NEUTRAL WHITE GROUND GREEN


CONSTRUCT


HANSON

ELECTRICAL LEGEND AND ABBREVIATIONS

KEWANEE MUNICIPAL AIRPORT KEWANEE, HENRY COUNTY, ILLINOIS

KE008





KE008

NOTES

- ALL VAULT WORK AND/OR POWER OUTAGES SHALL BE COORDINATED WITH THE AIRPORT MANAGER.
- 2. CONTRACTOR SHALL FIELD VERIFY EXISTING CONDITIONS TO CONFIRM POWER & CONTROL CIRCUITS.
- 3. EXISTING AIRFIELD CIRCUITS SHALL BE LOCATED, IDENTIFIED, DISCONNECTED, REROUTED & RECONNECTED TO THE NEW VAULT AS DETAILED HEREIN. ALL EXISTING AIRFIELD LIGHTING SYSTEMS SHALL BE OPERABLE DURING NIGHTFALL, CONTRACTOR SHALL PROVIDE ALL TEMPORARY WORK AS NECESSARY TO MAINTAIN OPERATION OF THE AIRFIELD LIGHTING SYSTEMS AT NIGHTFALL. CONTRACTOR SHALL COORDINATE TRANSFER OF EXISTING AIRFIELD CIRCUITS TO MINIMIZE DOWN
- 4. CCR DENOTES CONSTANT CURRENT REGULATOR.
- 5. PLASI'S ARE WIRED FOR CONTINUOUS OPERATION 24 HOURS A DAY. RELAY CONTACTS MIGHT BE BYPASSED. FIELD VERIFY AS NECESSARY.

KEWANEE MUNICIPAL AIRPORT KEWANEE, HENRY COUNTY, ILLINOIS


HANSON

EXSITING VAULT ELECTRICAL ONE-LINE DIAGRAM

CONSTRUCT VAULT

6 6 of 27 sheets

EXISTING VAULT ELECTRICAL ONE-LINE DIAGRAM




THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 1-800-892-0123.

NOTE

ABANDONMENT AND/OR REMOVAL OF EXISTING RUNWAY OR TAXIWAY LIGHTING CABLES SHALL BE INCIDENTAL TO ITEM AR108158 1/C NO. 8, 5KV, U.G. CABLE IN U.D.


KE008 LEGEND EXISTING PAVEMENT ---- EXISTING ELECTRICAL CABLES EXISTING ELECTRICAL DUCT --- PROPOSED 1/C NO. 8, 5KV, U.G. CABLE IN U.D. EXISTING STAKE MOUNTED TAXIWAY LIGHT EXISTING BASE MOUNTED TAXIWAY LIGHT EXISTING STAKE MOUNTED RUNWAY THRESHOLD LIGHT EXISTING STAKE MOUNTED RUNWAY LIGHT EXISTING BASE MOUNTED RUNWAY LIGHT EXISTING TAXI GUIDANCE SIGN



CONSTRUCT VAULT

HANSON

KEWANEE MUNICIPAL AIRPORT KEWANEE, HENRY COUNTY, ILLINOIS




KEWANEE MUNICIPAL AIRPORT KEWANEE, HENRY COUNTY, ILLINOIS

HANSON

PROPOSED ELECTRICAL PLAN A. 12+00 TO STA. 20+0

FULL SIZE SCALE: 1"= 30"



KEYED NOTES

- ELECTRIC UTILITY METER WITH SUPPORT HARDWARE PER SERVING ELECTRIC UTILITY COMPANY REQUIREMENTS
- 2 UTILITY SERVICE CONDUCTORS (BY UTILITY) IN 4" GRSC (BY CONTRACTOR) FROM UTILITY TRANSFORMER TO METER BASE. INCLUDE SPARE 4" GRSC PER UTILITY CO. REQUIREMENTS. CONTRACTOR SHALL FURNISH & INSTALL SERVICE CONDUCTORS & CONDUIT FROM METER BASE TO SERVICE PANEL. SEE "NEW VAULT ELECTRICAL ONE LINE DIAGRAM".
- 3 SERVICE PANEL A, SEE PANEL A SCHEDULE.
- 4 AC SURGE PROTECTOR/TVSS, SEE "NEW VAULT ELECTRICAL ONE LINE DIAGRAM."
- 5 2 #1/0 THWN, 1 #1/0 THWN NEUTRAL, 1 #4 GND IN 2" GRSC FROM SERVICE PANEL A TO PANEL B.
- 6 PANEL B, SEE PANEL B SCHEDULE.
- 7 LIGHTING CONTACTOR PANEL. SEE AIRFIELD LIGHTING WIRING SCHEMATIC AND LIGHTING CONTACTOR PANEL DETAIL
- 8 L-854 RADIO CONTROL UNIT. EXTEND RADIO ANTENNA CABLE AND MOUNT ANTENNA ON THE ROOF FOR PROPER
- RADIO RELAY INTERFACE PANEL WITH PHOTOCELL BYPASS SWITCH FOR RUNWAY 1-19 CCR, TAXIWAY CCR, AND RUNWAY 18-36 CCR. SEE AIRFIELD LIGHTING WIRING SCHEMATIC FOR WIRING REQUIREMENTS. MOUNT PHOTOCELL ON ROOF. FIELD VERIFY LOCATION FOR PROPER CONTROL AND OPERATION
- ELECTRIC WALL HEATER EH-1, 3000 WATT, 240 VAC, 1 PHASE, SUITABLE FOR SURFACE MOUNTING WITH INTEGRAL THERMOSTAT, Q-MARK MODEL CWH3407, OR APPROVED EQUAL. BOTTOM OF HEATER SHALL BE 3" (MIN.) ABOVE THE UPPER ELECTRICAL WIREWAY.
- [1] ELECTRIC WALL HEATER EH-2, 2000 WAIT, 240 VAC, 1 PHASE, SUITABLE FOR SURFACE MOUNTING WITH INTEGRAL THERMOSTAT, Q-MARK MODEL CWH3404, OR APPROVED EQUAL BOTTOM OF HEATER SHALL BE 3" (MIN.) ABOVE THE UPPER ELECTRICAL WIREWAY. COORDINATE WITH CCR INSTALLATION & FAN INSTALLATION. LOCATE HEATER ON WALL SUCH THAT IT IS NOT DIRECTLY BEHIND CCR.
- EXHAUST FAN EF-1, 2000 CFM AT .25" STATIC PRESSURE WITH ½ HP, 120 VAC MOTOR, COOK MODEL 20S10D, OR APPROVED EQUAL. INCLUDE WALL HOUSING WITH GUARD, GRAVITY BACK DRAFT DAMPER, ALUMINUM WEATHER-HOOD PAINTED TO MATCH BUILDING EXTERIOR, STAINLESS STEEL INSECT SCREEN, AND FRACTIONAL HP ELECTRICAL DISCONNECT. INSTALL FAN AS HIGH AS POSSIBLE. PROVIDE 120 VAC THERMOSTAT WITH CONTACTOR AND AUTO-OFF-MANUAL CONTROL SWITCH AT 48" AFF. MOUNT THERMOSTAT ON 2" THICK INSULATED BASE. SEE EXHAUST FAN CONTROL SCHEMATIC FOR WIRING REQUIREMENTS.
- 13 INTAKE LOUVER L-1, 24" WIDE BY 48" HIGH INTAKE LOUVER WITH STAINLESS STEEL INSECT SCREEN, 120 VAC MOTORIZED DAMPER WITH LIMIT SWITCH, KYNAR FINISH MATCHING BUILDING EXTERIOR, RUSKIN MODEL ELF375DX, OR APPROVED EQUAL. SEE EXHAUST FAN CONTROL SCHEMATIC FOR WIRING REQUIREMENTS.
- 6" BY 6" LOW VOLTAGE WIREWAY. LABEL "LOW VOLTAGE" EVERY 4 FEET. INSTALL ABOVE HIGH VOLTAGE WIREWAY.
- 6" BY 6" HIGH VOLTAGE WIREWAY. LABEL "HIGH VOLTAGE" EVERY 4 FEET. INSTALL BELOW LOW VOLTAGE WIREWAY.
- 16 RUNWAY 1-19 CONSTANT CURRENT REGULATOR. SEE GENERAL NOTE 1
- 17 RUNWAY 9-27 CONSTANT CURRENT REGULATOR. SEE GENERAL NOTE 1.
- 18 TAXIWAY CONSTANT CURRENT REGULATOR, SEE GENERAL NOTE 1.
- 19 SERIES PLUG CUTOUT TYPE S-1 WITH ENCLOSURE. SEE GENERAL NOTES 1 AND 2.
- 20 4-4" GRSC FROM LOW VOLTAGE WIREWAY TO LOW VOLTAGE HANDHOLE.
- 21 3-4" GRSC FROM HIGH VOLTAGE WIREWAY TO HIGH VOLTAGE HANDHOLE.
- 22 BOOST TRANSFORMERS. SEE ELEVATION VIEW.
- 23 VEGETATION BARRIER CONSISTING OF A MIN. 3" PEA GRAVEL SURFACE OVER FILTER OR LANDSCAPING FABRIC. PROPOSED SURFACE TREATMENT WILL COVER ENTIRE AREA BENEATH VAULT STRUCTURE AS WELL AS 18" AROUND THE PERIMETER OF THE BUILDING EDGE. THE STONE AND FABRIC AS WELL AS ANY EQUIPMENT AND LABOR REQUIRED TO COMPLETE THIS TASK WILL BE CONSIDERED INCIDENTAL TO THE INSTALLATION OF THE PROPOSED ELECTRICAL VAULT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- ENTRANCE PAD CONSTRUCTED OF 6" CONCRETE SLAB W/6X6-W5XW5 WELDED WIRE FABRIC ON A COMPACTED SUBGRADE. MINIMUM DIMENSIONS OF PAD WILL BE 7'WX5'DX6"H, SLOPED AT A MIN. OF 0.5"/FT AWAY FROM THE VAULT ENTRANCE. PCC USED TO CONSTRUCT THE PAD WILL CONFORM TO ITEM 61D. ALL MATERIALS, LABOR AND EQUIPMENT USED TO CONSTRUCT THE PAD INCLUDING ANY GRADING REQUIRED WILL BE CONSIDERED INCIDENTAL TO THE CONSTRUCTION OF THE PROPOSED ELECTRICAL VAULT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

GENERAL NOTES


- SEE "NEW VAULT ELECTRICAL ONE LINE DIAGRAM" FOR LOW VOLTAGE INPUT POWER WIRING REQUIREMENTS TO CCR'S (CONSTANT CURRENT REGULATORS). SEE "HIGH VOLTAGE WIRING SCHEMATIC" FOR CCR OUTPUT WIRING REQUIREMENTS. SEE "AIRFIELD LIGHTING WIRING SCHEMATIC" FOR CCR CONTROL WIRING REQUIREMENTS. PROVIDE 5 FEET MINIMUM CLEAR WORKING SPACE IN FRONT OF EACH CCR AND EACH SERIES PLUG CUTOUT.
- 2. CONSTANT CURRENT REGULATORS AND THEIR RESPECTIVE SERIES PLUG CUTOUTS SHALL BE CLEARLY LABELED TO IDENTIFY THE RESPECTIVE REGULATOR DESIGNATION, RUNWAY OR TAXIWAY SERVED, POWER SOURCE OR CIRCUIT, AND VOLTAGE SYSTEM.
- 3. SEE ELEVATION VIEWS FOR ADDITIONAL INFORMATION ON PROPOSED EQUIPMENT LAYOUTS.
- 4. COORDINATE CONDUIT & SLEEVE ENTRANCES THROUGH FLOOR SLAB AND WALLS.

KE008

COUNTY, ILLINOIS KEWANEE MUNI KEWANEE, HENRY

HAN M

CONSTRUCT VAULT



VAULT LIGHTING & RECEPTACLE PLAN

SCALE 1/2*=1'-0*
1 0 2 4 FEET

	·····	LIGHTING FIXTURE SO	JUCOULE		Olive Charles and the control of the	
TXT. TYPE	DESCRIPTION	MANUFACTURER & CATALOG NO.	LAMPS/ WATTS	VOLTS	MOUNTING	REMARKS
1	4 FT. WET LOCATION LISTED ENCLOSED AND GASKETED INDUSTRIAL FUNDRESCENT LIGHT FIXTURE, IMPACT RESISTANT, UV RESISTANT REINFORCED POLYESTER FIBERGLASS HOUSING, HIGH IMPACT ACRYLIC DIFFUSER, RAPID START COLD WEATHER O DEG. F. ELECTRONIC BALLAST WITH LESS THAN OR EQUAL TO 10% THD.	UTHONIA: DMW-2-32-AR120- CW-GEB10RS-WLF	2-32W TB 4100K 59 TOTAL INPUT WATTS	120	SURFACE TO HARD CEILING	PROVIDE WET LOCATION FITTINGS INSTALLED IN TOF OF FIXTURE.
1 A	SAME AS F1 EXCEPT PROVIDE AN EMERGENCY BALLAST CAPABLE OF OPERATING 2 LAMPS FOR 90 MINUTES AT 1100-1400 TOTAL LUMENS, BODINE #B50ST. NOTE BALLAST WILL HAVE TO BE REMOTE MOUNTED NEAR FIXTURE AS INDICATED ON THE PLANS.	CW-GEB10RS-WLF	2-32W T8 4100K 59 TOTAL INPUT WATTS	120	SURFACE TO HARD CEILING	PROVIDE WET LOCATION FITTINGS INSTALLED IN TOP OF FIXTURE.
2	COMPACT FLUORESCENT WALL—PAK, ONE PIECE INJECTION MOLDED UV STABILIZED POLYCARBONATE HOUSING, HIGH PERFORMANCE SPECULAR ANODIZED SEGMENTED REFLECTOR, ONE PIECE HIGH TEMPURATURE SILICONE GASKET, MEDIUM BRONZE FINISH, HIGH POWERFACTOR ELECTRONIC BALLAST WITH LESS THAN OR EQUAL TO 10% THD, UL USTED FOR WET LOCATIONS, FUSED.	TWA-42TRT-120-SF-	1-42W TRT 4100K 47 TOTAL INPUT WATTS		SURFACE TO WALL ABOVE EXTERIOR DOOR APPROXIMATELY 4 INCHES ABOVE TOP OF DOOR FRAME.	CONNECT TO WALL SWITCH LOCATED ON THE INSIDE O THE BUILDING.

 $\frac{\text{NOTE}}{\text{15 AMP & 20 AMP BRANCH CIRCUITS FOR LIGHTING & RECEPTACLES SHALL USE $$\#12 AWG THWN (MIN.).}$


KEWANEE, HENRY COUNTY, ILLINOIS


Seets 1.2"=1"-0"
Seets 1.2"=1"-0"
Seets 04/01/08
LAYOUT KNL 08/25/05
DRAWN NV 09/25/05

Hanson Professional Services Inc.
3125 Cardy 17ail, Suite 100
indiangolist, Indian 48214
Offices hattorwide

CONSTRUCT VAULT


VAULT LIGHTING AND RECEPTACLE PLAN





13 of 27 sheets

9. LIFMC DENOTES LIQUID TIGHT FLEXIBLE METAL CONDUIT UL LISTED. SUNLIGHT RESISTANT, & SUITABLE FOR GROUNDING.



14

14 of 27 sheets

CONSTRUCT

KEWANEE MUNICIPAL AIRPORT KEWANEE, HENRY COUNTY, ILLINOIS

HANSON

PANEL B SCHEDULE # DUTY
VAULT HEATER EH-1 15A 2P VAULT HEATER EH-2 9 SPARE
11 SPARE
13 SPARE
15 SPARE
17 BLANK
19 BLANK
21 BLANK
23 BLANK
25 BLANK
27 BLANK
29 BLANK 15A 1P 20A 1P 20A 1P GND_ (\$/N) 225 AMP, 120/240 VAC, 1 PHASE, 3 WIRE, 30 CIRCUIT PANELBOARD WITH MAIN LUGS IN A NEMA 1 ENCLOSURE. INCLUDE SEPARATE GROUND BAR KITS. ALL BRANCH BREAKERS SHALL BE BOLT-ON TYPE WITH 22,000 AIC AT 120/240 VAC. PANELBOARD SHALL BE SQUARE D CAT. NO.

NOTES

- I. PANELBOARD BUS SHALL BE COPPER. NEUTRAL BUS SHALL BE COPPER. EQUIPMENT GROUND BARS SHALL BE COPPER.
- 2. INCLUDE ENGRAVED PHENOLIC LEGEND PLATE LABELED "PANEL B, 120/240 VAC, 1 PHASE, 3 WIRE, FED FROM SERVICE PANEL A".

1. PANELBOARD BUS SHALL BE COPPER. NEUTRAL BUS SHALL BE COPPER. EQUIPMENT GROUND BARS SHALL BE COPPER. NOTE ONE OF THE EQUIPMENT GROUND BARS SHALL ACCOMMODATE LINE & TAP GROUND WIRES UP TO \$1/0 AWG. THE OTHER GROUND BAR SHALL ACCOMMODATE A #1/0 AWG LINE/BONDING JUMPER & TAP GROUND CONDUCTORS FROM #14 AWG TO #6 AWG.

GNO SZN GNO

400 AMP, 120/240 VAC, 1 PHASE, 3 WIRE, 42 CIRCUIT PANELBOARD WITH 400 AMP, 2 POLE MAIN BREAKER WITH 22,000 AIC AT 240 VAC IN A

NEMA 1 ENCLOSURE. INCLUDE SEPARATE GROUND BAR KITS. ALL BRANCH BREAKERS SHALL BE BOLT-ON TYPE WITH 22,000 AIC AT 120/240

VAC. PANELBOARD SHALL BE SQUARE D CAT. NO. NQOD42L400CU WITH NQOD4 MAIN BREAKER KIT AND Q4L2400 MAIN BREAKER IN A NEMA 1

SERVICE PANEL "A" SCHEDULE

20A 1P 20A 1P

PANELBOARD B

ENCLOSURE, OR APPROVED EQUAL

NOTES

RADIO CONTROL & PHOTOCELL
RUNWAY 9 PLASI
RUNWAY 27 PLASI
WINDCONE & WIND TEE
AIRPORT ROTATING BEACON

SIZE DUTY

60A 2P SURGE PROTECTOR/TVS

60A 2P RUNWY 9/27 CCR

60A 2P RUNWY 1/19 CCR

ANK

80A 2P TAXIWAY CCR

60A 2P SPARE

80A 2P SPARE 30A 2P SPARE

2. INCLUDE ENGRAVED PHENOLIC LEGEND PLATE LABELED "SERVICE PANEL A, 120/240 VAC, 1 PHASE, 3 WIRE". INCLUDE ADDITIONAL LEGEND PLATE FOR THE MAIN BREAKER LABELED "SERVICE BREAKER".

NOTES FOR FAN CONTROL SCHEMATIC

- 1. GROUND WIRES REQUIRED BUT NOT SHOWN FOR CLARITY.
- 2. ALL WIRING SHALL BE #12 THWN MINIMUM.
- 3. PROVIDE A NEMA 1 ENCLOSURE SIZED TO INSTALL THE CONTACTOR, HOA SELECTOR SWITCH & TERMINALS.
- PROVIDE LEGEND PLATE FOR THE CONTACTOR AND FRACTIONAL HP MOTOR STARTER IDENTIFYING THE LOAD SERVED 4. AND THE POWER SOURCE.

SIZE DUTY


15A 1P VAULT FAN
15A 1P VAULT INTERIOR LIGHTING
20A 1P VAULT RECEPTACLES
15A 1P VAULT EXTERIOR LIGHTING

BLANK


GND

- VERIFY MOTOR HORSEPOWERS AND FULL LOAD AMPS WITH THE RESPECTIVE MANUFACTURER. CONTRACTOR SHALL 5. COORDINATE MOTOR CIRCUIT BREAKER, CONTACTOR, FRACTIONAL HP STARTER, OVERLOADS, WIRE SIZES, CONDUIT SIZES, ETC. FOR THE RESPECTIVE EQUIPMENT FURNISHED, PER NEC & MANUFACTURER'S RECOMMENDATIONS. COORDINATE FAN & LOUVER INSTALLATION WITH BUILDING MFR.
- INTAKE LOUVERS SHALL OPEN AND EXHAUST FAN SHALL OPERATE WHEN SPACE TEMP EXCEEDS 85'F (ADJUSTABLE). EXHAUST FAN SHALL OPERATE ONLY WHEN DAMPER HAS PROVED "OPEN". IN MANUAL MODE DAMPER SHALL REMAIN 6. OPEN AND FAN SHALL RUN CONTINUOUSLY.

- 1 20VAC, NEMA SIZE 0 (MINIMUM), 1 POLE, FULL VOLTAGE CONTACTOR IN A NEMA 1 ENCLOSURE, SQUARE D CLASS 8502, TYPE SBGSV02 OR APPROVED EQUAL. INCLUDE H-O-A SELECTOR SWITCH WITH EACH CONTACTOR.
- (2) FRACTIONAL HORSEPOWER MOTOR MANUAL STARTER, SQUARE D MANUAL STARTER WITH HANDLE/GUARD/LOCK OFF, IN NEMA 1 ENCLOSURE CLASS 2510, TYPE FG5 OR APPROVED EQUAL. INCLUDE MELTING ALLOY TYPE THERMAL OVERLOADS SIZED AS REQUIRED TO PROTECT THE RESPECTIVE MOTOR. 120VAC MOTORS SHALL HAVE SINGLE POLE STARTERS.



EXHAUST FAN CONTROL SCHEMATIC




16

HIGH

COUNTY, ILLINO


KEWANEE MUNICIPAL KEWANEE, HENRY COUN


AIRPORT



AIRFIELD LIGHTING CONTROL SCHEMATIC

17 of 27 sheets





KEWANEE MUNICIPAL AIRPORT KEWANEE, HENRY COUNTY, ILLINOIS

HANSON

LIGHTING CONTACTC PANEL DETAIL

CONSTRUCT VAULT

VAULT LEGEND PLATE SCHEDULE

CUTOUT ENCLOSURE FOR RUNWAY RUNWAY 1-19 CUTOUT CUTOUT ENCLOUSRE FOR TAXIWAY TAXIWAY CUTOUT

CUTOUT ENCLOSURE FOR RUNWAY

EACH CUTOUT INPUT SIDE

EACH CUTOUT OUTPUT SIDE

EACH CUTOUT ENCLOSURE

CONTACTOR FOR EXHAUST FAN

CONNECTION

CONNECTION

RUNWAY 9-27 CUTOUT INPUT

> OUTPUT CAUTION OPERATE

CCR SHUT OFF EXHAUST FAN CONTACTOR

RADIO INTERFACE PANEL FOR RADIO RELAY INTERFACE CONTROL PANEL RUNWAYS & TAXIWAY LIGHTING CONTACTOR PANEL FOR LIGHTING CONTACTOR PANEL AIRFIELD LIGHTING EQUIPMENT

BOOST TRANSFORMER FOR RUNWAY RWY 9 PLASI BOOST TRANSFORMER FOR RUNWAY RWY 27 PLASI

27 PLASI BOOST TRANSFORMER FOR WIND CONE WIND CONE & WIND TEE


LOW VOLTAGE LOW VOLTAGE WIREWAY (PROVIDE 4 LEGEND PLATES 1/2" HIGH BLACK LETTERS WHITE BACKGROUND)

HIGH VOLTAGE WIREWAY (PROVIDE 4 HIGH VOLTAGE LEGEND PLATES 1/2" HIGH BLACK LETTERS WHITE BACKGROUND)


VAULT GROUND BUS VAULT GROUND BUS (PROVIDE 4 LEGEND PLATES 1/2" HIGH WHITE LETTERS GREEN BACKGROUND)

NOTE: LEGEND PLATES SHALL BE WEATHERPROOF ENGRAVED PLASTIC OR PHENOLIC MATERIAL, 1/4" HIGH BLACK LETTERS ON A WHITE BACKGROUND UNLESS NOTED OTHERWISE. SECURE WITH WEATHERPROOF ADHESIVE AND MACHINE SCREWS. FURNISH ADDITIONAL LEGEND PLATES WHERE REQUIRED BY CODE, FOR ADDITIONAL EQUIPMENT, AS DETAILED HEREIN ON THE PLANS, AND AS NOTED IN THE SPECIAL PROVISION SPECIFICATIONS.

FURNISH & INSTALL A WEATHERPROOF WARNING LABEL FOR EACH SAFETY SWITCH, PANELBOARD, LOAD CENTER, CUTOUT, & CONTROL PANEL TO WARN PERSONS OF POTENTIAL ELECTRIC ARC FLASH HAZARDS, PER THE REQUIREMENTS OF NEC 110.16 "FLASH PROTECTION", LABELS SHALL BE HAZARD COMMUNICATION SYSTEMS, LLC (190 OLD MILFORD RD., BOX 1174, MILFORD, PA 18337, PHONE: 1-877-748-0244) PART NO. H6010-9VWHBJ OR APPROVED EQUAL.




PROVIDE WARNING SIGN ON VAULT EXTERIOR DOORS LABELED "DANGER - HIGH VOLTAGE - KEEP OUT" PER THE REQUIREMENTS OF NEC 110.34 (C).



CONFIRM WIRING WITH RESPECTIVE TRANSFORMER MFR.

120 VAC TO 132 VAC BOOST TRANSFORMER CONNECTION DIAGRAM FOR SQUARE D CAT. NO. 250SV43B OR CAT. NO. 500SV43B TRANSFORMER




120 VAC TO 144 VAC BOOST TRANSFORMER CONNECTION DIAGRAM FOR SQUARE D CAT. NO. 500SV43B TRANSFORMER

KE008

KEWANEE MUNICIPAL AIRPORT KEWANEE, HENRY COUNTY, ILLINOIS


HANSON


CONSTRUCT VAULT



CABLE TO GROUND ROD

CABLE TO GROUND ROD






CABLE TO GROUND ROD

CABLE TO CABLE HORIZONTAL PARALLEL TAP

DETAIL NOTES

- 1. EXOTHERMIC WELDS SHALL BE CADWELD AS MANUFACTURED BY ERICO PRODUCTS, SOLON, OHIO OR THERMOWELD AS MANUFACTURED BY CONTINENTAL INDUSTRIES, TULSA, OKLAHOMA. VERIFY PROPER SIZES, TYPES, AND REQUIREMENTS FOR THE RESPECTIVE APPLICATION WITH THE MANUFACTURER, AND INSTALL PER
- FOR APPLICATIONS TO METAL SURFACES THAT ARE LESS THAN 3/16" THICK CONTACT THE EXOTHERMIC WELD MANUFACTURER FOR DIRECTION AND INSTRUCTION ON EXOTHERMIC WELD INSTALLATION TO THE RESPECTIVE
- 3. FOR APPLICATIONS TO GALVANIZED STEEL OR PAINTED STEEL, REMOVE GALVANIZING AND/OR PAINT & CLEAN THE SURFACE TO EXPOSE BARE STEEL BEFORE MAKING EXOTHERMIC WELD CONNECTION.
- 4. INDIMIDUAL GROUNDING ELECTRODE CONDUCTORS SHALL NOT BE INSTALLED IN METAL CONDUIT. INSTALL GROUNDING ELECTRODE CONDUCTORS IN SCHED 40 PVC CONDUIT AS REQUIRED IN FOUNDATIONS, FOR PROTECTION, WHERE ENTERING ENCLOSURES, ETC.

EXOTHERMIC WELD DETAILS




2 HOLE LONG BARREL COMPRESSION LUG TABLE				
WIRE SIZE	BURNDY CAT. NO.	THOMAS & BETTS CAT. NO.		
#6 AWG STRANDED	YA6C-2TC38	256-30695-1158		
#4 AWG STRANDED	YA4C-2TC38	256-30695-1159		
#2 AWG STRANDED	YA2C-2TC38	256~30695~1160		
#2 AWG SOLID	YA3C-2TC38	256-30695-1160		
#1/0 AWG STRANDED	YA252TC38	256-30695-1162		
#2/0 AWG STRANDED	YA26~2TC38	256-30695-1116		
#3/0 AWG STRANDED	YA27-2TC38	54816BE		

NOTES


- 1. ALL CONNECTIONS TO GROUND BUS BAR SHALL BE WITH 2 HOLE TONGUE LONG BARREL COMPRESSION LUGS BOLTED TO THE BUS BAR.
- 2. GROUND WIRE CONNECTIONS TO EQUIPMENT SHALL BE WITH 2 HOLE TONGUE LONG BARREL COMPRESSION LUGS BOLTED TO THE DEVICE OR WITH THE RESPECTIVE EQUIPT MANUFACTURER'S LUG OR TERMINAL WHERE APPLICABLE.
- 3. GROUNDING ELECTRODE CONDUCTORS, BONDING JUMPERS, & INDIVIDUAL GROUND WIRES SHALL NOT BE INSTALLED IN METAL CONDUIT. WHERE PLASTIC CONDUIT IS USED FOR INDMOUAL GROUND WIRES, DO NOT COMPLETELY ENCIRCLE THE CONDUIT WITH FERROUS AND/OR MAGNETIC MATERIALS. WHERE METAL CLAMPS ARE INSTALLED USE NYLON BOLTS, NUTS, WASHERS, & SPACERS TO INTERRUPT A COMPLETE METALLIC APTH FROM ENCIRCLING THE CONDUIT.
- 4. ALL CONNECTIONS SHALL BE COATED WITH A CORROSION PREVENTATIVE COMPOUND (SANCHEM INC. NO-OX-ID "A-SPECIAL", BURNDY PENETROX E. OR EQUAL) BEFORE JOINING. ALL COPPER BUS BARS SHALL BE CLEANED PRIOR TO MAKING CONNECTIONS TO REMOVE SURFACE OXIDATION. CLEAN SURFACES, OF RESPECTIVE DEVICES TO BE BONDED, TO BARE METAL, PER NEC 250-12.

GROUNDING LUG CONNECTION DETAIL



LIDS FOR LOW VOLTAGE HANDHOLES SHALL BE LABELED "LOW VOLTAGE". LIDS FOR HIGH VOLTAGE HANDHOLES SHALL BE LABELED "HIGH VOLTAGE". COORDINATE LETTERING WITH MFR.

ELECTRICAL HANDHOLE DETAIL



NOTES:

- 1.) ALL DIMENSIONS ARE MINIMUM.
- 2.) INCLUDE DUCT SPACERS AS MANUFACTURED BY UNDERGROUND DEVICES INC., TO MAINTAIN PROPER SEPARATION OF CONDUITS.

CONCRETE ENCASED DUCT DETAIL


(3-WAY & 4-WAY SHOWN)

CONSTRUCT VAUL

ELECTRICAL AND GROUNDING DETAILS

HANSON

KEWANEE MUNICIPAL AIRPORT KEWANEE, HENRY COUNTY, ILLINOIS




WIND CONE ELEVATION DETAIL

COUNTY, ILLINOIS


KEWANEE MUNICIPAL AIRPORT KEWANEE, HENRY COUNTY, ILLING

- PLASI UNITS LOCATED ON RUNWAY 9-27 ARE EXISTING. A HEAVY DUTY 60 AMP, 2 POLE OR 3 POLE WITH SOLID NEUTRAL & GND, 600 VAC NOT FUSIBLE SAFETY SWITCH IN A NEMA 3R AND 12 ENCLOSURE SHALL BE FURNISHED & INSTALLED AT EACH PLASI. 6D AMP SAFETY SWITCH IS REQUIRED TO ACCOMMODATE #4 AWG OR \$2 AWG CONDUCTORS FOR LUG TERMINATIONS & WIRE BENDING SPACE. NEUTRAL SHALL BE BONDED TO GROUND IN SAFETY SWITCH & GND ROD SHALL BE INSTALLED TO CONFORM WITH NEC 250.32
- LIFMC DENOTES LIQUID TIGHT FLEXIBLE METAL CONDUIT UL LISTED, SUITABLE FOR GROUNDING, AND SUNLIGHT RESISTANT. NEC 350.6 NOTES LIQUID TIGHT FLEXIBLE METAL CONDUIT AND ASSOCIATED FITTINGS SHALL BE LISTED. DO NOT INSTALL LITTMC THAT IS NOT UL LISTED.
- CONTRACTOR SHALL FURNISH & INSTALL BOOST TRANSFORMERS FOR PLASI UNITS IN THE VAULT. BOOST TRANSFORMERS SHALL BE SIZED & CONNECTED TO PROVIDE THE PROPER VOLTAGE AT THE RESPECTIVE PLASI UNIT AS RECOMMENDED BY THE PLASI MANUFACTURER (DEVORE AVIATION CORPORATION, 6104 JEFFERSON BLVD, N.E., ALBUQUERQUE, NEW MEXICO 87109-3410, PHONE: 505-345-8713, FAX: 505-344-3835).
- INSTALLATION OF THE SAFETY SWITCH AND ASSOCIATED CONDUIT, WIRING, FITTINGS, GROUNDING, & ACCESSORIES FOR EACH PLASI UNIT SHALL BE PAID FOR UNDER ITEM AR125989 REFURBISH PLASI PER EACH.
- SEE SHEETS 38, 42, 43, & 49 FOR ADDITIONAL INFORMATION REGARDING PLASI CIRCUIT WIRING.




NOTE: SEE NEW ELECTRICAL ONE LINE DIAGRAM FOR VAULT AND PLASI FOR ADDITIONAL INFORMATION ON EQUIPMENT AND WIRING.

PLASI SAFETY SWITCH ELEVATION



PLASI FOUNDATION PLAN VIEW




PLASI ELEVATION

ALL WORK SHOWN ON THIS SHEET SHALL BE PAID FOR UNDER ITEM AR125989 -REFURBISH PLASI - PER EA.

KE008

CABLE TO GROUND ROD




CABLE TO SURFACE


DETAIL NOTES

- EXOTHERMIC WELDS SHALL BE CADWELD AS MANUFACTURED BY ERICO PRODUCTS, SOLON, OHIO, ULTRAWELD AS MANUFACTURED BY HARGER LIGHTNING PROTECTION & GROUNDING EQUIPMENT, GRAYSLAKE, IL, OR THERMOWELD AS MANUFACTURED BY CONTINENTAL INDUSTRIES, TULSA, OKLAHOMA. VERIFY PROPER SIZES, MOLDS, TYPES, AND REQUIREMENTS FOR THE RESPECTIVE APPLICATION WITH THE MANUFACTURER, AND INSTALL PER THEIR DIRECTIONS.
- 2. FOR APPLICATIONS TO GALVANIZED STEEL OR PAINTED STEEL, REMOVE GALVANIZING AND/OR PAINT & CLEAN THE SURFACE TO EXPOSE BARE STEEL BEFORE MAKING EXOTHERMIC WELD CONNECTION.
- 3. VERIFY EXOTHERMIC MOLDS ARE SUITABLE FOR USE WITH THE RESPECTIVE TYPE (SOLID OR STRANDED) & SIZE CONDUCTOR.

EXOTHERMIC WELD DETAILS




- REFERENCES TO THOMPSON ARE THOMPSON LIGHTNING PROTECTION INC., 901 SIBLEY MEMORIAL HWY, ST. PAUL, MN 55188, PHONE: 651-455-7661, 800-777-1230, FAX: 651-455-2545.
- VERIFY LIGHTNING PROTECTION COMPONENTS AND CATALOG NUMBERS WITH THE RESPECTIVE LIGHTNING PROTECTION EQUIPMENT



125 AMP, 120/240 VAC, 1 PHASE, 3 WIRE, 12 CIRCUIT LOAD CENTER WITH CONVERTIBLE MAIN LUGS IN A NEMA 3R RAIN PROOF ENCLOSURE, SQUARE D CAT. NO. Q0112L125GRB OR APPROVED EQUAL.

- INCLUDE EQUIPT GROUND BAR KIT.
- 2. ALL BREAKERS SHALL HAVE 10,000 AIC RATING AT 120/240 VAC.
- PHASE "A" SHALL BE SWITCHED THROUGH A LIGHTING CONTACTOR AT THE VAULT. PHASE "B" SHALL BE UNSWITCHED.
- INCLUDE ENGRAVED PHENOLIC LEGEND PLATE LABELED ARB PANEL, 120/240 VAC, 1PH, 3W, FED FROM VAULT.

NOTE: SEE SHEETS 38, 42, 43, & 46 FOR ADDITIONAL INFORMATION REGARDING WIRING FOR THE AIRPORT ROTATING BEACON CIRCUIT.



LIGHTNING PROTECTION DETAIL FOR AIRPORT ROTATING BEACON


> ALL WORK SHOWN ON THIS SHEET SHALL BE PAID FOR UNDER ITEM AR800591 -UPGRADE AIRPORT ROTATING BEACON -PER L.S.

HANSON

COUNTY, ILLINOIS

KEWANEE MUNI KEWANEE, HENRY

CONSTRUCT VAULT LIGHTNING PROTECTION DETAILS FOR BEACON



- CONTRACTOR SHALL KEEP A COPY OF THE LATEST NEC IN FORCE ON SITE AT ALL TIMES DURING CONSTRUCTION FOR USE AS A REFERENCE.
- CONTRACTOR SHALL COORDINATE WORK AND ANY POWER OUTAGES WITH THE RESPECTIVE FACILITY OWNER PERSONNEL AND THE AIRPORT MANAGER.
- THE CONTRACTOR SHALL ASCERTAIN THAT ALL LIGHTING SYSTEM COMPONENTS FURNISHED BY HIM, INCLUDING FAA APPROVED EQUIPMENT, ARE COMPATIBLE IN ALL RESPECTS WITH EACH OTHER AND THE REMAINDER OF THE NEW/EXISTING SYSTEM. ANY NONCOMPATIBLE COMPONENTS FURNISHED BY THIS CONTRACTOR SHALL BE REPLACED BY HIM AT NO ADDITIONAL COST TO THE AIRPORT SPONSOR WITH A SIMILAR UNIT, APPROVED BY THE ENGINEER (DIFFERENT MODEL OR DIFFERENT MANUFACTURER) THAT IS COMPATIBLE WITH THE REMAINDER OF THE
- IN CASE THE CONTRACTOR ELECTS TO FURNISH AND INSTALL AIRPORT LIGHTING EQUIPMENT REQUIRING ADDITIONAL WIRING, TRANSFORMERS, ADAPTORS, MOUNTINGS, ETC., TO THOSE SHOWN ON THE DRAWINGS AND/OR LISTED IN THE SPECIFICATION, ANY COST FOR THESE ITEMS SHALL BE INCIDENTAL TO THE EQUIPMENT COST.
- THE CONTRACTOR INSTALLED EQUIPMENT (INCLUDING FAA APPROVED) SHALL NOT GENERATE ANY ELECTROMAGNETIC INTERFERENCE IN THE EXISTING AND/OR NEW COMMUNICATIONS, WEATHER, AIR NAVIGATION, AND AIR TRAFFIC CONTROL EQUIPMENT. ANY EQUIPMENT GENERATING SUCH INTERFERENCE SHALL BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST WITH THE EQUIPMENT MEETING THE APPLICABLE SPECIFICATIONS AND NOT GENERATING ANY INTERFERENCE.
- WHEN A SPECIFIC TYPE, STYLE, CLASS, ETC. OF FAA APPROVED EQUIPMENT IS SPECIFIED ONLY THAT TYPE, STYLE, CLASS, WILL BE ACCEPTABLE, EVEN THOUGH EQUIPMENT OF OTHER TYPES STYLES, CLASSES, ETC. MAY BE APPROVED.
- ANY AND ALL INSTRUCTIONS FROM THE ENGINEER TO THE CONTRACTOR REGARDING CHANGES IN OR DEVIATIONS FROM THE PLANS AND SPECIFICATIONS SHALL BE IN WRITING WITH COPIES SENT TO THE AIRPORT SPONSOR AND THE FAA FIELD OFFICE (ADO/AFO). THE CONTRACTOR SHALL NOT ACCEPT ANY VERBAL INSTRUCTIONS FROM THE RESIDENT ENGINEER REGARDING ANY CHANGES FROM THE PLANS AND SPECIFICATIONS.
- A MINIMUM OF THREE COPIES OF THE INSTRUCTION BOOK SHALL BE SUPPLIED WITH EACH DIFFERENT TYPE OF EQUIPMENT. THE BOOKS DESCRIBING A MORE SOPHISTICATED TYPE OF EQUIPMENT, SUCH AS REGULATORS, PAPI, REIL, ETC. AS A MINIMUM SHALL CONTAIN THE FOLLOWING:
 - A. A DETAILED DESCRIPTION OF THE OVERALL EQUIPMENT AND ITS INDIVIDUAL
 - THEORY OF OPERATION INCLUDING THE FUNCTION OF EACH COMPONENT.
 - C. INSTALLATION INSTRUCTION.
 - START-UP INSTRUCTIONS.
 - PREVENTATIVE MAINTENANCE REQUIREMENTS.
 - CHART FOR TROUBLE-SHOOTING.
 - COMPLETE POWER AND CONTROL DETAILED WIRING DIAGRAM(S), SHOWING EACH CONDUCTOR/CONNECTION/COMPONENT - "BLACK" BOXES ARE NOT ACCEPTABLE. THE DIAGRAM OF THE NARRATIVE SHALL SHOW VOLTAGE/CURRENTS/WAVE SHAPES AT STRATEGIC LOCATIONS TO BE USED WHEN CHECKING AND/OR TROUBLE-SHOOTING THE EQUIPMENT. WHEN THE EQUIPMENT HAS SEVERAL MODES OF OPERATION, SUCH AS SEVERAL BRIGHTNESS STEPS, THESE PARAMETERS SHALL BE INDICATED FOR ALL
- PARTS LIST WHICH WILL INCLUDE ALL MAJOR AND MINOR COMPONENTS SUCH AS RESISTORS, DIODES, ETC. IT SHALL INCLUDE A COMPLETE NOMENCLATURE OF EACH COMPONENT AND, IF APPLICABLE, THE NAME OF ITS MANUFACTURER AND THE CATALOG NUMBER.
- SAFETY INSTRUCTIONS.

POWER AND CONTROL NOTES

- PROVIDE LEGEND PLATES FOR ALL ELECTRICAL EQUIPMENT TO IDENTIFY FUNCTION, CIRCUIT VOLTAGE AND PHASE. WHERE THE EQUIPMENT CONTAINS FUSES, ALSO IDENTIFY THE FUSE OR FUSE LINK AMPERE RATING. WHERE THE EQUIPMENT DOES NOT HAVE SUFFICIENT AREA TO INSTALL LEGEND PLATES, THE LEGEND PLATES SHALL BE INSTALLED ON THE WALL NEXT TO THE UNIT. LEGEND PLATES SHALL BE WEATHERPROOF ENGRAVED PLASTIC OR PHENOLIC MATERIAL, 1/4" HIGH BLACK LETTERS ON A WHITE BACKGROUND UNLESS NOTED OTHERWISE. SECURE WITH WEATHERPROOF ADHESIVE AND MACHINE SCREWS. FURNISH ADDITIONAL LEGEND PLATES WHERE REQUIRED BY CODE, FOR ADDITIONAL EQUIPMENT, AS DETAILED HEREIN ON THE PLANS, AND AS NOTED IN THE SPECIAL PROVISION
- COLOR CODE ALL PHASE WIRING BY THE USE OF COLORED WIRE INSULATION AND/OR COLORED TAPE, WHERE TAPE IS USED. THE WIRE INSULATION SHALL BE BLACK. BLACK AND RED SHALL BE USED FOR SINGLE-PHASE, THREE WIRE SYSTEMS AND BLACK, RED AND BLUE SHALL BE USED FOR THREE-PHASE SYSTEMS. NEUTRAL CONDUCTORS, SIZE NO. 6 AWG OR SMALLER, SHALL BE IDENTIFIED BY A CONTINUOUS WHITE OR NATURAL GRAY OUTER FINISH ALONG ITS ENTIRE LENGTH. NEUTRAL CONDUCTORS LARGER THAN NO. 6 AWG SHALL BE IDENTIFIED EITHER BY A CONTINUOUS WHITE OR NATURAL GRAY OUTER FINISH ALONG ITS ENTIRE LENGTH OR BY THE USE OF WHITE TAPE AT ITS TERMINATIONS AND INSIDE ACCESSIBLE WIREWAYS. INSULATED GROUND CONDUCTORS SHALL HAVE GREEN COLORED INSULATION FOR ALL CONDUCTOR SIZES (AWG OR KCMIL).
- ALL BRANCH CIRCUIT CONDUCTORS CONNECTED TO A PARTICULAR PHASE SHALL BE IDENTIFIED WITH THE SAME COLOR. THE COLOR CODING SHALL BE EXTENDED
- IN CONTROL WIRING THE SAME COLOR SHALL BE USED THROUGHOUT THE SYSTEM FOR THE SAME FUNCTION, SUCH AS 10%, 30%, 100% BRIGHTNESS CONTROL,
- LOW VOLTAGE (600 V.) AND HIGH VOLTAGE (5000 V.) CONDUCTORS SHALL BE INSTALLED IN SEPARATE WIREWAYS.
- NEATLY LACE WIRING IN DISTRIBUTION PANELS, WIREWAYS, SWITCHES AND JUNCTION/PULL BOXES.
- THE MINIMUM SIZE OF PULL/JUNCTION BOXES, REGARDLESS OF THE QUANTITY AND SIZE OF THE CONDUCTORS SHOWN, SHALL BE AS FOLLOWS:
 - IN STRAIGHT PULLS THE LENGTH OF THE BOX SHALL NOT BE LESS THAN EIGHT TIMES THE TRADE DIAMETER OF THE LARGER CONDUIT. THE TOTAL AREA (INCLUDING THE CONDUIT CROSS-SECTIONAL AREA) OF A BOX END SHALL BE AT LEAST 3 TIMES GREATER THAN THE TOTAL TRADE CROSS-SECTIONAL AREA OF THE CONDUITS TERMINATING AT THE END.
 - IN ANGLE PULLS OR 'U' PULLS THE DISTANCE BETWEEN EACH CONDUIT ENTRY INSIDE THE BOX AND THE OPPOSITE WALL OF THE BOX SHALL NOT BE LESS THAN SIX (6) TIMES THE TRADE DIAMETER OF THE LARGEST CONDUIT. THIS DISTANCE SHALL BE INCREASED FOR ADDITIONAL ENTRIES BY THE AMOUNT OF THE SUM OF THE DIAMETERS OF ALL OTHER CONDUIT ENTRIES ON THE SAME WALL AS THE BOX. THE DISTANCE BETWEEN CONDUIT ENTRIES ENCLOSING THE SAME CONDUCTOR SHALL NOT BE LESS THAN SIX TIMES THE TRADE DIAMETER OF THE LARGEST CONDUIT.
- 8. A RUN OF CONDUIT BETWEEN TERMINATIONS AT EQUIPMENT ENCLOSURES, SQUARE DUCTS AND PULL/JUNCTION BOXES, SHALL NOT CONTAIN MORE THAN THE EQUIVALENT OF FOUR QUARTER BENDS (360 DEGREES TOTAL), INCLUDING THOSE BENDS LOCATED IMMEDIATELY AT THE TERMINATIONS, CAST, CONDUIT TYPE OUTLETS SHALL NOT BE TREATED AS PULL/JUNCTION BOXES.
- EQUIPMENT CABINETS SHALL NOT BE USED AS PULL/JUNCTION BOXES. ONLY WIRING TERMINATING AT THE EQUIPMENT SHALL BE BROUGHT INTO THESE
- SPLICES AND JUNCTION POINTS SHALL BE PERMITTED ONLY IN JUNCTION BOXES. DUCTS EQUIPPED WITH REMOVABLE COVERS, AND AT EASILY ACCESSIBLE
- CIRCUIT BREAKERS IN POWER DISTRIBUTION PANEL(S) SHALL BE THERMAL-MAGNETIC MOLDED CASE, PERMANENT TRÌP WITH 100 AMPERE, MINIMUM
- DUAL LUGS SHALL BE USED WHERE TWO (2) WIRES, SIZE NO. 6 OR LARGER, ARE TO BE CONNECTED TO THE SAME TERMINAL.
- ALL INTERIOR WALL MOUNTED EQUIPMENT ENCLOSURES SHALL BE MOUNTED ON HOT DIPPED CALVANIZED STEEL STRUT SUPPORT, OR STAINLESS STEEL STRUT SUPPORT, WITH CORROSION RESISTANT HARDWARE.
- SUPPORT FOR EXTERIOR MOUNTED EQUIPMENT SHALL USE HOT DIPPED GALVANIZED STEEL STRUT SUPPORT OR STAINLESS STEEL STRUT SUPPORT WITH STAINLESS STEEL HARDWARE. PROVIDE ZINC RICH PAINT APPLIED TO FIELD CUTS OF GALVANIZED STEEL SUPPORT TO MINIMIZE THE POTENTIAL FOR CORROSION PER THE RESPECTIVE STRUT SUPPORT MANUFACTURER'S RECOMMENDATIONS.

CONDUITS FOR ELECTRIC SERVICE ENTRANCE AND FEEDERS SHALL BE AS DETAILED HEREIN ON THE PLANS. WHERE GALVANIZED RIGID STEEL CONDUIT IS SPECIFIED IT SHALL HAVE THREADED FITTINGS. SET SCREW TYPE FITTINGS WILL NOT BE ACCEPTABLE. CONDUITS FOR UNDERGROUND APPLICATIONS SHALL BE AS DETAILED HEREIN. CONDUITS FOR GROUNDING ELECTRODE CONDUCTORS OR INDIVIDUAL GROUNDING CONDUCTORS SHALL BE SCHEDULE 40 OR SCHEDULE 80

- PROVIDE LIQUID TIGHT FLEXIBLE METAL CONDUIT AT CONNECTIONS TO EQUIPMENT SUBJECT TO VIBRATION OR WHERE FLEXIBILITY IS REQUIRED. LIQUID TIGHT FLEXIBLE METAL CONDUIT AND ASSOCIATED FITTINGS SHALL BE U.L. LISTED TO MEET THE REQUIREMENTS OF NEC 350.6, SUITABLE FOR GROUNDING, SUNLIGHT RESISTANT, AND RESISTANT TO OIL, GASOLINE, AND GREASE. LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS USED FOR FLEXIBILITY (INCLUDING CONNECTIONS TO MOTORS, TRANSFORMERS, & CONSTANT CURRENT REGULATORS) SHALL REQUIRE AN EXTERNAL BONDING JUMPER OR INTERNAL EQUIPMENT GROUNDING CONDUCTOR PER NEC 350.60. DO NOT INSTALL LIQUID TIGHT FLEXIBLE METAL CONDUIT THAT IS NOT UL. LISTED.
- UNLESS OTHERWISE SHOWN, ALL EXPOSED CONDUITS SHALL BE RUN PARALLEL TO OR AT RIGHT ANGLES WITH THE LINES OF THE STRUCTURE.
- ALL STEEL CONDUITS, FITTINGS, NUTS, BOLTS, ETC. SHALL BE GALVANIZED.
- USE CONDUIT BUSHINGS AT EACH CONDUIT TERMINATION, WHERE NO. 4 AWG OR LARGER UNDERGROUND WIRE IS INSTALLED, USE INSULATED BUSHINGS.
- 20. USE DOUBLE LOCK NUTS AT EACH CONDUIT TERMINATION.
- WRAP ALL PRIMARY AND SECONDARY POWER TRANSFORMER CONNECTIONS WITH SUFFICIENT LAYERS OF INSULATING TAPE (3M SCOTCH 23 ALL-VOLTAGE SPLICING TAPE, 3M SCOTCH 130C LINERLESS RUBBER SPLICING TAPE, OR APPROVED EQUAL) AND COVER WITH VINYL ELECTRICAL TAPE (3M SCOTCH 88 VINYL ELECTRICAL TAPE OR APPROVED EQUAL) FOR FULL VALUE OF CABLE INSULATION
- UNLESS OTHERWISE NOTED, ALL SINGLE CONDUCTOR CONTROL WIRING SHALL BE NO. 12 AWG, COPPER MINUMUM.
- 23. THE FOLLOWING SHALL APPLY TO RELAY/CONTACTOR PANELS/ENCLOSURES:
 - FOR INTERIOR LOCATIONS ALL COMPONENTS SHALL BE MOUNTED IN NEMA 12 (DUST TIGHT) ENCLOSURE(S) WITH VERTICALLY HINGED COVERS. FOR EXTERIOR/OUTDOOR LOCATIONS ALL COMPONENTS SHALL BE MOUNTED IN NEMA 4X STAINLESS STEEL ENCLOSURE(S) WITH VERTICALLY HINGED COVERS. ALL CONDUIT ENTRIES INTO NEMA 4, 4X ENCLOSURES SHALL HAVE NEMA 4 HUBS LISTED SUITABLE FOR THE RESPECTIVE ENCLOSURE TO MAINTAIN THE NEMA 4, 4X RATING OF THE ENCLOSURE.
 - THE ENCLOSURE(S) SHALL HAVE AMPLE SPACE FOR THE CIRCUIT COMPONENTS, TERMINAL BLOCKS AND INCOMING AND INTERNAL WIRING
 - ALL CONTROL CONDUCTOR TERMINATIONS SHALL BE OF THE OPEN-EYE CONNECTOR/SCREW TYPE. SOLDERED CLOSED-EYE TERMINATIONS, OR TERMINATIONS WITHOUT CONNECTORS ARE NOT ACCEPTABLE.
 - WHEN THE ENCLOSURE COVER IS OPENED, ALL CIRCUIT COMPONENTS WIRING AND TERMINALS SHALL BE EXPOSED AND ACCESSIBLE WITHOUT REMOVAL OF ANY PANELS, COVERS, ETC., EXCEPT THOSE COVERING HIGH
 - ACCESS TO, OR REMOVAL OF A CIRCUIT COMPONENT OR TERMINAL BLOCK WILL NOT REQUIRE THE REMOVAL OF ANY OTHER CIRCUIT COMPONENT OR
 - EACH CIRCUIT COMPONENT SHALL BE CLEARLY IDENTIFIED INDICATING ITS CORRESPONDING NUMBER SHOWN ON THE DRAWINGS AND ITS FUNCTION.
 - A COMPLETE WIRING DIAGRAM SHALL BE MOUNTED ON THE INSIDE OF THE COVER. THE DIAGRAM SHALL REPRESENT EACH CONDUCTOR BY A SEPARATE
 - THE DIAGRAM SHALL IDENTIFY EACH CIRCUIT COMPONENT AN NUMBERING AND COLOR OF EACH TERMINAL CONDUCTOR AND TERMINAL.
 - ALL WIRING SHALL BE NEATLY TRAINED AND LACED.
 - MINIMUM WIRE SIZE SHALL BE NO. 12 AWG.
- FURNISH & INSTALL A WEATHERPROOF WARNING LABEL FOR EACH METER SOCKET, SERVICE DISCONNECT, SAFETY SWITCH, CUTOUT, PANELBOARD, & CONTROL PANEL TO WARN PERSONS OF POTENTIAL ELECTRIC ARC FLASH HAZARDS, PER THE REQUIREMENTS OF NEC 110.16 "FLASH PROTECTION".

KE008

EE MUNI, HENRY

- NO COMPONENTS OF PRIMARY CIRCUIT SUCH AS CABLE, CONNECTORS AND TRANSFORMERS SHALL BE BROUGHT ABOVE GROUND AT EDGE LIGHTS, SIGNS, REIL, PARIL CTC.
- 3. THERE SHALL BE NO EXPOSED POWER/CONTROL CABLES BETWEEN THE POINT WHERE THEY LEAVE THE UNDERGROUND (DEB OR L-867 BASES) AND WHERE THEY ENTER THE EQUIPMENT (SUCH AS TAXIWAY SIGNS, PAPI, REIL, ETC.) ENCLOSURES. THESE CABLES SHALL BE ENCLOSED IN RIGID CONDUIT OR IN FLEXIBLE, WATERTIGHT CONDUIT WITH BREAKABLE COUPLING(S) AT THE GRADE OR THE HOUSING COVER, AS SHOWN IN APPLICABLE DETAILS.
- 4. THE JOINTS OF THE L-823 PRIMARY CONNECTORS SHALL BE WRAPPED WITH AT LEAST ONE LAYER OF RUBBER OR SYNTHETIC RUBBER TAPE AND ONE LAYER OF PLASTIC TAPE, ONE-HALF LAPPED, EXTENDING AT LEAST 1-1/2 INCHES ON EACH SIDE OF THE JOINT, AS SHOWN ON SHEET NO. 25.
- THE CABLE ENTRANCE INTO THE FIELD-ATTACHED L-823 CONNECTORS SHALL BE ENCLOSED BY A HEAT-SHRINKABLE TUBING WITH CONTINUOUS INTERNAL ADHESIVE, AS SHOWN ON SHEET NO. 25.
- L-823 TYPE II, TWO-CONDUCTOR SECONDARY CONNECTORS SHALL BE CLASS 'A' (FACTORY MOLDED).
- THERE SHALL BE NO SPLICES IN THE SECONDARY CABLE(S) WITHIN THE STEMS OF A RUNWAY/TAXIWAY EDGE/THRESHOLD LIGHTING FIXTURE AND THE WIREWAYS LEADING TO TAXIWAY SIGNS AND PAPI/REIL EQUIPMENT.
- ELECTRICAL INSULATING GREASE SHALL BE APPLIED WITHIN THE L-823, SECONDARY, TWO CONDUCTOR CONNECTORS TO PREVENT WATER ENTRANCE. THESE CONNECTORS SHALL NOT BE TAPED.
- DEB ISOLATION TRANSFORMERS SHALL BE BURIED AT A DEPTH OF TEN (10") INCHES
 ON A LINE CROSSING THE LIGHT AND PERPENDICULAR TO THE RUNWAY/TAXIWAY
 CENTERLINE AT A LOCATION TWELVE (12") INCHES FROM THE LIGHT OPPOSITE FROM
 THE RUNWAY/TAXIWAY.
- 10. A SLACK OF THREE (3') FEET, MINIMUM, SHALL BE PROVIDED IN THE PRIMARY CABLE AT EACH TRANSFORMER/CONNECTOR TERMINATION. AT STAKE-MOUNTED LIGHTS, THE SLACK SHALL BE LOOSELY COILED IMMEDIATELY BELOW THE ISOLATION TRANSFORMER.
- 11. DIRECTION OF PRIMARY CABLES SHALL, BE IDENTIFIED BY COLOR CODING AS FOLLOWS: WHEN FACING LIGHT WITH BACK TO PAVEMENT, CABLE TO THE LEFT IS CODED RED AND CABLE TO RIGHT IS CODED BLUE. THIS APPLIES TO STAKE MOUNTED LIGHTS AND BASE MOUNTED LIGHTS WHERE THE BASE HAS ONLY ONE ENTRANCE.
- 12. L-867 BASES SHALL BE SIZE B, 24" DEEP, CLASS I, UNLESS OTHERWISE NOTED.
- 13. BASE MOUNTED BREAKABLE COUPLINGS SHALL NOT HAVE WEEP HOLES TO THE OUTSIDE. PLUGGED UP HOLES SHALL NOT BE ACCEPTABLE. IT SHALL BE A 1/4" DIAMETER, MINIMUM, OR EQUIVALENT OPENING FOR DRAINAGE FROM THE SPACE AROUND THE SECONDARY CONNECTOR INTO THE L-867 BASE.
- 14. THE ELEVATION OF THE BREAKABLE COUPLING GROOVE SHALL NOT EXCEED 1-1/2" ABOVE THE EDGE OF THE COVER IN CASE OF BASE MOUNTED COUPLINGS, OR THE TOP OF THE STAKE IN CASE OF STAKE MOUNTED COUPLINGS.
- 15. WHERE THE BREAKABLE COUPLING IS NOT AN INTEGRAL PART OF THE LIGHT FIXTURE STEM OR MOUNTING LEG, A BEAD OF SILICON SEAL SHALL BE APPLIED COMPLETELY AROUND LIGHT STEM OR WIREWAY AT BREAKABLE COUPLING TO PROVIDE A WATERTIGHT SEAL
- TOPS OF THE STAKES SUPPORTING LIGHT FIXTURES SHALL BE FLUSH WITH THE SURROUNDING GRADE.
- 17. PLASTIC LIGHTING FIXTURE COMPONENTS, SUCH AS LAMP HEADS, STEMS, BREAKABLE COUPLINGS, BASE COVERS, BRACKETS, STAKES, SHALL NOT BE ACCEPTABLE.
- 18. THE TOLERANCE FOR THE HEIGHT OF RUNWAY/TAXIWAY EDGE LIGHTS SHALL BE: ONE (1) INCH. IN CASE OF STAKE MOUNTED LIGHTS, THE SPECIFIED LIGHTING FIXTURE HEIGHT SHALL BE MEASURED BETWEEN THE TOP OF THE STAKE AND THE TOP OF THE LENS. IN CASE OF BASE MOUNTED LIGHTS, THE SPECIFIED LIGHTING FIXTURE HEIGHT SHALL BE MEASURED BETWEEN THE TOP OF THE BASE FLANCE AND THE TOP OF THE LENS, THUS INCLUDING THE BASE COVER, THE FRANGIBLE COUPLING, THE STEM, THE LAMP HOUSING AND THE LENS.

- 19. THE TOLERANCE FOR THE LATERAL SPACING (LIGHT LANE TO RUNWAY/TAXIWAY CENTERLINE) OF RUNWAY/TAXIWAY EDGE LIGHTS SHALL BE ONE (1) INCH. THIS ALSO APPLIES AT INTERSECTIONS TO LATERAL SPACING BETWEEN LIGHTS OF A RUNWAY/TAXIWAY AND THE INTERSECTING RUNWAY/TAXIWAY.
- 20. ENTRANCES INTO L-867 BASES SHALL HAVE CONDUIT COUPLINGS OR REDUCERS TO INTERFACE UNIT DUCT/CONDUIT TO L-867 BASE HUBS, OR SHALL BE SEALED WITH HEAT SHRINK AS SHOWN ON SHEET NO. 25.
- GALVANIZED/PAINTED EQUIPMENT/COMPONENT SURFACES SHALL NOT BE DAMAGED BY DRILLING, FILING, ETC. DRAIN HOLES IN METAL TRANSFORMER HOUSINGS SHALL BE MADE BEFORE CALVANIZING.
- 22. EDGE LIGHT NUMBERING TAGS SHALL BE FACING THE PAVEMENT.
- 23. CABLE/SPLICE/DUCT MARKERS SHALL BE PRECAST CONCRETE OF THE SIZE SHOWN. LETTERS/NUMBERS/ARROWS FOR THE LEGEND TO BE IMPRESSED INTO THE TOPS OF THE MARKERS SHALL BE PRE-ASSEMBLED AND SECURED IN THE MOLD BEFORE THE CONCRETE IS POURED. LEGEND INSCRIBED BY HAND IN WET CONCRETE SHALL NOT BE ACCEPTABLE.
- 24. ALL UNDERGROUND CABLE RUNS SHALL BE IDENTIFIED BY CABLE MARKERS AT 200 FEET MAXIMUM SPACING, WITH AN ADDITIONAL MARKER AT EACH CHANGE OF DIRECTION OF THE CABLE RUN. CABLE MARKERS SHALL BE INSTALLED IMMEDIATELY ABOVE THE CABLES.
- THERE SHALL BE NO SPLICES BETWEEN THE ISOLATION TRANSFORMERS. L-823
 CONNECTORS ARE ALLOWED AT TRANSFORMER CONNECTIONS ONLY, UNLESS OTHERWISE
 SHOWN
- APPLY AN OXIDE INHIBITING, ANTI-SEIZING COMPOUND TO ALL SCREWS, NUTS AND BREAKAGE COUPLING THREADS.
- LOCATIONS OF ENDS OF ALL UNDERGROUND DUCTS SHALL BE IDENTIFIED BY DUCT MARKERS.
- 28. WHERE A PARALLEL, CONSTANT VOLTAGE PAPI SYSTEM IS PROVIDED, THE "T" SPLICES SHALL BE OF THE CAST TYPE.
- CONCRETE USED FOR SLABS, FOOTINGS, BACKFILL AROUND TRANSFORMER HOUSINGS, MARKINGS, ETC. SHALL BE 3000 PSI, AIR-ENTRAINED.
- 30. ALL POWER AND CONTROL CABLES IN MAN/HAND HOLES SHALL BE TAGGED. USE EMBOSSED COPPER STRIPS TO BE ATTACHED AT BOTH ENDS TO THE CABLE BY THE USE OF PLASTIC STRAPS. MINIMUM OF TWO TAGS SHALL BE PROVIDED ON EACH CABLE IN A MAN/HAND HOLE—ONE AT THE CABLE ENTRANCE AND ONE AT THE CABLE
- 31. THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANIES OF HIS OPERATIONAL PLANS AND SHALL OBTAIN FROM THE RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH MAINS AND SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT. CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 1-800-892-0123. ALSO CONTACT AIRPORT MANAGER AND/OR RESPECTIVE AIRPORT PERSONNEL FOR ASSISTANCE IN LOCATING UNDERGROUND AIRPORT CABLES AND/OR UTILITIES. CONTACT FAA FOR ASSISTANCE IN LOCATING THEIR CABLES.
- 32. WHEN PREPARING CABLE FOR SPLICES, THE CONTRACTOR SHALL USE A CABLE STRIPPER/PENCILLER WHENEVER CABLE CONNECTIONS ARE MADE.

GROUNDING NOTES FOR AIRFIELD LIGHTING

GROUNDING FOR RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS SHALL BE AS DETAILED ON THE PLANS AND AS SPECIFIED HEREIN. PER FAA AC 150/5340-30C DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS, CHAPTER 12, PART 12.6; A SAFETY GROUND MUST BE INSTALLED AT EACH LIGHT FIXTURE. THE PURPOSE OF THE SAFETY GROUND IS TO PROTECT PERSONNEL FROM POSSIBLE CONTACT WITH AN ENERGIZED LIGHT BASE OR MOUNTING STAKE AS THE RESULT OF A SHORTED CABLE OR ISOLATION TRANSFORMER. A SAFETY GROUND SHALL BE INSTALLED AT EACH TRANSFORMER BASE/LIGHT CAN ASSOCIATED WITH RUNWAY LIGHTS, TAXIWAY LIGHTS, AND LIGHTED TAXI GUIDANCE SIGNS. A SAFETY GROUND SHALL ALSO BE INSTALLED AT EACH STAKE MOUNTED LIGHT FIXTURE. THE SAFETY GROUND SHALL BE A #6 AWG BARE COPPER CONDUCTOR CONNECTED TO THE GROUND LUG ON THE RESPECTIVE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE AND A 5/8-INCH DIAMETER BY 8-FOOT LONG (MINIMUM) UL LISTED COPPER CLAD GROUND ROD. CONNECTIONS TO GROUND LUGS ON THE L-867 TRANSFORMER BASE/LIGHT CAN OR MOUNTING STAKE SHALL BE WITH A UL LISTED GROUNDING CONNECTION. CONNECTIONS TO GROUND RODS SHALL BE MADE WITH EXOTHERMIC WELD TYPE CONNECTORS, CADWELD BY ERICO PRODUCTS, INC., SOLON, OHIO, (PHONE: 800-248-9353), THERMOWELD BY CONTINENTAL INDUSTRIES, INC., TULSA, OKLAHOMA (PHONE: 918-663-1440) OR ULTRAWELD BY HARGER, GRAYSLAKE, ILLINOIS (PHONE: 800-842-7437). EXOTHERMIC WELD CONNECTIONS SHALL BE INSTALLED IN CONFORMANCE WITH THE RESPECTIVE MANUFACTURER'S DIRECTIONS USING MOLDS AS REQUIRED FOR EACH RESPECTIVE APPLICATION. BOLTED CONNECTIONS WILL NOT BE PERMITTED AT GROUND RODS. TOP OF GROUND RODS SHALL BE BURIED 12 INCHES MINIMUM BELOW GRADE, UNLESS SPECIFIED OTHERWISE HEREIN. FOR RESPECTIVE APPLICATIONS.

- CLEAN ALL METAL SURFACES BEFORE MAKING GROUND CONNECTIONS. METALLIC SURFACES TO BE JOINED SHALL BE PREPARED BY THE REMOVAL OF ALL NON-CONDUCTIVE MATERIAL PER 2008 NATIONAL ELECTRICAL CODE ARTICLE 250-12.
- PER FAA 150/5340-30C THE RESISTANCE TO GROUND OF THE RESPECTIVE MOUNTING STAKE OR LIGHT BASE (WITH GROUND ROD CONNECTED) MUST BE 25 OHMS OR LESS.
- GROUNDING FOR PLASI. GROUNDING FOR PLASI SHALL CONFORM TO THE RESPECTIVE PLASI MANUFACTURER'S INSTALLATION INSTRUCTIONS, AS DETAILED ON THE PLANS, AND AS SPECIFIED HEREIN. THE POWER CIRCUIT TO THE PLASI UNIT SHALL INCLUDE AN EQUIPMENT GROUND WIRE. THE EXISTING POWER FEEDER CIRCUIT IS A 120 VAC, 2-WIRE CIRCUIT WITHOUT AN EQUIPMENT GROUND WIRE. TO COMPLY WITH THE REQUIREMENTS OF NATIONAL ELECTRICAL CODE AND THE PLASI MANUFACTURER'S INSTALLATION INSTRUCTIONS A SAFETY SWITCH/DISCONNECT SHALL BE INSTALLED AT THE PLASI. THE 120 VAC FEEDER CONDUCTORS FROM THE VAULT SHALL TERMINATE ON THIS SAFETY SWITCH/DISCONNECT. FURNISH AND INSTALL A 3/4-INCH DIAMETER BY 10-FOOT LONG COPPER CLAD GROUND ROD AT THE SITE OF THE PLASI UNIT. TOP OF GROUND ROD SHALL BE BURIED 30 INCHES BELOW GRADE. ALL CONNECTIONS TO THE GROUND ROD SHALL BE EXOTHERMIC WELD AS MANUFACTURED BY CADWELD, THERMOWELD, OR ULTRAWELD. CONNECT THE SAFETY SWITCH ENCLOSURE FRAME/GROUND BAR TO THE GROUND ROD WITH A #6 AWG STRANDED COPPER GROUNDING ELECTRODE CONDUCTOR. BOND THE NEUTRAL TO GROUND IN THIS SAFETY WITH A #6 AWG (MINIMUM) STRANDED COPPER BONDING JUMPER. FROM THE LOAD SIDE OF THE SAFETY SWITCH INSTALL 1 #10 THWN, 1 \$10 THWN NEUTRAL, AND 1 \$10 EQUIPMENT GROUND IN 3/4-INCH LIQUID TIGHT FLEXIBLE METAL CONDUIT TO THE PLASI UNIT." TERMINATE THE EQUIPMENT GROUND WIRE ON THE RESPECTIVE GROUND LUG INSIDE THE PLASI UNIT OR ON THE PLASI UNIT METAL FRAME.

KE008

VAUL

CONSTRUCT