

# INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, GENERAL NOTES, STANDARDS
3 - 4	SUMMARY OF QUANTITIES
5 - 6	SCHEDULES OF QUANTITIES
7 - 19	OVERHEAD SIGN STRUCTURE SPAN DETAILS
20 - 22	SIGN DETAILS
23 - 28	SOIL BORINGS

# STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
630001-10	STEEL PLATE BEAM GUARDRAIL
630301-06	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631011-09	TRAFFIC BARRIER TERMINAL, TYPE 2
635001-01	DELINEATORS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
701101-03	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 2' FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701400-06	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-07	LANE CLOSURE, FREEWAY/EXPRESSWAY
701901-02	TRAFFIC CONTROL DEVICES
720021-02	SIGN PANELS, EXTRUDED ALUMINUM TYPE

# GENERAL NOTES

EXISTING STATE-OWNED AND MAINTAINED UTILITY ARE PRESENT AT THE LOCATIONS. THE CONTRACTOR SHALL NOTIFY THE DISTRICT OPERATIONS ENGINEER TWO WEEKS PRIOR TO COMMENCING ANY EXCAVATION IN THE VICINITY OF THESE LINES. THE STATE WILL THEN LOCATE AND MARK THE HORIZONTAL LOCATIONS OF THE LINES AND PROVIDE ANY AVAILABLE INFORMATION AS TO THEIR DEPTH. SHOULD ANY OF THE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATION, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF THE ENGINEER AND AT NO COST TO THE STATE.

ALSO THERE MAY BE UTILITIES PRESENT WHICH WERE INSTALLED BY THE STATE BUT ARE MAINTAINED BY OTHERS (CITY, TOWN, ETC.). THE CONTRACTOR SHALL COORDINATE THE LOCATING OF THESE LINES WITH THE LOCAL AGENCY PRIOR TO COMMENCING ANY EXCAVATION OR BORING IN THEIR VICINITY. SHOULD THESE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATIONS, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF, AND AT NO COST TO, THE LOCAL AGENCY AND THE STATE.

FINAL GRADING SHALL BE DONE BY HAND AROUND ANY NATURAL OR MAN-MADE OBJECTS WHERE SHALLOW FILLS OR CUTS ARE ADJACENT TO THE ITEMS. IT IS THE INTENT THAT THE LIMITS OF CONSTRUCTION BE SUCH AS TO PRESERVE IN THE ORIGINAL STATE AS MUCH AREA OF TEMPORARY EASEMENTS AS POSSIBLE. THE DECISION AS TO ITEMS TO REMAIN IN PLACE SHALL BE AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE CONSIDERED INCLUDED IN THE ASSOCIATED PAY ITEMS FOR SIGN TRUSS REPLACEMENT WITH NO ADDITIONAL COMPENSATION ALLOWED.

9S0441057R042.3 - FULL REPLACEMENT, TYPE I-A  
 9S0641024L037.7 - REPLACE FOUNDATIONS AND END SUPPORTS  
 9S0641024L038.6 - REPLACE FOUNDATIONS  
 9S0911057R029.8 - REPLACE FOUNDATIONS  
 9S1001024L001.1 - FULL REPLACEMENT, TYPE II-A  
 9S1001024L001.5 - FULL REPLACEMENT, TYPE I-A

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX, STANDARDS, GENERAL NOTES	SCALE	SHEET OF SHEETS	STA. TO STA.	*VARIOUS ROUTES
of\pwork\pindot\prtohetll\0334504\	prtohetll	DRAWN	REVISED						F.A.I. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.
	gn structure2013-ah-oludgn	CHECKED	REVISED						* 09 QVD SIN STR REPL13-11 VARIOUS 29 2
	PLOT SCALE = 1/8"=1'-0"	DATE	REVISED						CONTRACT NO. 46227
	PLOT DATE = 2/20/2013								ILLINOIS FED. AID PROJECT