

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				80% FED 20% STATE URBAN	ROADWAY	BRIDGE	BRIDGE	BRIDGE
					0001 URBAN	0008 S. N. 082-0334	0008 S. N. 082-0335	0008 S. N. 082-0314 & S. N. 082-0315
* 25100115	MULCH, METHOD 2	ACRE	12.3	12.3				
* 25100630	EROSION CONTROL BLANKET	SQ YD	32772	32772				
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	34144	34144				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	9060	9060				
28000305	TEMPORARY DITCH CHECKS	FOOT	91	91				
28000400	PERIMETER EROSION BARRIER	FOOT	1,648	1,648				
28000500	INLET AND PIPE PROTECTION	EACH	37	37				
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	134	134				
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	327	327				
28200200	FILTER FABRIC	SQ YD	327	327				
28500100	FABRIC FORMED CONCRETE REVETMENT MAT	SQ YD	60	60				
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	14,834	14,834				
30201500	LIME	TON	445	445				
31001500	LIME	TON	14,656	14,656				

* SPECIALTY ITEM

FILE NAME: P:\MISQ1-08-2012\08212123 1-3 Final Plot	USER NAME: jjoeger Contract: 76848\Draw\DR76848-shr-500.dgn PLOT SCALE: 2.0000 7' = 1"	DESIGNED: JJO DRAWN: JJO CHECKED: PJM DATE: 10/18/12	REVISED: REVISED: REVISED: REVISED:	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES SCALE: SHEET NO. OF SHEETS STA. TO STA.	F.A.P. RTE. 788 SECTION 520-1-2HVB, 520-1-2HVB-1 COUNTY ST. CLAIR TOTAL SHEETS 237 SHEET NO. 4 ILLINOIS FED. AID PROJECT
---	--	---	--	---	--	---