

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY	BRIDGE	BRIDGE	BRIDGE
				0001 URBAN	0008 S. N. 082-0334	0008 S. N. 082-0335	0008 S. N. 082-0314 & S. N. 082-0315
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	982	982			
31200800	STABILIZED SUBBASE - CEMENT AGGREGATE MIXTURE II, 4"	SO YD	9,985	9,985			
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SO YD	1,221	1,221			
40200800	AGGREGATE SURFACE COURSE TYPE B	TON	200	200			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	150	150			
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SO YD	8600	8600			
42001300	PROTECTIVE COAT	SO YD	10,216	10,216			
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	788	788			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	267	267			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	1,489	1,489			
48300505	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/4"	SO YD	4950	4950			
48301000	PROTECTIVE COAT	SO YD	4,950	4,950			
50200100	STRUCTURE EXCAVATION	CU YD	5096		2146	2116	834
50300225	CONCRETE STRUCTURES	CU YD	2492.5		969.4	969.4	553.7

FILE NAME: P:\DOT\08\2010\080124.27 R.I.P. Final.dgn	DESIGNED: JJO	REVISIONS:	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 788	SECTION 520-1-2HVB, 520-1-2HVB-1	COUNTY ST. CLAIR	TOTAL SHEETS 237	SHEET NO. 5
DESIGNED DATE: 10/18/12	CHECKED: PJM	REVISIONS:		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 76848				