

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY	BRIDGE	BRIDGE	BRIDGE
				0001	0008	0008	0008
				URBAN	S. N. 082-0334	S. N. 082-0335	S. N. 082-0314 & S. N. 082-0315
51202305	DRIVING PILES	FOOT	20895		7039	7670	6186
51203200	TEST PILE METAL SHELLS	EACH	8		2	2	4
51203800	TEST PILE STEEL HP14X73	EACH	4		2	2	
51204100	TEST PILE STEEL HP14X117	EACH	4				4
51204650	PILE SHOES	EACH	190		95	95	
51500100	NAME PLATES	EACH	4		1	1	2
52000110	PREFORMED JOINT STRIP SEAL	FOOT	177.2		88.6	88.6	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	20		10	10	
52100510	ANCHOR BOLTS, 3/4"	EACH	40		20	20	
52100520	ANCHOR BOLTS, 1"	EACH	96				96
52100560	ANCHOR BOLTS, 2"	EACH	40		20	20	
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	26	26			
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	67	67			

90% FED
20% STATE
URBAN

FILE NAME -
P:\MS07-08\2010-01\0134.27 IL 3 1 and 81a

USER NAME - j.joyce
CONTRACT - 76848
PLOT SCALE - 3/8"=1'-0"
PLOT DATE - 10/18/2012

DESIGNED - JJO
DRAWN - JJO
CHECKED - PJM
DATE - 10/18/12

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
788	520-1-2HVB, 520-1-2HVB-1	ST. CLAIR	237	7
CONTRACT NO. 76848				

SCALE: SHEET NO. OF SHEETS STA. TO STA.

ILLINOIS FED. AID PROJECT