

SCHEDULE OF EROSION CONTROL													
FROM		TO		AGGREGATE FOR TEMPORARY ACCESS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS	FABRIC FORMED CONCRETE REVETMENT MAT	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	
STA	OFFSET	STA	OFFSET										TON
638+30	LT	643+00	LT		525								
639+00	LT & RT	649+27	LT & RT				11,710	11,936					
639+35	LT & RT				405								
641+50	CL, LT, & RT					2			7				
641+30	RT	647+70	RT										
642+00	CL								7				
643+00	RT	646+00	LT		265								
643+00	CL & RT								14				
644+00	CL								7				
645+00	LT	1644+25	LT										
645+00	CL & RT								14				
645+27	LT					1							
646+00	CL								7				
646+18	RT					1							
647+20	RT								7				
648+31	LT					1							
647+00	CL								7				
648+76	LT									60			
1652+00	LT								7				
1651+79	LT					1							
1652+48	LT					1							
1652+75	LT								7				
1653+75	LT & RT	1677+70	LT & RT				21,062	22,208					
1654+25	RT	1657+30	RT										
1654+36	RT					1							
1655+00	LT	1666+90	LT										
1655+81	LT					1							
1656+00	CL, LT, & RT					3							
1656+16	RT					1							
1656+30	LT								7				
1656+75	LT					1							
1657+26	RT					1							
1657+50	LT	1668+65	LT										
1658+00	RT	1667+00	RT										
1658+49	RT					1							
1661+85	LT					1							
1661+85	RT					1							
1662+15	CL & RT					2							
1662+95	LT					1							
1664+20	RT	1665+95	RT	150									
1664+51	RT					1							
1665+00	LT, RT & CL					3							
1666+00	LT, RT & CL					3							
1666+05	LT					1							
1667+00	CL, LT, & RT					3							
1667+00	LT	1670+00	LT		453								
1667+80						1							
1668+13	CL, LT, & RT					4							
1670+45	LT										250	1	
1677+50	RT										250	1	
1677+50	LT										250	1	
TOTAL				150	1,648	37	32,772	34,144	91	60	750	3	

SCHEDULE OF ROADWAY APPURTENANCES					
STA	OFFSET	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	FURNISHING AND ERECTING DRAINAGE MARKERS	SEALING ABANDONED MONITORING WELLS	BARRICADES, TYPE III
		EACH	EACH	EACH	EACH
643+50.00	150.00' LT	1			
644+61.39	287.32' LT	1			
645+48.40	170.00' RT	1			
645+64.40	431.15' LT	1			
646+19.00	188' LT			1	
646+23.00	170.00' RT	1			
647+15.00	RT				
647+90.00	253' LT			1	
1651+77.00	360' LT			1	
1652+33.28	170.00' RT	1			
1652+94.00	220.00' LT	1			
1653+04.00	RT				
1653+08.51	200.15' RT	1			
1653+23.00	RT				
1654+29.55	195.08' RT	1			
1654+54.58	473.08' LT	1			
1655+01.68	224.76' RT	1			
1655+05.32	220.00' LT	1			
1655+50.00	220.00' LT	1			
1656+78.00	270.00' LT	1			
1657+01.68	223.86' RT	1			
1657+80.00	RT				
1657+78.09	270.00' LT	1			
1658+30.00	169' LT			1	
1658+36.91	209.72' RT	1			
1658+41.46	253.25' RT	1			
1658+61.42	407.35' LT	1			
1659+27.97	480.00' LT	1			
1659+57.00	457.00' LT	1			
1659+68.14	244.98' RT	1			
1660+00.13	272.95' RT	1			
1661+79.73	429.96' RT	1			
1662+69.99	427.00' LT	1			
1662+82.35	195.00' LT	1			
1663+53.00	135' LT			1	
1664+97.62	528.31' RT	1			
1665+28.00	388' RT			1	
1669+33.62	211.97' RT	1			
1669+63.25	211.97' RT	1			
1670+17.10	466.54' RT	1			
1664+97.94	240.45' RT		1		
1664+95.00	210.57' RT		1		
1665+25.00	208.61' RT		1		
1665+27.69	238.50' RT		1		
1667+53.00	124' RT			1	
1670+00.00	LT				8
1670+00.00	RT				6
TOTAL		30	4	7	14



USER NAME = dmeyer
 2705 McGraw Drive
 Bloomington, Illinois 61704
 309/663-8435, 309/663-1571 fax

DESIGNED - JJ0	REVISED - 02/06/13
DRAWN - JJ0	REVISED - 03/15/13
CHECKED - PJM	REVISED -
DATE - 12/10/12	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
788	520-1-2HVB, 520-1-2HVB-1	ST. CLAIR	237	17
CONTRACT NO. 76848				
ILLINOIS FED. AID PROJECT				