



BILL OF MATERIAL
(South MSE Wall)

ITEM	UNIT	TOTAL
Structure Excavation	Cu. Yd.	1930
Concrete Gutter, Type B	Foot	265
Chain Link Fence, 5'	Foot	265
Mechanically Stabilize Earth Retaining Wall	Sq. Ft.	2973
Pipe Underdrains for Structures 4"	Foot	376

See sheet C59 of 76 for crashwall quantities.

Note:
Offsets are measured from centerline of IL-Rte. 3 to front face of crash wall.
Limits of Mechanically Stabilized Earth Retaining Wall are from top of exposed panel line to top of crash wall.
Soil reinforcement and select fill behind crash wall will be included in the cost for the MSE wall.



USER NAME =	DESIGNED - PSS	REVISED -
FILE NAME =	CHECKED - KHH	REVISED -
PLOT SCALE =	DRAWN - AJF	REVISED -
PLOT DATE =	CHECKED - KHH	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SOUTH MSE WALL GENERAL PLAN & ELEVATION
STRUCTURE NO. 082-0334 (N.B.) & 082-0335 (S.B.)

SHEET NO. C54 OF 76 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
788	520-1-2HVB	ST. CLAIR	237	111
			CONTRACT NO. 76848	
ILLINOIS FED. AID PROJECT				