INDEX OF SHEETS

- INDEX OF SHEETS, GENERAL NOTES, & LIST OF STANDARDS
- SUMMARY OF QUANTITIES 3-3A
- SCHEDULE OF QUANTITIES
- TYPICAL CROSS SECTIONS GENERAL PLANS
- DETAIL SHEET
- TRAFFIC CONTROL AND PROTECTION, SPECIAL
- BRIDGE REPAIR PLANS

LIST OF STANDARDS

000001-06

STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS

DECIMAL OF AN INCH AND OF A FOOT

701422-05 LANE CLOSURE, MULTILANE, FOR SPEEDS > 45 MPH TO 55 MPH

701901-02 TRAFFIC CONTROL DEVICES

GENERAL NOTES

- 1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
- 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- 3, PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING STRUCTURE AND ROADWAY HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NORMAL CONSTRUCTION VARIATIONS. IT SHALL BE THE RESPONSIBILTY OF THE CONTRACTOR TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT BID FOR THE WORK.
- 4. IN ADDITION TO TO THE REQUIREMENTS OF ARTICLE 107.16, THE CONTRACTOR SHALL PROTECT THE SURFACE OF THE BRIDGE DECK AND BRIDGE APPROACH PAYEMENT IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 107.16 REGUARDLESS IF TRACK MOUNTED OR WHEELED.
- 5. UTILITY INTERFERENCES ARE NOT ANTICIPATED ON THIS CONTRACT, NO ADDITIONAL COST SHALL BE ADDED TO THE CONTRACT RESULTING FROM ANY UNANTICIPATED UTILITY INTERFERENCE, FOR ADDITIONAL INFORMATION, CONTACT THE JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS (J.U.L.I.E.) SYSTEM AT (800) 892-0123 OR 811.
- 6. THE DEPARTMENT STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTOR TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERAL FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORK FORCE TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION RELATED SKILLS. E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSE WORK (CARPENTRY, CONCRETE FLAT WORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION. TO PREPARE THEM FOR A CAREER IN THEIR HIGHWAY CONSTRUCTION TRADES, GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEYEL CONSTRUCTION WORKERS. CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCPT COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.
- 7. EXISTING PAVEMENT MARKINGS SHALL BE TEMPORARILY COVERED PRIOR TO APPLICATION OF THE DECK SURFACE TREATMENT. TO PREVENT THE SEALER FROM BEING APPLIED TO THE MARKINGS AND TO PROTECT THE REFLECTIVE PROPERTIES OF THE MARKINGS. THE TEMPORARY COVERING MATERIAL USED SHALL BE SUCH THAT IT WILL NOT AFFECT THE MARKING'S REFLECTIVITY WHEN REMOVED AFTER APPLICATION OF THE DECK SURFACE TREATMENT AND PRIOR TO OPENING TO TRAFFIC. THE COST OF THIS WORK SHALL BE INCLUDED IN THE PRICE BID FOR CONCRETE SEALER AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 8. CONTRACTOR MUST PROTECT ALL BRIDGE LIGHTING, UTILITIES, FIXTURES, CONDUITS, ETC. DURING WORK. ANY DAMAGE MUST BE REPORTED TO ENGINEER IMMEDIATELY.
- 9. CONTRACTOR SHALL FIELD VERIFY ALL DECK REPAIR LIMITS WITH ENGINEER PRIOR TO BEGINNING WORK.

COMMITMENTS

1. CONTRACTOR SHALL NOTIFY THE FOLLOWING INDIVIDUALS AT LEAST TWO WEEKS PRIOR TO PROCEEDING WITH THIS WORK:

MISSOURI DEPARTMENT OF TRANSPORTATION 1590 WOODLAKE DRIVE CHESTERFIELD, MO 63017 MR. ED HASSINGER, P.E. DISTRICT ENGINEER 314-275-1500

GREAT RIVERS GREENWAY 6174A DELMAR BOULEVARD ST. LOUIS, MO 63112 MS. SUSAN TRAUTMAN EXECUTIVE DIRECTOR 314-436-7009

METRO EAST PARKS AND RECREATION DISTRICT 104 UNITED DRIVE COLLINSVILLE, IL 62234 MR. MICHAEL BUEHLHORN EXECUTIVE DIRECTOR 618-346-4905

MADISON COUNTY TRANSIT DISTRICT 1 TRANSIT WAY PO BOX 7500 GRANITE CITY, IL 62010 MR. JERRY KANE MANAGING DIRECTOR 618-797-4600

LEAGUE OF ILLINOIS BICYCLISTS 2550 CHESHIRE DRIVE AURORA, IL 60504 MR. ED BARSOTTI EXECUTIVE DIRECTOR 630-978-0583

TRAIL NET 411 NORTH 10TH STREET SUITE 202 ST. LOIUS, MO 63101 MS. ANN RIVERS MACK EXECUTIVE DIRECTOR 314-436-1324 EXT 105

FILE HAME :	user name : •users	DESIGNED -	GEL	REVISED -		INDEX OF SHEETS, GENERAL NOTES, COMMITMENTS &						F.A.P.	SECTION	COUNTY	TOTAL	SHEET
\$F#LEL\$		DRAWN -	LAC	REVISED -	STATE OF ILLINOIS	LIST OF STANDARDS					MILLINICIAL 2 ST	304	1008-105-1	MADISON	58	2
	PLOT SCALE + *SCALE*	CHECKED -	MOP	REVISED -	DEPARTMENT OF TRANSPORTATION									CONTRAC	T NO.	16E73
	PLOY DATE = *DATE*	DATE - 11/16/2012		REVISED -		SCALE	SHEET NO.	OF	SHEETS	STA.	TO STA.		TLL DHOIS FED. A	ID PROJECT		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,