


















**LEGEND**

-  EXISTING HANDHOLE (HHBO-HANDHOLE BY OTHERS)
  -  EXISTING DOUBLE HANDHOLE
  -  EXISTING CONTROLLER
  -  EXISTING SERVICE INSTALLATION
  -  EXISTING GALVANIZED STEEL CONDUIT
  -  EXISTING RADAR DETECTOR
  -  EXISTING CCTV CAMERA
  -  EXISTING ITS CAMERA/DETECTOR POLE
  -  EXISTING FIBER OPTIC CABLE IN CONDUIT
  -  EXISTING JUNCTION BOX
  -  EXISTING SIGN TRUSS
  -  EXISTING HIGHWAY LIGHTING UNIT
  -  EXISTING UNDERGROUND LIGHTING CABLES
  -  PROPOSED HANDHOLE (HH)
  -  PROPOSED FIBER OPTIC CABLE IN CONDUIT
  -  PROPOSED FIBER OPTIC UTILITY MARKER (UM)
  -  PROPOSED GUARD RAIL WARNING PLATE (WP)
- UNDRGRD C CNC 1 1/2 UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/2" DIA.
- CON AT ST 1.5 GS PVC CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., PVC COATED GALVANIZED STEEL
- UNDRGRD C GALVS 1 1/2 UNDERGROUND CONDUIT, GALVANIZED STEEL, 1 1/2" DIA.

**GENERAL NOTES**

1. UNDERGROUND CONDUIT, GALVANIZED STEEL SHALL BE FURNISHED AND INSTALLED TO COMPLETE UNDERGROUND RACEWAY BETWEEN BRIDGE CONDUIT ATTACHED TO STRUCTURE AND ADJACENT HANDHOLE.
  2. COORDINATION WITH THE DEPARTMENT'S BUREAU OF OPERATIONS IS REQUIRED BEFORE ANY TRENCHING SHALL BE DONE TO LOCATE HIGHWAY LIGHTING/PUMP STATION/ITS FACILITIES AND TO COORDINATE OTHER FIELD ACTIVITIES.  
HIGHWAY LIGHTING/PUMP STATIONS: D. WALKER (618-346-3274)  
ITS FACILITIES: L. LEONARD (618-346-3285)
  3. ALL HANDHOLES SHALL BE CONSTRUCTED OF PORTLAND CEMENT CONCRETE PER SECTION 814 OF THE STANDARD SPECIFICATIONS. THE LEGEND ON THE COVER SHALL BE "CMS/IGN". SLOPE HANDHOLE TO MATCH FINAL GRADE ELEVATION.
  4. ALL UTILITIES AND DRAINAGE STRUCTURES SHALL BE LOCATED IN THE FIELD PRIOR TO ANY CONSTRUCTION. THE COST FOR LOCATING DRAINAGE STRUCTURES SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR UNDERGROUND CONDUIT.
  5. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:  
AMEREN ILLINOIS (GAS & ELECTRIC)•  
AT&T ILLINOIS (COMMUNICATIONS)•  
AT&T CORPORATION (COMMUNICATIONS)•  
CENTERPOINT ENERGY (PIPELINE)•  
CHARTER COMMUNICATIONS, INC. (CABLE TV)•  
CITY OF COLLINSVILLE (WATER AND SANITARY SEWER)•  
CONSOLIDATED COMMUNICATIONS, INC. (COMMUNICATIONS)•  
VILLAGE OF GLEN CARBON WATER & SANITARY (SEWER)•  
ILLINOIS AMERICAN WATER COMPANY (WATER)•  
ILLINOIS RURAL HEALTHNET (COMMUNICATIONS)•  
LEVEL 3 COMMUNICATIONS, LLC (COMMUNICATIONS)•  
MADISON COUNTY SPECIAL SERVICE AREA #1 (SANITARY SEWER)•  
MITCHELL PUBLIC WATER DISTRICT (WATER)•  
MCLEOD TELECOMMUNICATIONS SERVICES, LLC (COMMUNICATIONS)•  
SOUTHWESTERN ELECTRIC COOPERATIVE, INC. (ELECTRIC)•
- MEMBER OF J.U.L.I.E. (800-892-0123) OR 811 ARE INDICATED BY "•". NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
6. THE ENGINEER MAY PERMIT ACCESS CONTROL FENCING REMOVAL AND IMMEDIATE REPLACEMENT, TO FACILITATE CONDUIT INSTALLATION. THE PRICE OF ACCESS CONTROL FENCING REMOVAL AND REPLACEMENT SHALL BE INCLUDED IN THE UNIT COST OF ASSOCIATED CONDUIT INSTALLATION WITH NO ADDITIONAL COMPENSATION ALLOWED.
  7. THE DEPARTMENT STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTORS TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORKFORCE AND TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION-RELATED SKILLS, E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSEWORK (CARPENTRY, CONCRETE FLATWORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM FOR A CAREER IN THE HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL-TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS. CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.

**COMMITMENTS**

NONE

•=FAI 270/FAI 255/FAI 55/70

FILE NAME :	USER NAME : prastonne	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES, COMMITMENTS AND LEGEND</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\p\work\p\ridot\prastonne\0279800\076777-hts-ITS.dgn		DRAWN -	REVISED -			•	DIST 8 ITS 2013-1	MADISON	27	2
	PLOT SCALE : 100.0000' / 1" =	CHECKED -	REVISED -		SCALE:	SHEET OF SHEETS		STA.	TO STA.	
	PLOT DATE : 3/21/2013	DATE -	REVISED -				FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	
						CONTRACT NO. 76F77				