F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	100 (1&2) I-9	WILL	59	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
		S0Q-01 OF 01		

URBAN
90% FED./10% STATE

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY SFTY-2A
	35500100	BITUMINOUS BASE COURSE 4"	SQ YD	72,346
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7,365
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	28.0
	40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	947
	44000030	BITUMINOUS SURFACE REMOVAL, (VARIABLE DEPTH)	SQ YD	71,400
	44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	2,170
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	12,299
	44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	14,469
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
	67100100	MOBILIZATION	L SUM	1
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	64,164
	70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	3,308
	70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	1,700
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	25,293
*	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	64,164
*	78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	3,308
*	78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	1,700
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	25,293
	XX002870	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	SQ YD	18,656
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	762.8
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1
	X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	90
	X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	12
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1
⊙	Z0076600	TRAINEES	HOUR	500

⊙ Y080
* SPECIALTY ITEMS

REVISIONS NAME	DATE

PARSONS BRINCKERHOFF

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
US RTE. 30 TO WEBER ROAD

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 03-15-06
DRAWN BY: ALR
CHECKED BY: DM

FINAL