F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	•	COOK	916	15
STA. 190+65 (NB I-57) 1990+48 (NB FORD)		TO STA. 2316+00 (NB RYAN)		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
• (1516.1, 1717, & 1818) R-4			62304	

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	URBAN - 90% FEDERAL, 10% STATE							
					DAN RYAN J000-2A	DAN RYAN I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNING Y002-1C	STRUCTURAL		
										Y007 WALL C	X771-2A SN016-2852	~~SFTY~~-2A SN016-0073
*	E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	712	712							
*	E20220G1	VINE-PARTHENOCISSUS TRICUSPIDATA (BOSTON IVY), 1-GALLON POT	EACH	516	516							
*	K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	11	11							
	X0300057	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	11	7	4						
	X0301424	SILICONE JOINT SEALER	FOOT	1110								1110
⊙	X0320333	ROADWAY CLEANING (SPECIAL)	EACH	28	28							
	X0320870	BRACED EXCAVATION	CU YD	8					8			
	X0321027	DRILLING GROUT HOLES	FOOT	960	960							
	X0321430	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC), SPECIAL	SQ YD	849							849	
*	X0321866	REMOVE, STORE, AND RE-ERECT SIGN PANEL	SQ FT	866					866			
*	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1580	64				1516			
	X0322434	LIGHT TOWER SERVICE PAD, SPECIAL	EACH	1	1							
	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	3360	3360							
*	X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	17	17							
	X0322934	POLYMER CONCRETE	CU YD	3								3
* ⊙	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	58	58							
	X0323830	DRAINAGE SCUPPERS, DS-11	EACH	1							1	
	X0323907	COMMUNICATIONS VAULT	EACH	1				1				
*	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	18060	15745	2315						
*	X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	4516	3937	579						
	X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	12056	12056							
	X0324112	BARRIER BASE	FOOT	22725	21663	1062						
	X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	10237	10237							
*	X0324469	CONDUIT ENCASED, REINFORCED CONCRETE, 2 - 4" DIA., CNC	FOOT	124			124					
*	X0324471	CONDUIT ENCASED, REINFORCED CONCRETE, 4 - 4" DIA., CNC	FOOT	373			373					
*	X0324646	CONDUIT ENCASED, REINFORCED CONCRETE, 6 - 4" DIA., CNC	FOOT	927			927					
	X0324697	SOIL STABILIZERS	POUND	170000	170000							
	X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	147	147							
*	X0324980	CONDUIT ENCASED, REINFORCED CONCRETE, 3 - 4" DIA., CNC AND 1 - 2" DIA., CNC 2 WIDE X 2 HIGH	FOOT	65			65					
	X0325082	CTA BARRIER REMOVAL	FOOT	8152	8152							
*	X0325083	CTA FENCE	FOOT	8295	8295							
*	X0325084	CTA GATES	EACH	11	11							
	X0325088	PLACEMENT OF CEMENT GROUT	CU FT	2400	2400							
	X0325089	CONNECTION TO GROUT HOLE	EACH	64	64							
*	X0325095	MAIN DRAIN CLEANING	FOOT	4809	4809							
	X0325132	SHAPING AND GRADING AT HIGH MAST LIGHT TOWER	SQ YD	23	23							
	X0712400	TEMPORARY PAVEMENT	SQ YD	9634	9634							

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

⊙ - NON-PARTICIPATING

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 8 OF 9

SCALE: NONE DRAWN BY: RTM

DATE: MARCH 7, 2006 CHECKED BY: MPG