

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 100% STATE				STRUCTURAL	
				1-57	LIGHTING	SIGNING	SAFETY	SN016-1251 X271-2A	SN016-1252 X271-2A
				JO00-2A	Y030-1E	Y002-1C	Y032-1F		
50500505	STUD SHEAR CONNECTORS	EACH	42966					33201	9765
50800105	REINFORCEMENT BARS	POUND	380,550	386,030		520			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1012890					715040	297850
50800515	BAR SPLICERS	EACH	938					542	396
51100100	SLOPE WALL 4 INCH	SQ YD	1142	42				1100	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	10,403					12,689	3,774
51202305	DRIVING PILES	FOOT	27,964	11,501				12,689	3,774
51203600	TEST PILE STEEL HP12X53	EACH	6					4	2
51204650	PILE SHOES	EACH	927	448				375	104
51500100	NAME PLATES	EACH	2					1	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	816.0					431.0	385.0
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	93					62	31
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	31					31	
52100520	ANCHOR BOLTS, 1"	EACH	372					248	124
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2					
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2					
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	5	5					
54215547	METAL END SECTIONS 12"	EACH	4	4					
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	17	17					
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	7	7					
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1934	1934					
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	2727	2727					
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	849	849					
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	2426	2426					
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	1220	1220					
550A0600	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	130	130					
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	828	828					
550A0780	STORM SEWERS, CLASS A, TYPE 3 48"	FOOT	395	395					
550A1010	STORM SEWERS, CLASS A, TYPE 4 24"	FOOT	76	76					
550B0320	STORM SEWERS, CLASS B, TYPE 2 8"	FOOT	105	105					
55100500	STORM SEWER REMOVAL 12"	FOOT	640	640					
55100700	STORM SEWER REMOVAL 15"	FOOT	160	160					

TYLIN INTERNATIONAL	USER NAME =	DESIGNED - CAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-57 AT I-294 INTERCHANGE PROJECT SUMMARY OF QUANTITIES			F.A.I. RTE. 57	SECTION 1414.2B	COUNTY COOK	TOTAL SHEETS 516	SHEET NO. 6	
	PLOT SCALE =	CHECKED - JDF	REVISED -		SCALE: NTS	SHEET NO. 3 OF 9 SHEETS	STA.	TO STA.	CONTRACT NO. 60J27				
	PLOT DATE =	DATE - 3/18/2010	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								