

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 100% STATE				STRUCTURAL	
				I-57 J000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	SAFETY Y032-1F	SN016-1251 X271-2A	SN016-1252 X271-2A
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	2654	2654					
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	2892	2892					
78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	3122	3122					
78008220	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 5"	FOOT	781	781					
* 78008240	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	FOOT	3347	3347					
78008250	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	FOOT	1122	1122					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	540	540					
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	46	46					
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	378	378					
* 78100300	REPLACEMENT REFLECTOR	EACH	1049	1049					
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	2520	2520					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	32					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	24,197	24,197					
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	242			242			
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	87			87			
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	1620			1620			
J1013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	870			870			
81025600	CONDUIT ENCASED, REINFORCED CONCRETE, 4" DIA., PVC 2 WIDE X 1 HIGH	FOOT	7764			7764			
81025700	CONDUIT ENCASED, REINFORCED CONCRETE, 4" DIA., PVC 3 WIDE X 1 HIGH	FOOT	1577			1577			
81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	420		420				
81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	20		20				
81101000	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	878			878			
* 81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC COATED GALVANIZED STEEL	FOOT	919		247	672			
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	1232			1232			
81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	7880		284	7596			
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	14		14				
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	1		1				
* 81300555	JUNCTION BOX, STAINLESS STEEL ATTACHED TO STRUCTURE, 12" X 12" X 8"	EACH	4		4				
81304200	JUNCTION BOX EMBEDDED IN STRUCTURE 12" X 12" X 8"	EACH	8			8			
81300810	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 12" X 8"	EACH	3			3			
81400200	HEAVY-DUTY HANDHOLE	EACH	29			29			
* 81400320	UNIT DUCT, 600V, 3-1/C NO. 2, 1/C NO. 4 GROUND (EPR-TYPE RHW), 1 1/2" DIA., POLYETHYLENE	FOOT	3437		3437				
81700335	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C NO. 6	FOOT	2551			2551			
81800330	AERIAL CABLE, 3-1/C NO. 6 WITH MESSENGER WIRE	FOOT	1116			1116			
81800400	AERIAL CABLE, 4-1/C NO. 2 WITH MESSENGER WIRE	FOOT	2482		2482				

*SPECIALTY ITEMS

Rev. 5-27-10

TYLIN INTERNATIONAL	USER NAME =	DESIGNED - CAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-57 AT I-294 INTERCHANGE PROJECT SUMMARY OF QUANTITIES			F.A.I. RTE. 57	SECTION 1414.2B	COUNTY COOK	TOTAL SHEETS 516	SHEET NO. 9
	PLOT SCALE =	CHECKED - JDF	REVISED -		SCALE: NTS	SHEET NO. 6 OF 9 SHEETS	STA. TO STA.	CONTRACT NO. 60J27				
	PLOT DATE =	DATE - 3/18/2010	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							