

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 100% STATE				STRUCTURAL	
				I-57 J000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	SAFETY Y032-1F	SN016-1251 X271-2A	SN016-1252 X271-2A
<del>X7013020</del>	<del>TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS</del>	<del>GAL BA</del>	<del>399</del>	<del>399</del>					
X7040010	TEMPORARY CONCRETE BARRIER (SPECIAL)	FOOT	3790	3790					
X8160370	UNIT DUCT, WITH 3 1/4" NO. 4 AND 1/4" NO. 6 GROUND, 600V (EPR TYPE RHW), 1 1/4" DIA., POLYETHYLENE	FOOT	3242		3242				
X8360360	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 10" X 8"	EACH	2		2				
X8710027	FIBER OPTIC CABLE 4 FIBERS, SINGLE MODE	FOOT	681				681		
X8710035	FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	41443				41,443		
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	14415					4860	9555
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	53,113	53,113					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5			0.3	0.2	
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	10	10					
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	9	9					
Z0018800	DRAINAGE SYSTEM	L SUM	1				0.80	0.20	
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	6	6					
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	13	13					
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	14	14					
<del>Z0076600</del>	<del>TRAINERS</del>	<del>HOURL</del>	<del>0</del>						
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	1064	1064					
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	20,567	20,567					
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2					
60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	4	4					
60224448	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
X0301892	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	28,325	28,325					
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	2	2					
550A5500	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 42"	FOOT	916	916					
X0322441	DIGITAL LOOP DETECTOR SENSOR UNIT (4 CHANNEL)	EACH	1				1		
X0322442	TONE EQUIPMENT - 3 FREQUENCY RECEIVER PROGRAMMABLE	EACH	4				4		
X0322443	TONE EQUIPMENT - 3 FREQUENCY TRANSMITTER PROGRAMMABLE	EACH	4				4		
51201800	FURNISHING STEEL PILES HP 14 X 73	FOOT	11,501	11,501					
51203800	TEST PILE HP 14 X 73	EACH	2	2					

(SQ Cont.)

Code No.	Item Description	Unit	URBAN 100% STATE TOTAL QUANTITY	I-57 J000-2A	Lighting Y030-1E
X78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37,549	37,549	
X78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	10,281	10,281	
X78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4,020	4,020	
X78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,314	2,314	
X0326405	TEMPORARY FENCE (PRAIRIE PROTECTION)	FOOT	6,220	6,220	
X50200400	ROCK EXCAVATION FOR STRUCTURES	CY YD	34		34
X82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	2		2
X82105600	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 400 WATT	EACH	40		40
X83050810	LIGHT POLE, ALUMINUM, 47.5 FT M.H., 15FT. MAST ARM	EACH	2		2
X83504700	LIGHT TOWER, 120 FT. MOUNTING HEIGHT, LUMINAIRE MT-12	EACH	7		7
X83505700	LIGHT TOWER, 130 FT. MOUNTING HEIGHT, LUMINAIRE MT-12	EACH	1		1
X83700250	LIGHT TOWER FOUNDATION, 44" DIAMETER	FOOT	170		170
X83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	30		30
X0322434	LIGHT TOWER, SERVICE PAD, SPECIAL	EACH	8		8
X0325132	SHAPING AND GRADING AT HIGH MAST LIGHT TOWER	SQ YD	170		170
X8357595	LIGHT POLE, WOOD, 100 FT CLASS 4, WITH 15 FT MAST ARM	EACH	8		8
X84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	12		12
X8210015	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, 400 WATT	EACH	8		8

SQ Cont.

\* Specialty Items

REV. 5-27-10

<b>TYLIN INTERNATIONAL</b>	USER NAME =	DESIGNED - CAC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>I-57 AT I-294 INTERCHANGE PROJECT SUMMARY OF QUANTITIES</b>			F.A.I. RTE. 57	SECTION 1414.2B	COUNTY COOK	TOTAL SHEETS 516	SHEET NO. 11A
	PLOT SCALE =	CHECKED - JDF	REVISED -		SCALE: NTS	SHEET NO. 9 OF 9 SHEETS	STA. TO STA.	CONTRACT NO. 60J27				
	PLOT DATE =	DATE - 3/18/2010	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							