

CHAIN LINK FENCE REMOVAL

LOCATION DESCRIPTION	ALIGNMENT	FROM		TO		CHAIN LINK FENCE REM (FOOT)
		STATION	OFFSET	STATION	OFFSET	
I-57	I-57	1245+71.3	151.2 RT	1255+44.5	183.0 RT	974
I-57	I-57	1255+76.3	184.1 RT	1256+89.5	80.5 RT	177
I-57	I-57	1257+53.7	75.4 LT	1257+89.7	167.5 LT	99
I-57	I-57	1260+09.3	81.0 LT	1260+47.6	163.9 LT	91
I-57	I-57	1258+92.9	227.2 RT	1259+42.0	78.24 RT	159
I-57	I-57	1262+08.4	193.9 RT	1265+44.5	177.4 RT	337
TOTAL						1837

GUARDRAIL REMOVAL

LOCATION DESCRIPTION	ALIGNMENT	OFFSET DIRECTION	FROM	TO	GUARDRAIL REM (FOOT)
I-57 MEDIAN SOUTH OF BRIDGE	I-57	LT	1173+28.03	1257+24.44	9399
NB I-57 SOUTH OF BRIDGE OUTSIDE SHOULDER	I-57	RT	1242+70.7	1244+34.3	164
NB I-57 SOUTH OF BRIDGE OUTSIDE SHOULDER	I-57	RT	1252+06.4	1256+88.5	483
SB I-57 SOUTH OF BRIDGE OUTSIDE SHOULDER	I-57	LT	1256+51.6	1257+54.4	103
NB I-57 NORTH OF BRIDGE OUTSIDE SHOULDER	I-57	RT	1259+44.7	1260+58.5	114
I-57 MEDIAN NORTH OF BRIDGE	I-57	LT	1259+75.6	1271+05.2	1143
SB I-57 NORTH OF BRIDGE OUTSIDE SHOULDER	I-57	LT	1259+71.0	1262+40.7	270
I-294 NB (S. Leg)	I-294	RT	404+57.77	405+90.72	107
I-294 NB (N. Leg)	I-294	RT	407+59.85	408+33.65	133
I-294 SB (N. Leg)	I-294	LT	404+29.01	405+26.28	39
I-294 SB (S. Leg)	I-294	LT	406+94.54	407+33.49	97
TOTAL					12051

PAVEMENT MARKING REMOVAL

DESCRIPTION	ALIGNMENT	PAVEMENT MARKING REM (SQ YD)
4" PAVEMENT MARKING REMOVAL *	I-57	13323
5" PAVEMENT MARKING REMOVAL *	I-57	4582
8" PAVEMENT MARKING REMOVAL *	I-57	2243
12" PAVEMENT MARKING REMOVAL *	I-57	3368
TOTAL		23516

REMOVAL OF EXISTING STRUCTURES, LUG SYSTEM

LOCATION DESCRIPTION	ALIGNMENT	OFFSET DIRECTION	FROM	TO	LUG SYS REM (SQ YD)
SB I-57, North of I-294	I-57	LT	1261+06.5	1262+28.5	488
NB I-57, North of I-294	I-57	RT	1261+44.0	1261+94.0	200
TOTAL					689

*PAVEMENT MARKING REMOVAL QUANTITIES MATCH PROPOSED PAVEMENT MARKING QUANTITIES

TREE REMOVAL (6 TO 15 UNITS DIAMETER)

ALIGNMENT	STATION	OFFSET	TREE REMOVAL (6-15) (UNITS)
I-57	1256+82.13	91.41 LT	9.0
I-57	1257+36.93	107.00 LT	10.0
I-57	1257+36.93	107.00 LT	11.0
I-57	1260+37.06	103.28 LT	10.0
I-57	1260+58.40	148.61 LT	7.0
I-57	1260+58.40	148.61 LT	8.0
I-57	1260+58.40	148.61 LT	8.0
I-57	1260+58.40	148.61 LT	9.0
I-57	1260+61.96	97.73 LT	6.0
I-57	1260+67.78	111.30 LT	8.0
I-57	1260+70.59	95.35 LT	13.0
I-57	1261+14.68	157.08 LT	6.0
I-57	1261+26.38	120.94 LT	8.0
I-57	1261+28.52	147.27 LT	6.0
I-57	1261+41.56	146.00 LT	6.0
I-57	1261+48.20	99.63 LT	8.0
I-57	1261+49.31	134.18 LT	7.0
I-57	1262+18.77	156.43 LT	7.0
TOTAL			147.0

TYLIN INTERNATIONAL	USER NAME =	DESIGNED - CAC	REVISED - 4/29/2010	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-57 AT I-294 INTERCHANGE PROJECT		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	DRAWN - CAC	REVISED -		57	1414.2B	COOK	516	28		
	PLOT DATE =	CHECKED - JDF	REVISED -		SCHEDULE OF REMOVAL AND EARTHWORK QUANTITIES		CONTRACT NO. 60J27				
		DATE - 3/18/2010	REVISED -	SCALE: NTS	SHEET NO. 2 OF 2 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				