

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	099-0162 SFTY-2A QUANTITY	
20200100	EARTH EXCAVATION	CU YD	87	87	
20800150	TRENCH BACKFILL	CU YD	11	11	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	509	509	
25000210	SEEDING, CLASS 2A	ACRE	0.11	0.11	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10	
25100630	EROSION CONTROL BLANKET	SQ YD	509	509	
28000400	PERIMETER EROSION BARRIER	FOOT	765	765	
28100211	STONE RIPRAP, CLASS A6	TON	130	130	
28200200	FILTER FABRIC	SQ YD	215	215	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	99	99	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	60	60	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	485	485	
40600990	TEMPORARY RAMP	SQ YD	73	73	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	82	82	
42001300	PROTECTIVE COAT	SQ YD	761	761	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	107	107	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ. FT	150	150	

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	099-0162 SFTY-2A QUANTITY	
44000100	PAVEMENT REMOVAL	SQ YD	169	169	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	249	249	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	648	648	
44000700	APPROACH SLAB REMOVAL	SQ. YD.	214	214	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	4	4	
50200100	STRUCTURE EXCAVATION	CU. YD.	3	3	
50300225	CONCRETE STRUCTURES	CU. YD.	37	37	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	174	174	
50300260	BRIDGE DECK GROOVING	SQ. YD.	178	178	
50400305	PORTLAND CEMENT CONCRETE DECK BEAMS (17" DEPTH)	SQ. FT.	2000	2000	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	46,710	46,710	
50800515	BAR SPLICERS	EACH	256	256	
50900105	ALUMINUM RAILING, TYPE L	FOOT	25	25	
51500100	NAME PLATES	EACH	1	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	79	79	
59000200	EPOXY CRACK INJECTION	FOOT	83	83	
60200405	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 4 FRAME AND GRATE	EACH	2	2	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	93	93	
60235800	INLETS, TYPE A, TYPE 4 FRAME AND GRATE	EACH	2	2	

FILE NAME =
#FILE#



DESIGNED	VEA	REVISED	-
DRAWN	VEA	REVISED	-
CHECKED	TWL	REVISED	-
DATE	4/20/2010	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	11-5-B	COOK	39	3
CONTRACT NO. 60J44				
ILLINOIS FED. AID PROJECT				

Rev.