SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE IC00-2A					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	44	44					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1156	1156					
25200110	SODDING, SALT TOLERANT	SQ YD	1156	1156					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	35	35					
40600300	AGGREGATE (PRIME COAT)	TON	175	175					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	68	68					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	3460	3460					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	222	222					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	250	250					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3794	3794					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3983	3983					
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	45181	45181					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1300	1300					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1486	1486					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	382	382					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	16	16					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	845	845					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	9833	9833					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	7					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50					
60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	6	6					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1973	1973					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	353	353					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	43187	43187					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1684	1684					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	440	440					

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE IC00-2A					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	385	385					
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	353	353					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	43187	43187					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1684	1684					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	440	440					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	385	385					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	570	570					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	570	570					
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	1735	1735					
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103					
	~~X4421000~~	~~PARTIAL DEPTH PATCHING~~	~~TON~~	~~202~~	~~202~~					
	~~X4422030~~	~~PARTIAL DEPTH REMOVAL 3"~~	~~SQ YD~~	~~1200~~	~~1200~~					
NP	Z0018500	DRAINAGE STRUCTURE TO BE CLEANED	EACH	3	3					
	67100100	MOBILIZATION	L SUM	1	1					

*Speci

FILE NAME = c:\pw_work\pwidot\leyso\d0183516\D144110-sht-plan.dgn	USER NAME = leyso	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL. ROUTE 31 (WILDROSE SPRINGS DR. TO HORNE ST.) SUMMARY OF QUANTITIES	F.A.U. RTE. 3887	SECTION 2010-002RS	COUNTY KANE	TOTAL SHEETS 85	SHEET NO. 3
		DRAWN -	REVISED -							
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -		SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 60K15	
	PLOT DATE = 3/17/2010	DATE -	REVISED -							

Rev